



Vickery Extension Project Groundwater Monitoring Report

Quarterly Review November 2024 – January 2025

Whitehaven Coal Ltd

Blue Vale Rd, Boggabri NSW 2382 Australia

Prepared by:

SLR Consulting Australia

SLR Project No.: 640.031099.00001

26 March 2025

Revision: 1.0

Revision Record

Revision	Date	Prepared By	Checked By	Authorised By
1.0	26 March 2025	Joy Xie	Sharon Hulbert	Brian Rask

Basis of Report

This report has been prepared by SLR Consulting Australia (SLR) with all reasonable skill, care and diligence, and taking account of the timescale and resources allocated to it by agreement with Whitehaven Coal Ltd (the Client). Information reported herein is based on the interpretation of data collected, which has been accepted in good faith as being accurate and valid.

This report is for the exclusive use of the Client. No warranties or guarantees are expressed or should be inferred by any third parties. This report may not be relied upon by other parties without written consent from SLR.

SLR disclaims any responsibility to the Client and others in respect of any matters outside the agreed scope of the work.



Table of Contents

Basis of Report	ii
Acronyms and Abbreviations	v
1.0 Introduction	1
1.1 Background	1
1.2 Trigger Action Response Plan	3
1.3 Report Objective.....	3
2.0 Monitoring Results	4
2.1 Climate Data	4
2.2 Groundwater Monitoring Network.....	5
2.3 Data Availability.....	7
2.4 Groundwater Levels	7
2.4.1 Groundwater Level Data Summary.....	7
2.4.2 TARP Trigger Level Summary.....	15
2.5 Groundwater Quality and Exceedance Summary	16
3.0 Action and Response	20
4.0 Recommendations	21
5.0 References	22

Tables in Text

Table 1: Monthly rainfall vs long-term average rainfall	4
Table 2: Groundwater levels in alluvial aquifer.....	7
Table 3: Groundwater levels in Permian aquifer	10
Table 4: Summary of logger data availability	13
Table 5: Summary of TARP triggers	16
Table 6: Summary and status of recommendations to date	21

Figures in Text

Figure 1 On-site monthly rainfall vs long-term average monthly rainfall	4
Figure 2: VCM groundwater monitoring network.....	6
Figure 3: Alluvial bores hydrograph (manual dips, below ground level).....	8
Figure 4 Alluvial groundwater contour map (January 2025)	9
Figure 5: Permian bores hydrograph (manual dips).....	11
Figure 6 Permian aquifer groundwater level contour map (January 2025)	12



Figure 7: Logger hydrograph – VKY042C	15
Figure 8 Alluvial groundwater piper plots	18
Figure 9 Permian groundwater piper plots	19

Appendices

Appendix A	Trigger Action Response Plan
Appendix B	Groundwater Level Results
Appendix C	Groundwater Quality Results
Appendix D	Quality Trigger Level Analysis



Acronyms and Abbreviations

CMA	Corrective Management Actions
EC	Electronic Conductivities
EP&A Act	Environmental Planning and Assessment Act, 1979
GWMP	Groundwater Management Plan
mbgl	meter below ground level
mbtoc	meters below top of casing
pH	potential of Hydrogen
TARP	Trigger Action Response Plan
VCPL	Vickery Coal Pty Ltd
VEP	Vickery Extension Project
WMP	Water Management Plan



1.0 Introduction

1.1 Background

SLR Consulting Australia Pty Ltd (SLR) was engaged by Whitehaven Coal Pty Ltd (Whitehaven) to undertake a review of groundwater data for the Vickery Extension Project (VEP) between 1st November 2024 through 31st January 2025.

The VEP Development Consent (SSD-7480) was granted to Vickery Coal Pty Ltd. (VCPL) on 12 August 2020 by the NSW Independent Planning Commission as a delegate of the NSW Minister for Planning under Section 75J of the NSW Environmental Planning and Assessment Act 1979 (EP&A Act). Approval EPBC 2016/7649 under the Environmental Protection and Biodiversity Conservation Act 1999 (EPBC Act) was granted on 15 September 2021.

Pertinent to the groundwater monitoring and subsequent reporting, is Condition 8 of EPBC 2016/7649, that states:

8. In Addition to the Groundwater Management Plan monitoring requirements specified in condition B53 of the State Development Consent, the approval holder must:

a. Establish and maintain a network of groundwater monitoring bores designed to detect changes in groundwater levels and include bores that are co-located or paired with surface water monitoring sites to allow monitoring and analysis of groundwater – surface water interactions. These monitoring bores must be installed prior to the commencement of mining operations.

b. Monitor groundwater levels in each bore (required under condition 8.a) at least once every 3 months, starting within one week of the commencement of mining operations for the life of this approval.

c. Publish on the website all groundwater monitoring data from the bore network, updated at least once every three months to include the most recent readings available and to maintain the data on the website for the life of this approval. The monitoring data must include hydrographs for the bore network and explain what the data means in relation to the groundwater performance measures specified in the State Development Consent.

This quarterly report has been compiled for Vickery Coal Mine (VCM) to comply with Condition 8(c) of EPBC 2016/7649. Groundwater monitoring commenced in October 2023 aligning with the commencement of mining in October 2023 and in accordance with Condition 8(b). Reporting to date includes:

- 1 Initial Quarterly Report (August 2023 through October 2023), published January 2024.
- 2 2023 Annual Review (1st January 2023 through 31st December 2023), to be published on the website following approval from NSW Department of Planning, Housing and Infrastructure (DPHI).
- 3 Second Quarterly Report (November 2023 through January 2024), published April 2024.
- 4 Third Quarterly Report (February 2024 through April 2024), published July 2024.
- 5 Forth Quarterly Report (May 2024 through July 2024), published October 2024.
- 6 Fifth Quarterly Report (August 2024 through October 2024), published January 2025.



Mining operations continue on site, with coal extraction occurring. Within the reporting period, Whitehaven Coal completed construction of Mine Water Dam 2 (MWD2) and are continuing extraction in the main box cut pit. As production zones gets deeper, there is increased in-pit water, which is a combination of groundwater seepage, direct rainfall collection, water runoff from on-site activities (i.e. dust suppression) and surface runoff. In-pit water is being managed via extraction through sump pumps into water carts for dust suppression and pumping excess water into MWD2. A water fill point is also operational at MWD2 allowing for efficient circulation of water carts for dust suppression across the active haul roads.



1.2 Trigger Action Response Plan

A Trigger Action Response Plan (TARP) was established in the Groundwater Management Plan (GWMP), as a means of providing specific suitable action where exceedances of the groundwater performance criteria are observed. The aim of the TARPs is to evaluate potential adverse changes to existing groundwater sources, confirm if they are due to the development, and provide a means to repair, mitigate and/or offset any adverse groundwater impacts (Whitehaven 2023). The groundwater level and quality TARP for the open cut activities at VEP is shown in **Appendix A**.

The GWMP states the procedure for the review, as follows. The confirmed exceedances will prompt an investigation, carried out by suitably qualified personnel, to assess the reasons for trigger exceedance, which could include but not be limited to climatic conditions, agriculture abstraction, and or mining activities. In the case exceedances are attributed to mining activities, the changes in groundwater conditions, such as a decrease in water level or changes in groundwater quality, will be compared to performance measures (discussed in Section 8.1 of GWMP) to evaluate the significance of any impacts manifested on the groundwater systems.

The results of the trigger investigations will be reported in each annual review. WHC will use the annual review following each reporting period to analyse the data and revise the trigger thresholds in response to additional baseline data as it becomes available. When this occurs the GWMP will be updated.

1.3 Report Objective

This report assesses the VEP groundwater monitoring data against the trigger levels for all required parameters (as per the TARP in the site GWMP) for the reporting period from 1st November 2024 through 31st January 2025.

This report includes:

- A summary of TARP exceedances, if any, during the reporting period;
- A summary of trigger exceedances, if any, over time including the identification of breaches of triggers that remain within normal condition in this reporting period;
- A high-level outline of potential influence factors for exceedances (a detailed analysis of exceedances is not discussed in this report) during the reporting period; and
- Recommendation of relevant actions and responses to be undertaken, in alignment with the TARPs.

The information in this monitoring report will be included in the ongoing quarterly monitoring reports for VEP and summarised in the 2025 Annual Review.



2.0 Monitoring Results

This section summarises the climate information, groundwater monitoring network, and monitoring results available to the conclusion of the reporting period.

2.1 Climate Data

Local climate data was obtained from the Vickery Coal Mine (VCM) (MET2) station, which commenced monitoring in September 2023. In order to understand long-term rainfall trends, the SILO climate record for the location 0.05° x 0.05° tile centred on a location within proximity of VEP (latitude: -30.75, longitude: 150.15) has been utilised (Queensland Government 2024). Comparison of the data sets show analogous trends, indicating the SILO data is a suitable representation of long-term trends.

Rainfall over the past 12 months, in comparison to the long-term average (i.e., January 1900 – present) is shown in **Table 1** and on **Figure 1**. Within the reporting period, MET2 showed slightly lower rainfall compared to long-term average rainfall in November and December 2024, and significantly lower rainfall in January 2025.

Table 1: Monthly rainfall vs long-term average rainfall

Year	2024												2025
Month	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan
SILO 2024-2025 monthly rainfall (mm)	52.6	20.7	17.6	68.6	33.0	70.3	51.1	56.9	42.1	33.6	54.2	58.3	35.8
SILO Long-term average rainfall (mm)	69.4	57.7	46.0	33.2	39.2	40.5	38.6	35.2	37.3	49.0	58.0	60.9	69.4
On-site Rainfall (mm)	29.4	40.8	25.8	101.8	52.8	74.0	43.0	68.2	16.0	54.6	53.1	60.7	12.9




Figure 1 On-site monthly rainfall vs long-term average monthly rainfall




2.2 Groundwater Monitoring Network

Based on the GWMP, the existing groundwater monitoring network consists of 59 monitoring sites, including

- 32 monitoring locations in Alluvial aquifer; and
- 29 monitoring locations in Permian aquifer.
- Two sites (WR1 and WR2) positioned to monitor the potential for seepage from the spoil dump (installed January 2024).
- Two water supply bores (GW971400 and GW971614).

The groundwater network is presented on **Figure 2**, and full details provided in the GWMP (Whitehaven, 2023).





Legend

- | | |
|----------------------------|-------------------------------|
| Alluvial | Proposed Bores |
| Alluvial (data logger) | Northern Borefield (Proposed) |
| Government Monitoring Well | Yr 5 Mining Pit |
| Kurrumbede Bore | Overburden Emplacement |
| Permian | Mining Lease |
| Permian (data logger) | Alluvial |
| Private Bore | |
| Seepage Monitoring Bore | |

Vickery Coal Mine Groundwater Monitoring Locations

Date: Dec 2024
Scale: 1:79,000
Author: A. Quiroz



2.3 Data Availability

In line with the VCM GWMP, the full suite of bores available was monitored during the reporting period.

2.4 Groundwater Levels

Groundwater levels are measured via both manual dip and continuous loggers. The data available since April 2022 is presented in this section, and shown in **Appendix B**.

2.4.1 Groundwater Level Data Summary

A summary of the groundwater level data available to date is presented below.

2.4.1.1 Alluvial Groundwater Bores

The groundwater levels in the alluvial monitoring bores are summarised in **Table 2** and presented in **Figure 3**.

Table 2: Groundwater levels in alluvial aquifer

Sample Location	Depth to Water (mbgl*)								
	Apr-22	Dec-22	May-23	Oct-23	Jan-24	Apr-24	Jul-24	Oct-24	Jan-25
GW01	9.1	8.2	8.4	8.5	9.2	9.5	8.8	9.3	9.0
GW02	-	7.5	8.3	8.5	8.8	9.0	8.8	8.7	8.6
GW-11	-	-	-	16.7	16.6	16.6	14.2	16.6	16.5
GW-14	-	-	-	-	-	-	-	10.9	10.7
GW-15	-	-	-	-	-	-	-	12.7	13.3
GW-2	-	-	-	-	-	19.6	-	18.4	20.5
GW-9	-	-	-	17.8	18.4	17.8	17.8	17.7	17.6
SB01	7.3	6.4	7.2	7.2	7.4	7.9	7.7	7.6	7.3
SB02	10.3	9.8	9.7	9.5	9.7	10.0	9.8	1.4^	9.9
SB04	7.5	6.3	7.6	7.3	7.6	8.2	8.1	7.9	7.9
SB05	8.3	7.1	7.9	7.7	8.1	8.6	8.4	8.2	8.4
SB06	9.8	8.4	8.8	8.9	9.0	9.4	9.2	9.1	9.2
SB07		8.0	8.9	8.8	8.8	9.5	9.5	9.2	9.4
SB08	7.8	6.7	7.6	7.7	7.6	8.1	8.0	7.8	7.8
SB09	7.9	6.4	7.3	7.2	7.5	8.0	7.8	7.7	7.7
SB10	8.1	7.5	8.0	8.2	8.2	8.6	8.5	8.3	8.4
SB11	9.8	8.1	8.7	8.6	9.2	9.5	9.1	9.2	9.4
SB15	9.3	8.2	8.8	9.1	9.6	9.8	9.1	9.5	9.4
VNW223	-	-	-	22.0	21.9	22.1	-	21.5	21.2
VNW394	-	6.7	6.8	6.5	6.5	6.5	6.7	6.9	7.1
VNW395	-	7.4	7.3	7.3	7.3	7.5	6.5	7.6	7.6



Sample Location	Depth to Water (mbgl*)								
	Apr-22	Dec-22	May-23	Oct-23	Jan-24	Apr-24	Jul-24	Oct-24	Jan-25
WR1	-	-	-	-	-	14.6	14.5	14.4	12.0
WR2	-	-	-	-	-	12.1	12.4	12.4	12.0

* mbgl = metres below ground level. ^Reading considered outlier/error.





Figure 3: Alluvial bores hydrograph (manual dips, below ground level)

The groundwater contour map, based on the results from January 2025 monitoring round, is presented in **Figure 4**. These maps will be prepared for all future quarterly reports for ongoing comparison.





WHITEHAVEN COAL PTY LTD
Groundwater Monitoring Locations

Paper size A4
Scale: 1:80,000
 500 0 500 1000 1500 2000 2500 3000
 Metres
 Spatial Reference:
 Name: GDA 1994 MGA Zone 56
 Datum: GDA 1994
 Projection: Transverse Mercator
 Date Exported: 25/07/2023 10:15 AM

Legend

- ▲ Government monitoring wells
- Vickery northern borefield (proposed)
- VEP bore
- ▲ Proposed seepage monitoring locations
- Private bore
- Proposed monitoring location
- ▲ Proposed monitoring location (data logger)
- Permian
- ▲ Alluvial (data logger)
- ▲ Permian (data logger)
- Yr 2 overburden emplacement
- Yr 5 overburden emplacement
- Mine lease
- Yr 5 Mining Pit
- VEP Monitoring locations**
- Geological Unit
- Alluvial
- Geology**
- Alluvial

Figure 4 Alluvial groundwater contour map (January 2025)



2.4.1.2 Permian Groundwater Bores

The groundwater levels in the Permian monitoring bores are summarised in **Table 3**, and presented in **Figure 5**.

Table 3: Groundwater levels in Permian aquifer

Sample Location	Depth to Water (mbgl*)								
	Apr-22	Dec-22	May-23	Oct-23	Jan-24	Apr-24	Jul-24	Oct-24	Jan-25
GW03	-	6.1	6.9	7.2	7.3	7.1	7.5	7.2	6.9
GW-4	-	-	-	-	-	-	-	19.3	19.1
GW-6	-	-	-	-	-	-	-	23.3	23.1
GW-7	-	-	-	27.9	27.8	27.9	28.0	27.8	27.7
GW-8	-	-	-	21.7	21.7	21.6	21.6	21.8	22.1
GW-10	-	-	-	-	-	-	-	17.9	18.6
GW-13	-	-	-	-	-	-	-	23.2	20.1
MD01	-	28.0	27.6	27.7	27.6	28.0	27.6	28.8	29.6
MD02	-	41.0	40.6	40.3	40.0	39.9	39.8	40.6	41.3
TR18	-	13.0	13.4	12.9	13.2	13.3	13.4	13.3	13.1
TR26	-	12.4	12.4	12.2	12.2	12.3	12.4	12.3	12.3
TR35	-	18.2	18.2	18.0	11.2	18.4	18.5	18.4	18.3
TR7	-	9.9	9.9	9.8	9.7	9.8	11.0	9.8	9.7
VKY034C	-	39.8	40.0	39.6	40.3	39.4	40.1	40.3	30.1
VKY035C	-	42.4	42.0	42.0	42.0	41.9	42.6	42.1	42.1
VKY036C	-	49.2	47.2	49.2	49.9	49.5	49.8	49.9	50.3
VKY042C	-	42.7	42.4	42.6	42.8	42.5	42.7	42.8	43.0
VKY043C	-	16.4	15.6	15.7	15.8	15.2	15.7	15.4	16.0
VNW390	-	9.4	9.3	9.4	9.4	9.5	9.5	9.6	9.6
VNW391	-	7.8	7.8	7.8	7.8	7.9	8.0	7.9	8.0
VNW392	-	6.3	6.1	6.2	6.2	6.4	6.5	6.4	6.5
VNW393	-	10.6	10.5	10.5	10.6	10.6	10.7	10.7	10.8

* Metres below ground level







Figure 5: Permian bores hydrograph (manual dips)

The groundwater contour map, based on the results of January 2025 monitoring round, is presented in **Figure 6**. These maps will be prepared for all future quarterly reports for ongoing comparison.





WHITEHAVEN COAL PTY LTD
Groundwater Monitoring Locations

Paper size A4
Scale: 1:80,000
 500 0 500 1000 1500 2000 2500 3000
 Metres
 Spatial Reference
 Name: GDA 1994 MGA Zone 56
 Datum: GDA 1994
 Projection: Transverse Mercator
 Date Exported: 25/07/2023 10:15 AM

Legend

- ▲ Government monitoring wells
- Vickery northern borefield (proposed)
- VEP bore
- ▲ Proposed seepage monitoring locations
- Private bore
- Proposed monitoring location
- ▲ Proposed monitoring location (data logger)
- Permian
- ▲ Alluvial (data logger)
- ▲ Permian (data logger)
- Yr 2 overburden emplacement
- Yr 5 overburden emplacement
- Mine lease
- Yr 5 Mining Pit
- VEP Monitoring locations**
- Geological Unit
- Alluvial

Figure 6 Permian aquifer groundwater level contour map (January 2025)



2.4.1.3 Data Loggers

A summary of the available logger data is presented in **Table 4**. An example of a logger plot is provided in **Figure 7**, with all plots provided in **Appendix B**.

Table 4: Summary of logger data availability

Bore ID	Logger Type	Recording Period	Number of Data Points	Comments
GW01	VWP	10/10/2023 – 13/01/2025	-	Data were not adopted due to significant drifting in logger readings, with generally unrealistic water levels results (i.e., above ground level). Sensor is considered malfunctioned; further investigation required.
GW02	VWP	15/11/2023 – 12/01/2025	-	Data were not adopted due to significant drifting in logger readings, with generally unrealistic water levels results (i.e., above ground level). Sensor is considered malfunctioned; further investigation required.
GW03	VWP (01-10-6743)	17/01/2024 – 18/08/2024; 05/12/2024 – 13/01/2025	3,547	-
GW-9	Logger (Rugged TROLL 100)	24/04/2020 – 16/01/2025	1,339	-
VNW395	Logger (Rugged TROLL 100)	17/01/2024 – 17/04/2024	272	Logger data was not downloaded since the July 2024 monitoring round. A temporary logger has been deployed while searching for a replacement.
TR7	Logger (Rugged TROLL 100)	17/03/2012 – 19/03/2014; 03/06/2020 – 17/04/2024; 25/07/2024 – 12/01/2025	1,985	Logger data was not available for the July 2024 monitoring round. In the January 2025 monitoring round, the logger file was named SB07, which is considered to be a typo, as the historical record matches bore TR7. This needs to be confirmed.
TR18	Logger (Rugged TROLL 100)	16/04/2020 – 04/07/2024	1,939	Logger data was not available in the January 2025 monitoring round
VKY034C	Logger (Rugged TROLL 100)	07/01/2020 – 15/01/2025	6,931	-
VKY035C	Logger (Rugged TROLL 100)	04/11/2020 – 18/10/2024	5,611	Logger data was not available in the January 2025 monitoring round



Bore ID	Logger Type	Recording Period	Number of Data Points	Comments
VKY036C	Logger (Rugged TROLL 100)	07/01/2020 – 15/01/2025	7,625	-
VKY041C (38, 51, 70, 95, 115 m)	VWP (DT2055-02027)	11/03/2015 – 13/01/2025	-	Calibration factors and sensor depths to be confirmed.
VKY041C (140, 170, 199 m)	VWP (DT2055-02023)	11/03/2015 – 13/01/2025	-	Calibration factors and sensor depths to be confirmed.
VKY042C	Logger (Rugged TROLL 100)	04/11/2020 – 15/01/2025	6,019	-
VKY043C	Logger (Rugged TROLL 100)	07/01/2020 – 13/07/2023	5,135	Logger stopped reading in July 23
VKY3053C	VWP	04/03/2020 – 17/01/2024		No data in April 2023. Calibration factors and sensor depths to be confirmed.
VKY33C (38, 51, 70, 95, 115m)	VWP (DT2055-02087)	11/03/2015 – 14/01/2025	-	Calibration factors and sensor depths to be confirmed.
VKY33C (140, 170, 190m)	VWP (DT2055-02029)	11/03/2015 – 14/01/2025	-	Calibration factors and sensor depths to be confirmed.
VS048 (30m)	VWP	17/06/2011 – 15/06/2012; and 04/03/2020 – 13/01/2025	7,349	-
VS054 (23, 96, 120, 167m)	VWP (SN11-1769/1776/1770/1772)	"17/06/2012 – 15/06/2012; and		-
16/11/2023 – 14/01/2025"	~7,916/sensor			-
VS056 (25, 100m)	VWP (SN11-1765/1771)	04/03/2020 – 13/01/2025	VS056-25m: 7,951; VS056-100m: 1,569	
VS058 (18, 88, 159m)	VWP (SN11-1768)	16/04/2020 – 14/01/2025	~6,933/sensor	
VS062	VWP	12/02/2021 – 13/01/2025	10,416	
VS059 (30, 65, 113m)	VWP	16/04/2020 – 13/01/2025	~6,930/sensor	-
WR-1	Logger (Rugged TROLL 100)	30/04/2024 - 14/01/2025	1,035	-






Figure 7: Logger hydrograph – VKY042C

2.4.2 TARP Trigger Level Summary

Groundwater levels in the Alluvial bores have shown minor variation in water levels between October 2024 and January 2025 monitoring rounds. For those bores with more than three water level readings, all are within historical fluctuations.

During the October 2024 monitoring round, SB02 had a groundwater level of 1.38 meters below ground level, representing an 8.4-meter increase from the July 2024 monitoring round. In the current reporting period, the water level measurement is 9.9 meters below ground level, returning to the historical level observed before October 2024. This confirms that the October 2024 result is considered an outlier.

Groundwater levels in the Permian have shown minor increase and decrease across the suite of bores. The water levels in all Permian bores are within the historical level, except for VKY034C. The water level in VKY034C was 30.1 m below ground level, which increased 10.2 m compared to the October 2024 monitoring round. Continuous logger data at VKY034C indicate a slightly decrease of water level during this reporting period, which indicates that the manual measurement at VKY034C in January 2025 monitoring round is an outlier. Ongoing monitoring and review will be undertaken to determine the nature of this increase.

It was noted mining has intersected groundwater during this reporting period, as observed by increased in-pit water. Additionally, a dry period has begun to be recorded. The variation in groundwater levels in both Alluvial and Permian bores does not indicate significant flux of water from the aquifer, resulting in groundwater drawdown. Historically, groundwater levels have typically shown a strong correlation to rainfall trends and any review of trends will need to consider mining operations and climatic conditions.



Given the early status of mining and the stable to increasing groundwater levels, the current groundwater levels are considered to be reflective of natural conditions and not impacted by extraction activities. Additionally, review against the newly derived triggers does not indicate any breach in trigger levels. Therefore, the groundwater levels do not result in the enactment of the TARP.

2.5 Groundwater Quality and Exceedance Summary

Routine groundwater monitoring commenced in October 2023 and continues quarterly. The full January 2025 field and laboratory suite results are summarised in **Appendix C**.

The TARP enacted, as set out in Table 8-3 of the GWMP, during the reporting period are summarised in **Table 5**. **Appendix D** provides a summary of all monitoring rounds to date compared to the interim trigger values or ANZECC default guideline values for slightly to moderately disturbed ecosystems.

Except for the pH result in TR7 and the EC levels in TR7 and GW03, all triggers identified during this reporting period are based on either interim trigger levels or ANZECC default guideline values. These trigger levels were defined using standard guideline values and, consequently, do not necessarily reflect local natural conditions. As per the GWMP, these trigger values will be updated once sufficient baseline data is acquired.

In addition, piper diagrams are used to present the geochemical signature of groundwater. Piper plots will continue to be prepared for both the alluvial and Permian aquifers to compare the geochemical signature over time.

Figure 8 and **Figure 9** show the piper diagrams for the alluvial and Permian groundwater respectively. Where data was available, the July 2024 and January 2025 data has been presented for analysis of trending change in geochemistry across the suite of bores. The piper plots show no trending variation between historical and current geochemical signature.

Review of the individual temporal plots do not indicate consistent increasing or decreasing trends over time, or across multiple locations. Additionally, there is no correlation with groundwater level trends (as groundwater is typically stable). Consequently, the groundwater quality results indicate a 'normal condition' TARP response.

Table 5: Summary of TARP triggers

Bore	Para.	Unit	Trigger Level	Oct-23	Jan-24	Apr-24	Jul-24	Oct-24	Jan-25
TR7	pH	pH unit	7.4-7.8	6.53	7.05	6.71	6.82	6.63	6.51
GW03	EC	µS/cm	811	862	888	862	947	1,004	983
TR18			12,315*	13,400	13,640	12,730	15,350	13,820	13,810
TR35			12,315*	15,300	17,330	16,740	17,260	16,690	18,320
TR-7			12,970	14,800	15,390	14,410	15,380	14,840	15,520
GW-7	SO4 ²⁻	mg/L	86*	364	385	399	380	396	414
SB05			365*	735	551	520	595	496	447
TR18			86*	702	620	592	622	626	630
TR26			86*	194	230	180	198	195	229
TR35			86*	660	651	622	624	624	526



Bore	Para.	Unit	Trigger Level	Oct-23	Jan-24	Apr-24	Jul-24	Oct-24	Jan-25
TR7			365*	508	714	501	518	563	458
VKY034C			86*	123	185	116	98	90	115
VKY036C			86*	244	294	281	100	174	190
VKY042C			86*	302	309	312	283	326	307
VNW392			86*	-	284	296	263	314	300
VNW393			86*	179	185	200	165	202	205
VNW394			365*	-	551	560	574	591	498
TR35				-	0.007	0.01	0.011	0.01	0.008
TR7	Cobalt	mg/L	0.0014	-	0.008	0.004	0.008	0.004	0.005
VNW392				-	0.003	0.003	0.003	0.003	0.002
TR35	Nickel	mg/L	0.011	-	0.713	0.558	0.435	0.308	0.111
TR7				-	0.39	0.118	0.272	0.045	0.024
MD01	Zinc	mg/L	0.008	-	0.31	0.213	0.106	0.049	0.014
TR7				-	0.015	0.03	0.02	0.017	0.009

*Interim water level triggers adopted (as insufficient data has been recorded) based on all data for that geology. Red text shows exceedance of trigger level. Highlighted cell shows trigger level 1 as defined by TARP in the GWMP (Appendix A).






Figure 8 Alluvial groundwater piper plots

* Note: GW-2 water chemistry data are from April 24 and VNW223 from Oct 23






Figure 9 Permian groundwater piper plots



3.0 Action and Response

Based on the results summary presented in **Section 2.0**, the fact that both groundwater level and groundwater quality are considered “Normal Conditions”, there are no specific action and responses required.



4.0 Recommendations

Table 6 provides a summary of the historical recommendations, from Annual and prior quarterly reporting, with a comment on their current status.

Table 6: Summary and status of recommendations to date

Recommendation	Cited	Status
Several monitoring wells were unlocated (GW-2) or inaccessible (GW030051, GW030052, and GW036459) during the reporting period. It is recommended to locate these wells for future monitoring or provide justifications for updating the GWMP.	2023 Annual Review/Quarterly Report	COMPLETE: GW-2 has been monitored in the October 2024 monitoring round. Water level data for GW030051, GW030052, and GW036459 have been obtained from WaterNSW, and therefore continue monitoring in the ongoing events.
Continue the monitoring program and the quarterly reporting on groundwater levels and quality as outlined in the GWMP.	2023 Annual Review	COMPLETE/ONGOING: ongoing monitoring and reporting established.
Review logger data from TR7 and GW01, as appears erroneous, and replace as necessary.	April 2024 Quarterly	ONGOING: Loggers review underway.
Elevation survey of all bores to assist with groundwater level trigger development and plotting of bores as reduced water levels (i.e. as metres below Australian height datum – mAHD).	April 2024 Quarterly	COMPLETE: Elevation survey has been done for all bores. Water level plots have been updated to reflect reduced water levels (as mAHD, refer to Appendix B)
Verify sensor depths for all VWP's in the network to assist with groundwater level calculation (calibration certificates in hand for review and update of database). Revise trigger levels based on updated sensor depth and calibration data. If this calibration data is unavailable, the overall usefulness of these bores to the network will be reviewed as part of the 2024 annual review.	April 2024 Quarterly	ONGOING: Verify sensor depths for VKY033C (or VKY3033C) and VKY041C to assist with groundwater level calculation. COMPLETE: Sensor depths have been verified for all standpipe loggers and VWP's, except for abovementioned VKY033C and VKY041C.
When adequate baseline data becomes available, review and update the quality trigger values.	October 2024	ONGOING: Trigger level review underway.

Recommendations based on the review and analysis completed herein, are as follows:


- Dissolved copper or cadmium were not analysed during the January 2025 monitoring round. It is recommended that the two parameters to be included in the ongoing monitoring rounds.



5.0 References

- Hydrosimulations. 2018. "Vickery Extension Project: Groundwater Assessment. Report ."
- Queensland Government. 2024. *SILO Long Paddock*. <https://www.longpaddock.qld.gov.au/>.
- Whitehaven. 2023. "Vickery Coal Mine Water Management Plan Appendic C Groundwater Management Plan."





Appendix A Trigger Action Response Plan

Vickery Extension Project Groundwater Monitoring Report

Quarterly Review November 2024 – January 2025

Whitehaven Coal Ltd

SLR Project No.: 640.031099.00001

26 March 2025

Table A-1: Tigger Action Response Plan

PERFORMANCE MEASURE AND INDICATOR, TARP OBJECTIVE AND ASSESSMENT CRITERIA	MONITORING PROGRAM	MANAGEMENT		
		TRIGGER	ACTION	RESPONSE
<p>Performance Measure Feature Negligible groundwater level impact on the Namoi Alluvium aquifer and associated surface watercourses, groundwater dependent ecosystems, and private landowner bores.</p> <p>Negligible groundwater level impact on the Permian bedrock and associated private landowner bores, outside that predicted by the approved groundwater impacts (Hydrosimulations 2018).</p> <p>TARP Objective This TARP defines levels of deviation in groundwater level from 'normal' conditions and the actions to be implemented in response to each level deviation as a result of open cut mining.</p> <p>Assessment Criteria Bore specific trigger values are based on the water levels across the entire history of monitoring in each individual bore and the predicted impacts from the Hydrosimulations (2018) numerical groundwater model.</p>	<p>Locations Open standpipes and VWPs All monitoring locations as set out in Table 4-1 of the Groundwater Management Plan (GWMP).</p> <p>All monitoring locations are shown in Figure 4-1 of the GWMP.</p> <p>Monitoring Frequency During mining Quarterly manual measurements of water level. Continuous monitoring in bores installed with Vibrating Wire Piezometers (VWPs).</p> <p>Post-mining TBC</p>	Normal Condition		
		<ul style="list-style-type: none"> Groundwater level remains above the respective trigger limits (defined as the 95th percentile over the baseline period and detailed in Table 8-2 of the GWMP) for each individual groundwater bore. 	<ul style="list-style-type: none"> Continue monitoring and review of data as per monitoring program. 	<ul style="list-style-type: none"> No response required.
		Level 1		
		<ul style="list-style-type: none"> One quarterly monitoring result shows an exceedance of the trigger limit as detailed in Table 8-2 of the GWMP. 	<ul style="list-style-type: none"> Actions as required for Normal Condition. Re-sample of groundwater level within seven days. 	<ul style="list-style-type: none"> Report declines and climate investigation outcomes in Annual Review.
		Level 2		
<ul style="list-style-type: none"> Groundwater level in a groundwater bore exceeds the respective trigger limit during three consecutive quarterly monitoring rounds. <p>OR</p> <ul style="list-style-type: none"> Complaint received by landowners of private bores regarding groundwater level declines. 	<ul style="list-style-type: none"> Actions as stated in Level 1. <p>For Open Standpipe Monitoring Bores, VWPs, and Private Bores:</p> <ul style="list-style-type: none"> Undertake a preliminary hydrogeological investigation as efficiently as practicable to check and validate the data and assess cause of trigger exceedances to determine if mining related as per the requirements set out in Section 8.3 of the GWMP. Review of groundwater levels to be carried out by qualified personnel. Increase monitoring and review of data frequency for sites where Level 2 has been reached, subject to land access. <p>For Private Bores:</p> <ul style="list-style-type: none"> Undertake investigation to demonstrate if the decline will impact the long-term viability of the affected water supply works. Commence level monitoring of said private bore in quarterly monitoring rounds, subject to negotiation and land access restrictions. <p>The investigation will be commenced/ completed as efficiently as practicable.</p>	<ul style="list-style-type: none"> Responses as stated in Level 1. Include outcomes from the preliminary investigation report in Annual Review. 		
Level 3				



PERFORMANCE MEASURE AND INDICATOR, TARP OBJECTIVE AND ASSESSMENT CRITERIA	MONITORING PROGRAM	MANAGEMENT		
		TRIGGER	ACTION	RESPONSE
		<ul style="list-style-type: none"> The reduction in water level is determined in the Level 2 preliminary investigation not to be controlled by climatic or external anthropogenic factors. <p>OR</p> <ul style="list-style-type: none"> Groundwater level in a groundwater bore continues to exceed the respective trigger limit during six consecutive monitoring rounds. 	<ul style="list-style-type: none"> Actions as stated in Level 2. <p>For Open Standpipe Monitoring Bores, VWPs, and Private Bores:</p> <ul style="list-style-type: none"> Undertake a detailed investigation to assess if the change in behaviour is related to mining effects (e.g., catchment changes, another effect unrelated to mining). Review groundwater model. <p>For Private Bores:</p> <ul style="list-style-type: none"> Review corrective management actions (CMAs) as specified in Section 8.3 of the GWMP considering findings from further investigations and consider additional reasonable and feasible options. 	<ul style="list-style-type: none"> Responses as stated in Level 2. Report trigger exceedance to DPE and key stakeholders. Provide the detailed investigation report to relevant agencies within a reasonable timeframe of identifying the non-compliance. Report trigger exceedance and investigation outcomes in Annual Review. Develop/design contingency and remedial measures based on the results of the above investigations. Contingency and remedial measures considered practical for implementation may include: <ul style="list-style-type: none"> 7 Undertake landholder and government consultation; 8 Offset groundwater leakage from the Namoi Alluvium aquifer; 9 Review and refine the GWMP including undertaking additional 10 specific monitoring of private landholder bores; 11 Review Site Water Balance and predictive groundwater model; and 12 Review mine plan impacts on alluvial groundwater source. <p>For Private Bores:</p> <ul style="list-style-type: none"> Provide DPE and key stakeholders with proposed corrective management actions (CMAs) for consultation (e.g., extending the depth of the bore, establishment of additional bores, compensation to affected landowners as per Section 8.3 of the GWMP). Implement CMAs, subject to land access (finalise negotiations and implement the agreed "make-good" arrangements). Monitor and report on success of CMAs in Annual Review.
<p>Performance Measure Feature</p> <p>Negligible quality impact on the Namoi Alluvium aquifer and associated surface watercourses and private landholder bores.</p> <p>Negligible quality impact on the Permian bedrock and associated private landowner bores, outside that predicted by the approved groundwater (Hydrosimulations 2018).</p> <p>TARP Objective</p> <p>This TARP defines levels of deviation in groundwater quality from baseline conditions and the actions to be implemented in response to each level deviation.</p> <p>Assessment Criteria</p> <p>Quality in each monitoring bore remains within the 5th and 95th percentile of the baseline conditions set out in Table 8-4 of the GWMP for the following parameters:</p> <ul style="list-style-type: none"> Electrical Conductivity; pH; and Sulfate. <p>Other major and metal ions will be assessed against the relevant ANZECC guidelines.</p>	<p>Locations</p> <p>Open standpipes</p> <p>All open standpipe monitoring locations as set out in Table 4-2 of the GWMP.</p> <p>Monitoring Frequency</p> <p>During mining</p> <p>Six-monthly measurements of pH and electrical conductivity parameters.</p> <p>Other parameters (detailed in Table 4-2 of the GWMP) to be measured on an annual basis.</p> <p>Post-mining</p> <p>TBC</p>	<p>Normal Condition</p>		
		<ul style="list-style-type: none"> Groundwater pH remains within the baseline 5th and 95th percentile range, as specified in the GWMP. Other groundwater quality parameters remain below the baseline 95th percentile, as specified in the GWMP. 	<ul style="list-style-type: none"> Continue monitoring and review of data as per monitoring program. 	<ul style="list-style-type: none"> No response required.
		<p>Level 1</p>		
		<ul style="list-style-type: none"> Two six-monthly exceedances or one annual quality exceedances outside of the specified baseline range (pH) or above 95th percentile baseline (other quality parameters). 	<ul style="list-style-type: none"> Actions as required for Normal Condition. Re-sample of groundwater quality within seven days 	<ul style="list-style-type: none"> Report declines and climate investigation outcomes in Annual Review.
		<p>Level 2</p>		
<ul style="list-style-type: none"> Three consecutive six-monthly exceedances or two annual quality exceedances (including re-samples from Level 1) outside of the specified baseline range (pH) or above 95th percentile baseline (other quality parameters). <p>OR</p> <ul style="list-style-type: none"> Complaint received by landowners of private bores regarding groundwater quality declines. 	<ul style="list-style-type: none"> Actions as stated in Level 1. <p>For Open Standpipe Monitoring Bores:</p> <ul style="list-style-type: none"> Undertake a preliminary hydrogeological investigation as efficiently as practicable to assess cause of quality exceedances and determine if mining related as per the requirements set out in Section 8.3 of the GWMP. Review of groundwater quality to be carried out by qualified personnel. Increase monitoring and review of data frequency for sites where Level 2 has been reached, subject to land access. <p>For Private Bores:</p> <ul style="list-style-type: none"> Collect quality sample from said private bore for comparison with wider aquifer data, subject to negotiation and land access restrictions. Undertake investigation to demonstrate if quality will impact the long-term viability of the affected water supply works. <p>The investigation will be commenced/ completed as efficiently as practicable.</p>	<ul style="list-style-type: none"> Responses as stated in Level 1. Include outcomes from the preliminary investigation report in Annual Review. 		



PERFORMANCE MEASURE AND INDICATOR, TARP OBJECTIVE AND ASSESSMENT CRITERIA	MONITORING PROGRAM	MANAGEMENT		
		TRIGGER	ACTION	RESPONSE
		Level 3		
		<ul style="list-style-type: none"> The water quality changes are determined from Level 2 preliminary investigation to not be controlled by climatic, local land uses, or other external anthropogenic factors. <p>OR</p> <ul style="list-style-type: none"> Groundwater quality continues to decline with six consecutive six-monthly exceedances or three annual quality exceedances outside of the specified baseline range (pH) or above 95th percentile baseline (other quality parameters). <p>AND</p> <ul style="list-style-type: none"> Quality exceedances are widespread (three or more bores in an aquifer show water quality exceedances) across the aquifers being monitored. 	<ul style="list-style-type: none"> Actions as stated in Level 2. <p>For Private Bores and Open Standpipe Monitoring Bores</p> <ul style="list-style-type: none"> Increase monitoring to at least quarterly measurements for sites where Level 3 has been reached, subject to land access. Undertake a detailed investigation to assess if the change in behaviour is related to mining effects (e.g., catchment changes, another effect unrelated to mining). Review corrective management actions (CMAs) as specified in Section 8.3 of the WMP considering findings from further investigations and consider additional reasonable and feasible options. 	<ul style="list-style-type: none"> Responses as stated in Level 2. <p>For Private Bores and Open Standpipe Monitoring Bores:</p> <ul style="list-style-type: none"> Report trigger exceedance to DPE and key stakeholders. Report trigger exceedance and investigation outcomes in Annual Review. <p>For Private Bores, if the changes have been confirmed to be related to mining effects:</p> <ul style="list-style-type: none"> Initiate negotiations with impacts landowners as soon as practicable. Consider all reasonable and feasible options for remediation as relevant (e.g., isolation, remediation, etc.). Provide DPE and key stakeholders with proposed corrective management actions (CMAs) for consultation (e.g., extending the depth of the bore, establishment of additional bores, compensation to affected landowners as per Section 10.2.2 of the WMP). Implement CMAs, subject to land access (finalise negotiations and implement the agreed "make-good" arrangements). Monitor and report on success of CMAs in Annual Review.





Appendix B Groundwater Level Results







Vickery Extension Project Groundwater Monitoring Report







Quarterly Review November 2024 – January 2025







Whitehaven Coal Ltd







SLR Project No.: 640.031099.00001







26 March 2025




















































Appendix C Groundwater Quality Results

Vickery Extension Project Groundwater Monitoring Report

Quarterly Review November 2024 – January 2025

Whitehaven Coal Ltd

SLR Project No.: 640.031099.00001

26 March 2025

Table C-1: Field GW Monitoring Data

Sample Location	Date	pH - Field	EC - Field (µS)	Temperature	Redox	Odour	Appearance	Colour	Comments
SB02	24-10-2023 10:40	7.21	7250	24.1	44	Nil	Slightly turbid	Orange	Quarterly sampling
GW01	24-10-2023 9:36	7.33	1042	22.4	79	Nil	Clear	Colourless	Quarterly sampling
SB15	24-10-2023 10:10	7.29	1019	22.6	59	Nil	Clear	Colourless	Quarterly sampling
SB06	24-10-2023 7:35	7.35	3280	20.6	41	Nil	Clear	Colourless	Quarterly sampling
SB11	24-10-2023 8:25	7.26	1080	22.6	46	Nil	Clear	Colourless	Quarterly sampling
SB10	23-10-2023 15:55	7.43	1880	24.3	34	Nil	Clear	Colourless	Quarterly sampling; small amount of sediment in water
SB05	23-10-2023 16:20	2.09	3740	25	43	Nil	Clear	Colourless	Quarterly sampling
SB09	23-10-2023 15:20	3.32	949	27.3	28	Nil	Slightly turbid	Orange/brown	Quarterly sampling; a lot of sediment in water, possible rust particles
SB01	23-10-2023 15:00	7.44	1541	26.5	36	Nil	Clear	Colourless	Quarterly sampling
SB04	23-10-2023 13:19	7.29	2680	28.2	47	Slight	Slightly turbid	Grey	Quarterly sampling; bailed due to depth; Standpipe extremely unstable; too shallow to hydrasleeve so bailed to test.
SB08	23-10-2023 13:35	7.24	983	26.3	41	Nil	Clear	Colourless	Quarterly sampling
SB07	23-10-2023 11:47	7.35	770	23.2	46	Nil	Clear	Colourless	Quarterly sampling
GW02	23-10-2023 10:51	7.59	731	25.2	25	Nil	Clear	Colourless	Quarterly sampling
MD01	25-10-2023 9:50	11.58	1799	25.6	-91	Slight	Clear	Colourless	Quarterly sampling; Slight unknown odour. No cap on bore;
MD02	25-10-2023 11:10	6.84	1195	27.4	-69	Nil	Clear	Colourless	Quarterly sampling
GW03	23-10-2023 14:14	7.19	862	25.9	21	Nil	Clear	Colourless	Quarterly sampling; fence panels down and logger missing (assume down the bore).
TR26	25-10-2023 12:00	7.06	6290	26.3	52	Nil	Clear	Colourless	Quarterly sampling
TR7	25-10-2023 12:25	6.53	####	26.4	61	Nil	Clear	Colourless	Quarterly sampling
TR18	25-10-2023 13:30	6.58	####	27.8	99	Nil	Clear	Colourless	Quarterly sampling
TR35	25-10-2023 14:10	6.66	####	25.5	-55	Slight	Clear	Colourless	Quarterly sampling
VKY043C	26-10-2023 8:25	7.72	2990	20	-32	Nil	Clear	Colourless	Quarterly sampling
VKY042C	26-10-2023 11:45	6.75	5420	28.1	-28	Nil	Clear	Colourless	Quarterly sampling; Unable to determine total bore depth as it was greater than 150m (length of the dip tape)
VKY035C	26-10-2023 10:40	7.1	3110	25.5	-26	Nil	Clear	Colourless	Quarterly sampling
VKY034C	26-10-2023 9:15	7.3	3590	23.4	70	Nil	Clear	Colourless	Quarterly sampling
VKY036C	26-10-2023 12:40	7.08	5600	25.1	-39	Nil	Clear	Colourless	Quarterly sampling
VNW390	24-10-2023 12:35	6.92	2300	22.6	-96	Moderate	Clear	Colourless	Quarterly sampling; Sulphur odour
VNW391	24-10-2023 14:20	7.04	2530	23.9	-60	Nil	Clear	Colourless	Quarterly sampling
VNW392	22-11-2023 13:58	6.74	3690	20.8	-96	Slight	Clear	Colourless	Quarterly sampling; No access - locked out on 24/10/2023; Sampled 22/11/2023; Slight H2S odour
VNW393	24-10-2023 13:05	7.36	2740	22.1	26	Slight	Clear	Colourless	Quarterly sampling; Slight sulphur odour
VNW394	22-11-2023 13:12	7.13	5520	12.8	-70	Nil	Slight	Grey	Quarterly sampling;
VNW395	24-10-2023 13:41	7.47	463	20.9	57	Slight	Clear	Colourless	Quarterly sampling; no logger
GW-8	22-11-2023 15:47	7.11	4290	22.5	-176	Nil	Slight	Brown	Quarterly sampling; Unable to locate on 27/10/2023; Sampled 22/11/2023
GW-7	27-10-2023 11:50	8.89	4300	22.7	60	Nil	Clear	Colourless	Quarterly sampling; Suspended matter in water
VNW223	27-10-2023 10:10	7.25	5940	19.9	49	Nil	Clear	Colourless	
GW-11	27-10-2023 9:40	7.36	4360	21.5	-111	Nil	Clear	Colourless	Quarterly sampling; old windmill overhead
GW-9	27-10-2023 12:55	7.94	6110	22.6	-87	Nil	Clear	Brown	Quarterly sampling; old windmill overhead
VKY GW Duplicate 1	24-10-2023 8:25	7.26	1081	22.6	46	Nil	Clear	Colourless	Quarterly sampling; site duplicate taken from SB11
VKY GW Duplicate 2	26-10-2023 8:25	7.71	2990	20.1	-32	Nil	Clear	Colourless	Quarterly sampling; site duplicate taken from VKY0043C
VKY GW Lab Split Dup 1	24-10-2023 8:25	7.27	1080	22.7	47	Nil	Clear	Colourless	Quarterly sampling; site split duplicate taken from SB11
VKY GW Lab Split Dup 2	26-10-2023 8:25	7.71	2990	20	-33	Nil	Clear	Colourless	Quarterly sampling; site split duplicate taken from VKY0043C

Sample Location	Date	pH - Field	EC - Field (µS)	Temperature	Redox	Odour	Appearance	Colour	Comments
VKY GW Blank	24-10-2023 7:35	8.77	13	15.4	70	Nil	Clear	Colourless	Quarterly sampling; blank
SB02	25-10-2023 12:25	7.28	7330	22.5	Clear	Nil	Slightly turbid	Orange	-
GW01	23-01-2024 7:39	7.2	1265	19.6	-15.7	Nil	Clear	Colourless	-
SB15	23-01-2024 8:05	7.23	1070	21.1	-88	Nil	Clear	Colourless	-
SB06	17-01-2024 12:55	7.61	3460	26.5	-84	Nil	Turbid	Brown	-
SB11	17-01-2024 13:26	7.7	1021	26.4	-62	Nil	Clear	Colourless	-
SB10	17-01-2024 13:49	7.47	1972	29.7	-69	Nil	Clear	Colourless	-
SB05	17-01-2024 14:31	7.73	3690	28	-131	Nil	Clear	Colourless	-
SB09	17-01-2024 15:18	7.56	1014	26.1	-70	Nil	Slightly turbid	Black	-
SB01	17-01-2024 14:58	7.31	1716	28.3	-70	Nil	Clear	Colourless	-
SB04	17-01-2024 15:51	7.43	3360	24.6	-188	Slightly	Clear	Colourless	Slight H2S odour
SB08	18-01-2024 16:09	7.39	1115	23.4	-119	Nil	Clear	Colourless	-
SB07	17-01-2024 16:32	7.47	919	24.5	-87	Nil	Clear	Colourless	-
GW02	18-01-2024 10:54	7.79	971	23.9	-74	Nil	Clear	Colourless	-
MD01	18-01-2024 9:10	11.69	1786	22.9	-135	Nil	Slightly turbid	Brown	-
MD02	23-01-2024 10:29	6.78	1306	24.3	-140	Nil	Clear	Colourless	-
GW03	23-01-2024 6:59	7.16	888	19.6	66	Nil	Clear	Colourless	-
TR26	18-01-2024 13:35	7.16	8380	24.8	-62	Nil	Slightly turbid	Brown	-
TR7	18-01-2024 13:55	7.05	1539	25.2	-30	Nil	Slightly turbid	Brown	-
TR18	18-01-2024 14:28	6.85	1364	24.5	-21	Nil	Slightly turbid	Brown	-
TR35	18-01-2024 15:25	6.75	1733	24	-63	Nil	Clear	Colourless	-
VKY043C	18-01-2024 14:58	7.8	3410	24.1	-74	Nil	Clear	Colourless	-
VKY042C	23-01-2024 12:58	6.72	5430	31	-119	Nil	Clear	Colourless	-
VKY035C	23-01-2024 12:14	7.01	3340	27.2	-170	Nil	Clear	Colourless	-
VKY034C	23-01-2024 11:05	6.94	3850	29.4	-149	Nil	Slightly turbid	Brown	-
VKY036C	23-01-2024 11:35	6.79	5810	28.7	-139	Nil	Clear	Colourless	-
VNW390	17-01-2024 11:23	7.13	2376	24.3	-69	Nil	Clear	Colourless	-
VNW391	17-01-2024 11:52	7.31	2471	23.1	-109	Nil	Clear	Colourless	-
VNW392	17-01-2024 12:22	6.74	3310	26.1	-149	Nil	Clear	Grey	-
VNW393	17-01-2024 10:51	7.56	2830	29.5	-90	Slightly	Clear	Colourless	Very slight H2S odour
VNW394	17-01-2024 9:30	6.92	5410	23.9	-104	Nil	Slightly turbid	Grey	-
VNW395	17-01-2024 11:39	7.77	1395	27	-168	Nil	Clear	Grey	-
GW-8	24-01-2024 13:55	7.03	3950	26.5	-208	Nil	Clear	Black	-
GW-7	23-01-2024 9:12	8.82	4490	23	-64	Nil	Clear	Colourless	Site overgrown and dangerous - Need cleaning up
VNW223	24-01-2024	-	-	-	-	-	-	-	Blocked at 1.3 mbtoc
GW-11	23-01-2024 14:26	6.93	4340	30.6	-192	Nil	Slightly turbid	Orange	-
GW-9	23-01-2024 13:49	6.68	3320	24.2	-196	Nil	Slightly turbid	Brown	No logger
GW030051	-	-	-	-	-	-	-	-	No access - NSWWater locked bore
GW030052	-	-	-	-	-	-	-	-	No access - NSWWater locked bore
GW-2	-	-	-	-	-	-	-	-	Unable to locate
VKY GW Duplicate 1 - MD01	18-01-2024 9:38	11.54	1848	22.9	-147	Nil	Slightly turbid	Brown	-

Sample Location	Date	pH - Field	EC - Field (µS)	Temperature	Redox	Odour	Appearance	Colour	Comments
VKY GW Duplicate 2 - GW-11	23-01-2024 14:26	-	-	-	-	-	-	-	-
VKY GW Lab Split Dup 1 - MD01	18-01-2024 9:42	11.73	1872	22.9	-149	Nil	Slightly turbid	Brown	-
VKY GW Lab Split Dup 2 -	23-01-2024 13:53	6.65	3490	24.8	-193	Nil	Slightly turbid	Brown	-
VKY GW Blank	17-01-2024 9:35	8.94	3.1	22.8	100	Nil	Clear	Colourless	-
VS058	15-04-2024 13:49	-	-	-	-	-	-	-	Li Battery 3.67V
SB02	15-04-2024 13:36	7.14	7210	24.7	-128	Nil	Slightly Turbid	Orange	
GW01	15-04-2024 13:12	7.14	1384	26.5	-127	Nil	Slightly Turbid	Black	Suspended solids minor
SB15	15-04-2024 12:56	7.17	972	27	43	Nil	Clear	Clear	Suspended solids minor
SB06	15-04-2024 12:21	7.42	3410	26.1	-70	Nil	Turbid	Black	-
SB11	15-04-2024 12:37	7.45	1048	24.3	69	Nil	Clear	Clear	-
SB10	15-04-2024 11:11	7.28	1859	24	-5	Nil	Slightly Turbid	Black	Suspended solids minor
SB05	15-04-2024 11:31	7.63	3680	22.9	-113	Nil	Slightly Turbid	Black	Suspended solids moderate
SB09	15-04-2024 10:52	7.27	973	21.7	-61	Nil	Turbid	Black	Suspended solids minor
SB01	15-04-2024 10:34	7.2	1698	24.1	-91	Nil	Clear	Grey	Suspended solids minor
SB04	15-04-2024 9:21	7.27	1868	24.1	-214	Yes	Turbid	Black	Sufer odour, suspended solids
SB08	15-04-2024 9:31	7.17	1039	21.2	-55	Nil	Clear	Clear	-
SB07	15-04-2024 8:48	7.28	934	21	57	Nil	Clear	Clear	Suspended solids minor
GW02	15-04-2024 8:16	7.14	926	24.3	8	Nil	Clear	Clear	Suspended solids moderate
VS062	15-04-2024 9:04	-	-	-	-	-	-	-	Li Battery 3.64V
VS059	15-04-2024 12:05	-	-	-	-	-	-	-	Li Battery 3.64V
VS056	17-04-2024 11:23	-	-	-	-	-	-	-	-
VS056	17-04-2024 11:26	-	-	-	-	-	-	-	-
MD01	18-04-2024 10:23	10.73	1283	24.2	-286	Strong	Slightly Turbid	Grey	Strong fecal odour
VS048	17-04-2024 10:59	-	-	-	-	-	-	-	-
VS054	17-04-2024 11:50	-	-	-	-	-	-	-	Li Battery 3.65V
MD02	17-04-2024 11:38	6.59	1210	31.1	-114	Slight	Clear	Clear	Suspended solids moderate
GW03	15-04-2024 9:56	7.05	862	24	-26	Nil	Clear	Grey	Suspended solids minor
TR26	17-04-2024 12:31	7.11	5180	29.4	60	Nil	Clear	Clear	
TR7	17-04-2024 12:49	6.71	14410	27.4	157	Nil	Clear	Orange	Logger length recorded
TR18	17-04-2024 13:26	6.69	12730	27.8	57	Nil	Slightly Turbid	Orange	Logger length recorded
TR35	17-04-2024 14:20	6.72	16740	22.8	48	Nil	Clear	Clear	
VKY43C	17-04-2024 14:06	7.65	3410	23.6	-47	Nil	Slightly Turbid	Orange	Logger was not working, removed at client request, not being replaced
VKY041C	17-04-2024 12:14								51.7% (should be battery)
	17-04-2024 12:17								35.2% (battery?)
VKY042C	29-04-2024 10:32	6.61	5480	24.3	-36	Nil	Clear	Clear	last 8m of logger cable rusty
VKY33C	18-04-2024 11:03	-	-	-	-	-	-	-	-
	18-04-2024 11:04	-	-	-	-	-	-	-	-
VKY035C	29-04-2024 14:41	6.88	3230	25	-120	Nil	Clear	Clear	
VKY034C	29-04-2024 9:58	7.05	4030	23.4	-80	Nil	Clear	Grey	
VKY036C	29-04-2024 14:10	6.8	5780	24.6	-93	Nil	Clear	Clear	
VKY3053C	29-04-2024 8:41	-	-	-	-	-	-	-	In forest? Incline to east VKY034C; Battery = 34.9%
VNW390	17-04-2024 8:30	6.59	2291	23.9	-98	Yes	Clear	Clear	Very slight sulfur odour

Sample Location	Date	pH - Field	EC - Field (µS)	Temperature	Redox	Odour	Appearance	Colour	Comments
VNW391	17-04-2024 10:11	7.06	2352	24.3	-107	Nil	Clear	Clear	
VNW392	17-04-2024 10:25	6.66	3480	21.9	-90	Nil	Clear	Grey	Suspended solids minor
VNW393	15-04-2024 14:40	7.2	2840	26.9	-103	Nil	Clear	Grey	
VNW394	15-04-2024 14:16	6.94	5400	25.7	-104	Nil	Turbid	Black	
VNW395	17-04-2024 9:28	7.77	1681	27.1	41	Nil	Clear	Clear	Logger length recorded
GW036459	-	-	-	-	-	-	-	-	-
GW-8	29-04-2024 8:28	6.95	4000	19.7	-151	Nil	Clear	Grey	
GW-7	30-04-2024 11:31	8.79	4560	21.9	97	Nil	Clear	Clear	
VWN223	29-04-2024 13:42	-	-	-	-	-	-	-	Blocked at 1.3m
GW-11	29-04-2024 12:59	6.59	4550	25.1	-123	Nil	Clear	Orange	
GW-9	29-04-2024 12:10	6.81	5630	22.2	-125	Nil	Slightly Turbid	Orange	
GW030051	-	-	-	-	-	-	-	-	No access, NSW Water locked bore
GW030052	-	-	-	-	-	-	-	-	No access, NSW Water locked bore
GW-2	29-04-2024 11:30	6.85	1218	25.3	70	Nil	Clear	Clear	Located, NotE?
WR-1	30-04-2024 10:15	6.7	####	22.7	217	Nil	Clear	Grey	Logger + HS installed
WR-2	30-04-2024 11:50	6.57	####	22.5	155	Nil	Slightly Turbid	Orange	Logger + HS installed
VKY GW Duplicate 1 - VWN390	17-04-2024 9:07	6.72	2320	22.4	-96	Nil	Clear	Clear	
VKY GW Duplicate 2 - GW-9	29-04-2024 12:33	6.72	5650	22.4	-155	Nil	Clear	Orange	
VKY GW Blank	17-04-2024 8:25	7.56	3.7	18.1	141	Nil	Clear	Clear	
VKY GW Lab Split Dup 1 - TR18	17-04-2024 13:52	6.77	####	25.2	139	Nil	Slightly Turbid	Orange	
VKY GW Lab Split Dup 2 - GW-11	29-04-2024 13:20	6.55	4520	25.1	-121	Nil	Clear	Orange	
VS058	01-07-2024 14:28	-	-	-	-	-	-	-	-
SB02	01-07-2024 14:04	7.2	6860	20.3	-109	Nil	Slightly Turbid	Brown	-
GW01	01-07-2024 13:42	7.2	1052	19.1	-32	Nil	Clear	Clear	-
SB15	01-07-2024 13:25	7.3	1049	19.6	8	Nil	Clear	Clear	-
SB06	01-07-2024 12:36	7.56	3440	18.6	-56	Nil	Turbid	Brown	Turbid brown
SB11	01-07-2024 13:05	7.77	461	17.9	-11	Nil	Clear	Clear	-
SB10	01-07-2024 12:01	7.5	1928	18	-23	Nil	Clear	Clear	Black particulate
SB05	01-07-2024 12:18	7.58	3490	18.6	-126	Nil	Clear	Clear	-
SB09	01-07-2024 11:40	7.52	1013	18.4	-84	Nil	Clear	Clear	Black particulate
SB01	01-07-2024 11:15	7.21	1756	17.6	-134	Nil	Clear	Clear	Black particulate
SB04	01-07-2024 10:07	7.12	2390	15.5	-204	H2S	Clear	Clear	H ₂ S
SB08	01-07-2024 10:16	7.29	1088	16.9	-132	Nil	Clear	Clear	-
SB07	01-07-2024 9:51	7.22	978	15.8	28	Nil	Clear	Clear	-
GW02	01-07-2024 9:00	7.23	1065	14.4	151	Nil	Clear	Clear	-
VS062	01-07-2024 8:44	-	-	-	-	-	-	-	-
VS059	01-07-2024 13:25	-	-	-	-	-	-	-	-
VS056	04-07-2024 12:50	-	-	-	-	-	-	-	-
VS056	04-07-2024 12:55	-	-	-	-	-	-	-	-
MD01	04-07-2024 12:45	9.59	1505	19.6	-244	-	Slightly Turbid	Brown	H ₂ S; Vegetable matter
VS048	04-07-2024 11:55	-	-	-	-	-	-	-	-
VS054	04-07-2024 12:15	-	-	-	-	-	-	-	Comm Port 25 (V3.66)

Sample Location	Date	pH - Field	EC - Field (µS)	Temperature	Redox	Odour	Appearance	Colour	Comments
MD02	04-07-2024 12:24	6.57	1224	19.9	-117	-	Clear	Clear	Black particulate; vegetable matter
GW03	01-07-2024 10:45	7.36	947	15.7	-143	-	Clear	Clear	Slight H2S
TR26	05-07-2024 9:37	6.69	7330	20.4	-	-	Slightly Turbid	Brown	
TR7	05-07-2024 10:27	6.82	####	17.9	-	-	Clear	Clear	
TR18	05-07-2024 10:53	6.64	####	17.2	-	-	Slightly Turbid	Brown	
TR35	05-07-2024 12:02	6.75	####	18.7	-	-	Clear	Clear	
VKY43C	05-07-2024 11:38	7.85	3290	7.2	-	-	Clear	Clear	
VKY041C	04-07-2024 13:45	-	-	-	-	-	-	-	Battery 53%
VKY041C	04-07-2024 13:45	-	-	-	-	-	-	-	Battery 34%
VKY042C	08-07-2024 15:02	6.65	5990	19.5	-13	-	Clear	Clear	
VKY33C	05-07-2024 12:32	-	-	-	-	-	-	-	Lithium 34%
VKY33C	05-07-2024 12:32	-	-	-	-	-	-	-	Lithium 37.1%
VKY035C	08-07-2024 13:25	6.9	3290	20.6	-88	-	Clear	Clear	-
VKY034C	05-07-2024 12:40	7.25	4170	19.3	-	-	Slightly Turbid	Grey	Slightly turbid; too turbid to filter, lab to filter; Grey
VKY036C	08-07-2024 14:27	7.19	5830	20.5	-111	-	Clear	Clear	-
VKY3053C	05-07-2024 8:31	-	-	-	-	-	-	-	Lithium
VNW390	04-07-2024 9:45	6.84	2473	17.7	-117	-	Clear	Clear	-
VNW391	04-07-2024 11:03	6.81	2458	19.2	-134	-	Clear	Clear	-
VNW392	04-07-2024 11:24	6.51	3510	19.6	-78	-	Clear	Clear	Slight H2S odor, black particulate
VNW393	04-07-2024 8:45	7.13	3090	18.4	104	-	Clear	Clear	-
VNW394	04-07-2024 8:28	6.62	5620	18.2	227	-	Slightly Turbid	Grey	-
VNW395	04-07-2024 10:27	7.61	1832	18.5	-4	-	Clear	Clear	Logger not responding
GW036459	-	-	-	-	-	-	-	-	No access - WaterNSW locked bore
GW-8	05-07-2024 8:00	6.49	4100	12.5	-	-	Slightly Turbid	Brown	-
GW-7	05-07-2024 10:39	8.67	4710	18.1	135	-	Clear	Clear	-
VWN223	05-07-2024 12:58	-	-	-	-	-	-	-	Blocked at 1.38mboc
GW-11	08-07-2024 12:20	6.09	4760	18.8	-54	-	Slightly Turbid	Brown	-
GW-9	08-07-2024 11:50	6.76	1591	19.3	-130	-	Slightly Turbid	Green	Slightly turbid; green
GW030051	-	-	-	-	-	-	-	-	No access - WaterNSW locked bore
GW030052	-	-	-	-	-	-	-	-	No access - WaterNSW locked bore
GW-2	-	-	-	-	-	-	-	-	Unable to locate
WR-1	08-07-2024 0:00	6.47	26800	18.2	254	-	Slightly Turbid	Brown	-
WR-2	08-07-2024 0:00	6.52	26600	17	10	-	Slightly Turbid	Brown	-
VKY GW Duplicate 1 - VNW390	04-07-2024 0:00	6.69	2366	19	-111	-	Clear	Clear	-
VKY GW Duplicate 2 - TR26	05-07-2024 0:00	7.03	7330	20.4	-	-	Slightly Turbid	Brown	-
VKY GW Blank	01-07-2024 0:00	7.1	2315	14.4	-124	-	Clear	Clear	-
VKY GW Lab Split Dup 1 - VNW393	04-07-2024 0:00	6.97	3270	20.5	-85	-	Clear	Clear	-
VKY GW Lab Split Dup 2 - VKY035C	08-07-2024 0:00	8	1.6	11	92	-	Clear	Clear	-
GW-11	18-10-2024 9:25	7.17	4760	22.6	-94	NIL	Clear	Brown	Overgrown
GW-13	21-10-2024 12:48	7.35	1647	23.5	-158	NIL	Clear	Black	C?
GW-14	21-10-2024 10:33	6.95	3840	23.4	22	NIL	Clear	Colourless	Overgrown
GW-2	22-10-2024 10:58	6.84	1226	21	100	NIL	Clear	Colourless	-

Sample Location	Date	pH - Field	EC - Field (µS)	Temperature	Redox	Odour	Appearance	Colour	Comments
GW-6	15-11-2024 9:11	7.73	1459	27.3	-142	NIL	Slightly Turbid	Black	No access to bore on 21-10-24; uncovered on 15-11-24
GW-7	18-10-2024 13:30	8.3	4470	24.5	55	NIL	Clear	Colourless	Overgrown
GW-8	21-10-2024 8:40	7	3930	16.1	-210	NIL	Slightly Turbid	Brown	-
GW-9	21-10-2024 9:40	6.68	1099	20.7	-188	NIL	Slightly Turbid	Orange	-
GW01	14-10-2024 13:47	7.16	738	19.8	-84	S	Clear	Colourless	Slight H2S odour. Ant bait changed.
GW02	14-10-2024 8:50	7.42	1016	18.7	196	NIL	Clear	Colourless	Comport 1?. Ant bait changed.
GW03	14-10-2024 11:10	7.22	1004	19	-39	NIL	Clear	Colourless	Ant bait changed.
MD01	15-10-2024 12:16	8.33	1787	25	-280	Decomposing odour (organic matter?)	Slightly Turbid	Grey	Decomposing odour (organic matter?)
MD02	15-10-2024 12:03	6.72	1279	25	-71	NIL	Clear	Colourless	-
SB01	14-10-2024 11:31	7.23	1869	20.7	-60	NIL	Clear	Colourless	-
SB02	14-10-2024 14:06	7.23	7250	19.9	-113	NIL	Slightly Turbid	Brown	-
SB04	14-10-2024 10:22	7.21	2289	19.4	-178	Mild H2S	Clear	Colourless	Mild H2S
SB05	14-10-2024 12:27	7.71	3790	19.5	-45	NIL	Clear	Colourless	-
SB06	14-10-2024 12:48	7.7	2790	19.5	-113	NIL	Slightly Turbid	Grey	-
SB07	14-10-2024 9:42	7.58	1042	18.4	98	NIL	Clear	Colourless	-
SB08	14-10-2024 10:35	7.27	388	19.3	-57	Mild H2S	Clear	Colourless	Mild H2S
SB09	14-10-2024 11:58	7.44	1130	20.6	7	NIL	Clear	Colourless	-
SB10	14-10-2024 12:09	7.38	2200	20.4	32	NIL	Clear	Grey	-
SB11	14-10-2024 13:07	7.51	1266	19.8	-9	NIL	Clear	Colourless	-
SB15	14-10-2024 13:30	7.24	1143	19.8	44	NIL	Clear	Colourless	-
TR18	15-10-2024 14:05	6.79	13820	21.3	100	NIL	Slightly Turbid	Brown	Logger removed
TR26	15-10-2024 13:30	6.93	6090	28.5	-31	NIL	Clear	Colourless	-
TR35	15-10-2024 14:34	6.73	16690	23	92	NIL	Clear	Colourless	-
TR7	15-10-2024 13:45	6.63	1484	26.2	80	NIL	Clear	Colourless	-
VKY035C	18-10-2024 11:15	7.09	3330	28.4	-48	NIL	Clear	Colourless	-
VKY036C	18-10-2024 10:24	7.21	6020	24.7	-71	NIL	Clear	Grey	-
VKY042C	18-10-2024 10:54	6.72	5850	23.9	-18	NIL	Clear	Colourless	-
VKY034C	18-10-2024 12:02	7.25	3970	26.4	29	NIL	Turbid	Grey	Too turbid, send lab to filter
VKY041C	15-10-2024 13:09	-	-	-	-	-	-	-	Not sure which is which as no machine serial numbers on loggers. Change battery in 02027. Ant bait changed.
VKY041C	15-10-2024 13:09	-	-	-	-	-	-	-	Ant bait changed
VKY043C	15-10-2024 14:20	7.7	3050	22.7	30	NIL	Clear	Colourless	
VKY33C	18-10-2024 12:44	-	-	-	-	-	-	-	Ant bait changed
VKY33C	18-10-2024 12:46	-	-	-	-	-	-	-	Ant bait changed
VKY3053C	21-10-2024 8:46	-	-	-	-	-	-	-	Ant bait changed
VNW223	18-10-2024 8:32	7.17	5360	22.2	129	NIL	Clear	Colourless	
VNW390	15-10-2024 10:09	6.81	2431	21.6	-103	NIL	Clear	Colourless	
VNW394	15-10-2024 9:10	7.07	5420	19.8	-98	NIL	Clear	Colourless	
VNW392	15-10-2024 11:04	6.74	3410	23.3	-60	NIL	Clear	Colourless	
VNW393	15-10-2024 9:45	7.16	3140	23.7	-117	NIL	Clear	Colourless	
VNW391	15-10-2024 10:45	7.1	2424	22.4	-104	NIL	Clear	Colourless	

Sample Location	Date	pH - Field	EC - Field (µS)	Temperature	Redox	Odour	Appearance	Colour	Comments
VNW395	15-10-2024 10:30	7.56	1834	21.7	40	NIL	Clear	Colourless	No logger; Ant bait changed
VS048	15-10-2024 11:35	-	-	-	-	-	-	-	Ant bait changed
VS054	15-10-2024 11:51	-	-	-	-	-	-	-	Comport 25; Ant bait changed
VS056	15-10-2024 12:24	-	-	-	-	-	-	-	Ant bait changed
VS056	15-10-2024 12:24	-	-	-	-	-	-	-	Ant bait changed
VS058	14-10-2024 14:20	-	-	-	-	-	-	-	Ant bait changed
VS059	14-10-2024 8:30	-	-	-	-	-	-	-	Ant bait changed
VS062	14-10-2024 10:00	-	-	-	-	-	-	-	Ant bait changed
WR-1	18-10-2024 13:58	6.5	2680	23.5	150	NIL	Clear	Grey	Comport 8
WR-2	18-10-2024 14:40	6.36	2660	24.2	-37	NIL	Slightly Turbid	Grey	
GW036459	-	-	-	-	-	-	-	-	No access - NSW Water locked bore
GW030051	-	-	-	-	-	-	-	-	No access - NSW Water locked bore
GW030052	-	-	-	-	-	-	-	-	No access - NSW Water locked bore
GW-4	15-11-2024 8:50	7.92	2980	21.8	177	NIL	Slightly Turbid	Colourless	No access for sampling on 22 Oct 2024, bore uncovered on 15 Nov 2024
GW-10	22-10-2024 11:45	7.57	1438	23.8	93	NIL	Clear	Orange	-
GW-15	22-10-2024 13:30	8.97	638	23.6	12	NIL	Clear	Colourless	See photos
GW971614	22-10-2024 9:40	6.65	651	19	219	NIL	Clear	Colourless	Sampled from tank outflow?
GW971400	22-10-2024 10:15	6.8	2458	20.2	76	NIL	Clear	Colourless	Sampled from outflow
GW4	22-10-2024 11:30	-	-	-	-	-	-	-	No access
VKY GW Duplicate 1 - GW-9	21-10-2024 9:40	6.66	1076	20.3	779	NIL	Slightly Turbid	Orange	-
VKY GW Duplicate 2 - GW-10	22-10-2024 11:45	7.54	1478	23.7	77	NIL	Clear	Colourless	-
VKY GW Blank	21-10-2024 7:30	7.5	3.2	19.7	-83	NIL	Clear	Colourless	-
VKY GW Lab Split Dup 1 - GW-14	21-10-2024 10:33	6.91	3830	21.6	10	NIL	Clear	Colourless	-
VKY GW Lab Split Dup 2 - GW-10	22-10-2024 11:45	7.6	1477	22.8	110	NIL	Clear	Colourless	-
GW-11	15-01-2025 12:25	7.03	4310	33.5	-142	NIL	Slightly Turbid	Grey	-
GW-13	15-01-2025 13:30	7.3	1570	32.7	55	NIL	Clear	Green/Grey	-
GW-14	16-01-2025 8:30	6.53	4260	21.8	-215	NIL	Clear	Colourless	
GW-2	16-01-2025 7:50	6.45	1339	20.6	-210	NIL	Clear	Colourless	
GW-6	15-01-2025 13:45	7.52	1256	31.5	-142	NIL	Slightly Turbid	Green	
GW-7	16-01-2025 9:30	7.76	4690	25.5	-192	NIL	Clear	Colourless	
GW-8	15-01-2025 7:45	6.62	4350	28.9	-119	NIL	Slightly Turbid	Brown	
GW-9	16-01-2025 7:40	5.4	1544	21.6	-147	NIL	Slightly Turbid	Brown	
GW01	14-01-2025 8:08	7.1	1244	23.6	-164	NIL	Clear	Colourless	
GW02	13-01-2025 8:45	6.63	992	22	69	NIL	Clear	Colourless	D/cell
GW03	13-01-2025 12:42	7.08	983	26.2	-143	NIL	Clear	Grey	
MD01	14-01-2025 10:11	8.84	1519	28.1	-323	NIL	Clear	Colourless	Mild H2S Odour
MD02	14-01-2025 9:37	6.81	1381	28.9	-158	NIL	Clear	Colourless	-
SB01	13-01-2025 13:12	7.12	1851	26.7	-114	NIL	Clear	Grey	-
SB02	14-01-2025 8:32	7.22	6990	28.4	-126	NIL	Clear	Colourless	-
SB04	13-01-2025 11:52	7.04	3420	25.3	-171	S	Slightly Turbid	Grey	H2S ODOR
SB05	13-01-2025 14:30	7.52	3660	25.2	-128	NIL	Slightly Turbid	Grey	-
SB06	13-01-2025 15:04	7.42	3160	29.3	-127	NIL	Clear	Grey	-

Sample Location	Date	pH - Field	EC - Field (µS)	Temperature	Redox	Odour	Appearance	Colour	Comments
SB07	13-01-2025 9:32	7.29	1009	22.7	-53	NIL	Clear	Colourless	TR7 Logger
SB08	13-01-2025 12:04	7.27	1154	24.7	-68	NIL	Clear	Colourless	-
SB09	13-01-2025 13:40	7.4	1045	28.4	-78	NIL	Clear	Colourless	-
SB10	13-01-2025 14:06	7.25	2086	28.4	22	NIL	Clear	Colourless	-
SB11	13-01-2025 15:19	7.39	1209	27.8	-27	NIL	Clear	Colourless	-
SB15	14-01-2025 7:42	7.41	1163	23	61	NIL	Clear	Colourless	-
TR18	14-01-2025 13:10	6.68	13810	27.3	12	NIL	Slightly Turbid	Grey	-
TR26	14-01-2025 12:40	6.85	6170	35.3	-47	NIL	Slightly Turbid	Grey	-
TR35	14-01-2025 13:40	6.54	18320	26	122	NIL	Clear	Colourless	-
TR7	14-01-2025 12:55	6.51	1552	26.8	76	NIL	Slightly Turbid	Grey	-
VKY035C	15-01-2025 10:10	6.93	3220	30.2	-86	NIL	Clear	Colourless	-
VKY036C	15-01-2025 10:45	7.06	2980	30.6	-110	NIL	Slightly Turbid	Grey	-
VKY042C	15-01-2025 11:15	6.64	5590	30.4	-54	NIL	Clear	Colourless	-
VKY034C	15-01-2025 9:45	7.16	3910	28.9	18	NIL	Grey	Grey	Too turbid to field filter
VKY041C	15-01-2025 12:10	-	-	-	-	-	-	-	Batt. 48.7%
VKY041C	15-01-2025 12:18	-	-	-	-	-	-	-	Batt. 31.2%
VKY043C	14-01-2025 13:25	7.5	3240	31	-42	NIL	Clear	Colourless	-
VKY33C	15-01-2025 9:35	-	-	-	-	-	-	-	Batt. 34.5%
VKY33C	15-01-2025 9:35	-	-	-	-	-	-	-	-
VKY3053C	15-01-2025 8:00	-	-	-	-	-	-	-	-
VNW223	15-01-2025 11:45	7.07	4390	32.5	88	NIL	Clear	Colourless	
VNW390	14-01-2025 10:15	6.96	2629	28.4	-10	NIL	Clear	Colourless	
VNW391	14-01-2025 11:40	7.02	2550	24.7	-129	NIL	Clear	Green	
VNW392	14-01-2025 12:10	6.47	3480	31.3	-467	NIL	Clear	Colourless	
VNW393	14-01-2025 11:30	6.94	3210	29.8	-70	NIL	Clear	Grey	
VNW394	14-01-2025 11:00	6.87	5480	29.5	-46	NIL	Slightly Turbid	Grey	
VNW395	14-01-2025 11:17	7.58	2153	23.1	-229	S	Clear	Green	Slight Unknown
VS048	14-01-2025 10:55	-	-	-	-	-	-	-	D-cell
VS054	14-01-2025 9:55	-	-	-	-	-	-	-	Lithium Dk
VS056	14-01-2025 10:32	-	-	-	-	-	-	-	D-cell
VS056	14-01-2025 10:38	-	-	-	-	-	-	-	D-cell
VS058	14-01-2025 8:57	-	-	-	-	-	-	-	Lithium Dk
VS059	13-01-2025 8:15	-	-	-	-	-	-	-	Indicated low battery-changed
VS062	13-01-2025 11:25	-	-	-	-	-	-	-	D-cell
WR-1	14-01-2025 9:30	6.95	25400	27.8	93	NIL	Clear	Colourless	
WR-2	14-01-2025 7:50	6.41	27900	23.8	29	NIL	Slightly Turbid	Colourless	
GW-4	16-01-2025 8:25	7.84	2970	21	-258	NIL	Clear	Colourless	
GW-10	15-01-2025 13:00	7.36	1423	-	67	NIL	Clear	Green	
GW-15	15-01-2025 8:43	8.85	644	30.8	-224	NIL	Clear	Colourless	
GW971614	16-01-2025 12:00	7.08	608	26.7	-106	NIL	Clear	Colourless	
Landreef Tap	16-01-2025 11:30	6.96	841	27.6	-103	NIL	Clear	Colourless	
VKY GW Duplicate 1 - GW-15	15-01-2025 8:45	8.91	684	26.4	-200	NIL	Clear	Colourless	

Sample Location	Date	pH - Field	EC - Field (µS)	Temperature	Redox	Odour	Appearance	Colour	Comments
VKY GW Duplicate 2 - GW-11	15-01-2025 12:25	6.92	4650	30	-124	NIL	Clear	Colourless	
VKY GW Blank	16-01-2025 8:40	4.83	-5.8	22.7	286	NIL	Clear	Colourless	
VKY GW Lab Split Dup 1 - GW-15	15-01-2025 8:45	8.94	716	24.4	-187	NIL	Clear	Colourless	
VKY GW Lab Split Dup 2 - GW-11	15-01-2025 12:25	8.67	4840	27.2	-118	NIL	Clear	Colourless	

Table C-2: Laboratory GW Monitoring Data (as COA provided by ALS and Eurofin)

LAB USE ONLY RECEIVED (DATE/TIME): 17-01-25 10:30 APPROPRIATELY SEALED?: YES NO TEMPERATURE: 3.8 JOB #: SIGNED: IR

LABORATORY	ALS Newcastle 5/585 Maitland Road Mayfield West 2304 NSW
SAMPLERS	Greg Quayle
QUOTE #	SYBQ-403-21v4
PO #	

SITE	Vickery
PROJECT	Vickery Quarterly Groundwaters
PROJECT MANAGER	
COMPANY	CBased Environmental Pty Ltd PO Box 245 Cessnock NSW 2325
CONTACT PERSON	Mamie Blake
CONTACT NUMBER	
CONTACT FAX	
CONTACT EMAILS	monitoringresults@cbased.com.au
INVOICING EMAILS	accounts@cbased.com.au
RESULT EMAILS	monitoringresults@cbased.com.au, inxpreservemail@whitehavencoal.com.au, vickeryenvironment@whitehavencoal.com.au

ANALYSIS REQUIRED	GENERAL INSTRUCTIONS
A. Ammonia as N B. Bicarbonate Alkalinity as CaCO3 C. Calcium (dissolved) D. Carbonate Alkalinity as CaCO3 E. DO F. EC G. Hydroxide Alkalinity as CaCO3 H. Ionic balance I. Nitrate as N J. Nitrite + Nitrate as N K. Nitrite as N L. Oil and Grease M. pH N. Sodium (Dissolved) O. TDS	

#	SAMPLE NAME	DATE/TIME	SAMPLE ID	CONTAINERS	MATRIX	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	SAMPLE INSTRUCTIONS
1	GW-11	2025-01-15 12:25	4F55Y3NQ-1	4	Water	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	
2	GW-13	2025-01-15 13:30	4F55Y3NQ-2	4	Water	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	
3	GW-14	2025-01-16 08:55	4F55Y3NQ-3	4	Water	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	
4	GW-2	2025-01-16 07:50	4F55Y3NQ-4	4	Water	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	
5	GW-6	2025-01-15 13:45	4F55Y3NQ-5	4	Water	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	
6	GW-7	2025-01-16 13:30	4F55Y3NQ-6	4	Water	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	
7	GW-8	2025-01-15 07:45	4F55Y3NQ-7	4	Water	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	
8	GW-9	2025-01-16 07:40	4F55Y3NQ-8	4	Water	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	
9	GW01	2025-01-14 08:08	4F55Y3NQ-9	4	Water	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	
10	GW02	2025-01-13 08:45	4F55Y3NQ-10	4	Water	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	
11	GW03	2025-01-13 12:42	4F55Y3NQ-11	4	Water	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	
12	MD01	2025-01-14 10:11	4F55Y3NQ-12	4	Water	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	
13	MD02	2025-01-14 09:47	4F55Y3NQ-13	4	Water	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	
14	SB01	2025-01-13 13:12	4F55Y3NQ-14	4	Water	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	
15	SB02	2025-01-14 08:32	4F55Y3NQ-15	4	Water	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	
16	SB04	2025-01-13 11:52	4F55Y3NQ-16	4	Water	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	
17	SB05	2025-01-13 14:30	4F55Y3NQ-17	4	Water	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	
18	SB06	2025-01-13 15:04	4F55Y3NQ-18	4	Water	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	

ALS PU

Environmental Division
 Newcastle
 Work Order Reference
EN2500866



10	GW02	2025-01-13 08:45	4F55Y3NQ-10	4	Water	X	X	X	X	X	X	X	X	X	X	X	X	X	X		
11	GW03	2025-01-13 12:42	4F55Y3NQ-11	4	Water	X	X	X	X	X	X	X	X	X	X	X	X	X	X		
12	MD01	2025-01-14 10:11	4F55Y3NQ-12	4	Water	X	X	X	X	X	X	X	X	X	X	X	X	X	X		
13	MD02	2025-01-14 09:47	4F55Y3NQ-13	4	Water	X	X	X	X	X	X	X	X	X	X	X	X	X	X		
14	SB01	2025-01-13 13:12	4F55Y3NQ-14	4	Water	X	X	X	X	X	X	X	X	X	X	X	X	X	X		
15	SB02	2025-01-14 08:32	4F55Y3NQ-15	4	Water	X	X	X	X	X	X	X	X	X	X	X	X	X	X		
16	SB04	2025-01-13 11:52	4F55Y3NQ-16	4	Water	X	X	X	X	X	X	X	X	X	X	X	X	X	X		
17	SB05	2025-01-13 14:30	4F55Y3NQ-17	4	Water	X	X	X	X	X	X	X	X	X	X	X	X	X	X		
18	SB06	2025-01-13 15:04	4F55Y3NQ-18	4	Water	X	X	X	X	X	X	X	X	X	X	X	X	X	X		
19	SB07	2025-01-13 09:32	4F55Y3NQ-19	4	Water	X	X	X	X	X	X	X	X	X	X	X	X	X	X		
20	SB08	2025-01-13 12:04	4F55Y3NQ-20	4	Water	X	X	X	X	X	X	X	X	X	X	X	X	X	X		
21	SB09	2025-01-13 13:40	4F55Y3NQ-21	4	Water	X	X	X	X	X	X	X	X	X	X	X	X	X	X		
22	SB10	2025-01-13 14:14	4F55Y3NQ-22	4	Water	X	X	X	X	X	X	X	X	X	X	X	X	X	X		
23	SB15	2025-01-14 07:42	4F55Y3NQ-23	4	Water	X	X	X	X	X	X	X	X	X	X	X	X	X	X		

CHAIN OF CUSTODY PS4XXPD HANDED OVER BY CBased Environment HANDOVER DATE/TIME 2025-01-17 10: REQUIRED TURNAROUND 5 Working Days RETURN EQUIPMENT N EDD FORMAT IN PAGE 8 OF 9

ANALYSIS REQUIRED	GENERAL INSTRUCTIONS
AE. Lead (dissolved) AF. Magnesium (dissolved) AG. Manganese (dissolved) AH. Mercury (dissolved) AI. Molybdenum (dissolved) AJ. Nickel (dissolved) AK. Phosphorus (dissolved) AL. Potassium (dissolved) AM. Selenium (dissolved) AN. Silver (dissolved) AO. Strontium (dissolved) AP. Sulfate as SO ₄ - Turbidimetric (dissolved) AQ. Tin (dissolved) AR. Zinc (dissolved)	



CERTIFICATE OF ANALYSIS

Work Order : **EN2500866**
Client : **CBASED ENVIRONMENTAL PTY LTD**
Contact : All Deliverables
Address : Unit 3 2 Enterprise Cres
Singleton NSW 2330
Telephone : +61 02 6571 3334
Project : Vickery Quarterly Groundwaters
Order number : ----
C-O-C number : ----
Sampler : Greg Quayle
Site : Vickery
Quote number : SYBQ/403/21v4 and PLANNED EVENTS
No. of samples received : 52
No. of samples analysed : 52

Page : 1 of 35
Laboratory : Environmental Division Newcastle
Contact :
Address : 5/585 Maitland Road Mayfield West NSW Australia 2304
Telephone : +61 2 4014 2500
Date Samples Received : 17-Jan-2025 10:30
Date Analysis Commenced : 24-Jan-2025
Issue Date : 03-Feb-2025 17:48



Accreditation No. 825
Accredited for compliance with
ISO/IEC 17025 - Testing

This report supersedes any previous report(s) with this reference. Results apply to the sample(s) as submitted, unless the sampling was conducted by ALS. This document shall not be reproduced, except in full.

This Certificate of Analysis contains the following information:

- General Comments
- Analytical Results

Additional information pertinent to this report will be found in the following separate attachments: Quality Control Report, QA/QC Compliance Assessment to assist with Quality Review and Sample Receipt Notification.

Signatories

This document has been electronically signed by the authorized signatories below. Electronic signing is carried out in compliance with procedures specified in 21 CFR Part 11.

<i>Signatories</i>	<i>Position</i>	<i>Accreditation Category</i>
Ankit Joshi	Senior Chemist - Inorganics	Sydney Inorganics, Smithfield, NSW



General Comments

The analytical procedures used by ALS have been developed from established internationally recognised procedures such as those published by the USEPA, APHA, AS and NEPM. In house developed procedures are fully validated and are often at the client request.

Where moisture determination has been performed, results are reported on a dry weight basis.

Where a reported less than (<) result is higher than the LOR, this may be due to primary sample extract/digestate dilution and/or insufficient sample for analysis.

Where the LOR of a reported result differs from standard LOR, this may be due to high moisture content, insufficient sample (reduced weight employed) or matrix interference.

When sampling time information is not provided by the client, sampling dates are shown without a time component. In these instances, the time component has been assumed by the laboratory for processing purposes.

Where a result is required to meet compliance limits the associated uncertainty must be considered. Refer to the ALS Contract for details.

Key : CAS Number = CAS registry number from database maintained by Chemical Abstracts Services. The Chemical Abstracts Service is a division of the American Chemical Society.
LOR = Limit of reporting
^ = This result is computed from individual analyte detections at or above the level of reporting
ø = ALS is not NATA accredited for these tests.
~ = Indicates an estimated value.

- As per QWI – EN55-3 Data Interpreting Procedures, Ionic balances are typically calculated using Major Anions - Chloride, Alkalinity and Sulfate; and Major Cations - Calcium, Magnesium, Potassium and Sodium. Where applicable and dependent upon sample matrix, the Ionic Balance may also include the additional contribution of Ammonia, Dissolved Metals by ICPMS and H+ to the Cations and Nitrate, SiO₂ and Fluoride to the Anions.
- EG020: Poor matrix spike recovery was obtained for Cadmium, Magnesium and Nickel. Confirmed by reanalysis
- It has been noted that Nitrite is greater than NO_x, however this difference is within the limits of experimental variation.
- EK057/EK059G: Nitrite and NO_x results confirmed by re analysis.
- TDS by method EA-015 may bias high for various samples due to the presence of fine particulate matter, which may pass through the prescribed GF/C paper.
- EK067: It has been noted that Filtered is greater than Total Phosphorous for various samples, however this difference is within the limits of experimental variation.
- Sodium Adsorption Ratio (where reported): Where results for Na, Ca or Mg are <LOR, a concentration at half the reported LOR is incorporated into the SAR calculation. This represents a conservative approach for Na relative to the assumption that <LOR = zero concentration and a conservative approach for Ca & Mg relative to the assumption that <LOR is equivalent to the LOR concentration.
- ED045G: The presence of Thiocyanate, Thiosulfate and Sulfite can positively contribute to the chloride result, thereby may bias results higher than expected. Results should be scrutinised accordingly.



Analytical Results

Sub-Matrix: WATER (Matrix: WATER)				Sample ID	GW-11 4F55Y3NQ-1	GW-13 4F55Y3NQ-2	GW-14 4F55Y3NQ-3	GW-2 4F55Y3NQ-4	GW-6 4F55Y3NQ-5
Sampling date / time				15-Jan-2025 12:25	15-Jan-2025 13:30	16-Jan-2025 08:55	16-Jan-2025 07:50	15-Jan-2025 13:45	
Compound	CAS Number	LOR	Unit	EN2500866-001	EN2500866-002	EN2500866-003	EN2500866-004	EN2500866-005	
				Result	Result	Result	Result	Result	
EA005P: pH by PC Titrator									
pH Value	----	0.01	pH Unit	7.29	7.72	7.26	7.29	7.96	
EA010P: Conductivity by PC Titrator									
Electrical Conductivity @ 25°C	----	1	µS/cm	4620	1680	3690	1200	1380	
EA015: Total Dissolved Solids dried at 180 ± 5 °C									
Total Dissolved Solids @180°C	----	10	mg/L	3590	1050	2570	812	872	
ED037P: Alkalinity by PC Titrator									
Hydroxide Alkalinity as CaCO3	DMO-210-001	1	mg/L	<1	<1	<1	<1	<1	
Carbonate Alkalinity as CaCO3	3812-32-6	1	mg/L	<1	<1	<1	<1	<1	
Bicarbonate Alkalinity as CaCO3	71-52-3	1	mg/L	185	736	544	515	711	
Total Alkalinity as CaCO3	----	1	mg/L	185	736	544	515	711	
ED041G: Sulfate (Turbidimetric) as SO4 2- by DA									
Sulfate as SO4 - Turbidimetric	14808-79-8	1	mg/L	3	26	462	23	<1	
ED045G: Chloride by Discrete Analyser									
Chloride	16887-00-6	1	mg/L	1500	148	807	119	60	
ED093F: Dissolved Major Cations									
Calcium	7440-70-2	1	mg/L	216	29	204	98	9	
Magnesium	7439-95-4	1	mg/L	52	16	92	29	5	
Sodium	7440-23-5	1	mg/L	669	378	574	159	361	
Potassium	7440-09-7	1	mg/L	11	12	2	2	2	
EG020F: Dissolved Metals by ICP-MS									
Aluminium	7429-90-5	0.01	mg/L	<0.01	<0.01	<0.01	<0.01	<0.01	
Antimony	7440-36-0	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	
Arsenic	7440-38-2	0.001	mg/L	<0.001	<0.001	<0.001	0.001	<0.001	
Barium	7440-39-3	0.001	mg/L	0.112	0.043	0.044	0.204	0.306	
Chromium	7440-47-3	0.001	mg/L	<0.001	<0.001	<0.001	0.002	<0.001	
Cobalt	7440-48-4	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	
Lead	7439-92-1	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	



Analytical Results

Sub-Matrix: WATER
 (Matrix: WATER)

Sample ID

				GW-11 4F55Y3NQ-1	GW-13 4F55Y3NQ-2	GW-14 4F55Y3NQ-3	GW-2 4F55Y3NQ-4	GW-6 4F55Y3NQ-5
Sampling date / time				15-Jan-2025 12:25	15-Jan-2025 13:30	16-Jan-2025 08:55	16-Jan-2025 07:50	15-Jan-2025 13:45
Compound	CAS Number	LOR	Unit	EN2500866-001	EN2500866-002	EN2500866-003	EN2500866-004	EN2500866-005
				Result	Result	Result	Result	Result
EG020F: Dissolved Metals by ICP-MS - Continued								
Manganese	7439-96-5	0.001	mg/L	1.04	0.136	0.008	0.009	0.029
Molybdenum	7439-98-7	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001
Nickel	7440-02-0	0.001	mg/L	<0.001	0.005	0.001	<0.001	<0.001
Selenium	7782-49-2	0.01	mg/L	<0.01	<0.01	<0.01	<0.01	<0.01
Silver	7440-22-4	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001
Strontium	7440-24-6	0.001	mg/L	3.02	0.894	2.58	0.930	0.166
Tin	7440-31-5	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001
Zinc	7440-66-6	0.005	mg/L	0.034	0.020	0.031	0.016	<0.005
Boron	7440-42-8	0.05	mg/L	0.13	0.08	<0.05	<0.05	0.08
Iron	7439-89-6	0.05	mg/L	8.70	0.38	<0.05	<0.05	0.11
EG035F: Dissolved Mercury by FIMS								
Mercury	7439-97-6	0.0001	mg/L	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001
EK055G: Ammonia as N by Discrete Analyser								
Ammonia as N	7664-41-7	0.01	mg/L	1.96	4.26	0.05	0.05	0.88
EK057G: Nitrite as N by Discrete Analyser								
Nitrite as N	14797-65-0	0.01	mg/L	0.01	0.05	0.02	0.02	<0.01
EK058G: Nitrate as N by Discrete Analyser								
Nitrate as N	14797-55-8	0.01	mg/L	0.03	<0.01	0.71	0.36	0.02
EK059G: Nitrite plus Nitrate as N (NOx) by Discrete Analyser								
Nitrite + Nitrate as N	----	0.01	mg/L	0.04	0.04	0.73	0.38	0.02
EK067FG: Filtered Total Phosphorus as P by Discrete Analyser								
Filtered Total Phosphorus as P	----	0.01	mg/L	<0.01	0.12	0.02	0.05	0.13
EK067G: Total Phosphorus as P by Discrete Analyser								
Total Phosphorus as P	----	0.01	mg/L	0.08	1.41	0.04	0.04	0.99
EN055: Ionic Balance								
∅ Total Anions	----	0.01	meq/L	46.1	19.4	43.2	14.1	15.9
∅ Total Cations	----	0.01	meq/L	44.4	19.5	42.8	14.2	16.6



Analytical Results

Sub-Matrix: WATER
 (Matrix: WATER)

Sample ID

				GW-11 4F55Y3NQ-1	GW-13 4F55Y3NQ-2	GW-14 4F55Y3NQ-3	GW-2 4F55Y3NQ-4	GW-6 4F55Y3NQ-5
Sampling date / time				15-Jan-2025 12:25	15-Jan-2025 13:30	16-Jan-2025 08:55	16-Jan-2025 07:50	15-Jan-2025 13:45
Compound	CAS Number	LOR	Unit	EN2500866-001	EN2500866-002	EN2500866-003	EN2500866-004	EN2500866-005
				Result	Result	Result	Result	Result
EN055: Ionic Balance - Continued								
∅ Ionic Balance	----	0.01	%	1.80	0.23	0.56	0.42	2.20
EP020: Oil and Grease (O&G)								
Oil & Grease	----	5	mg/L	<5	<5	<5	<5	<5
EP025: Oxygen - Dissolved (DO)								
Dissolved Oxygen	----	0.1	mg/L	7.8	8.4	8.6	8.7	7.3



Analytical Results

Sub-Matrix: WATER (Matrix: WATER)				Sample ID	GW-7 4F55Y3NQ-6	GW-8 4F55Y3NQ-7	GW-9 4F55Y3NQ-8	GW01 4F55Y3NQ-9	GW02 4F55Y3NQ-10
Sampling date / time				16-Jan-2025 13:30	15-Jan-2025 07:45	16-Jan-2025 07:40	14-Jan-2025 08:08	13-Jan-2025 08:45	
Compound	CAS Number	LOR	Unit	EN2500866-006	EN2500866-007	EN2500866-008	EN2500866-009	EN2500866-010	
				Result	Result	Result	Result	Result	
EA005P: pH by PC Titrator									
pH Value	----	0.01	pH Unit	8.41	7.47	5.71	7.49	7.68	
EA010P: Conductivity by PC Titrator									
Electrical Conductivity @ 25°C	----	1	µS/cm	4200	3750	1340	1060	897	
EA015: Total Dissolved Solids dried at 180 ± 5 °C									
Total Dissolved Solids @180°C	----	10	mg/L	2780	2290	1080	676	582	
ED037P: Alkalinity by PC Titrator									
Hydroxide Alkalinity as CaCO3	DMO-210-001	1	mg/L	<1	<1	<1	<1	<1	
Carbonate Alkalinity as CaCO3	3812-32-6	1	mg/L	50	<1	<1	<1	<1	
Bicarbonate Alkalinity as CaCO3	71-52-3	1	mg/L	985	733	8	445	365	
Total Alkalinity as CaCO3	----	1	mg/L	1040	733	8	445	365	
ED041G: Sulfate (Turbidimetric) as SO4 2- by DA									
Sulfate as SO4 - Turbidimetric	14808-79-8	1	mg/L	414	109	<1	132	91	
ED045G: Chloride by Discrete Analyser									
Chloride	16887-00-6	1	mg/L	706	885	448	48	43	
ED093F: Dissolved Major Cations									
Calcium	7440-70-2	1	mg/L	6	130	69	74	50	
Magnesium	7439-95-4	1	mg/L	160	84	16	47	22	
Sodium	7440-23-5	1	mg/L	637	668	129	143	142	
Potassium	7440-09-7	1	mg/L	324	9	10	1	<1	
EG020F: Dissolved Metals by ICP-MS									
Aluminium	7429-90-5	0.01	mg/L	<0.01	<0.01	<0.01	<0.01	<0.01	
Antimony	7440-36-0	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	
Arsenic	7440-38-2	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	
Barium	7440-39-3	0.001	mg/L	0.022	0.192	0.041	0.081	0.046	
Chromium	7440-47-3	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	
Cobalt	7440-48-4	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	
Lead	7439-92-1	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	



Analytical Results

Sub-Matrix: WATER
 (Matrix: WATER)

Sample ID

				GW-7 4F55Y3NQ-6	GW-8 4F55Y3NQ-7	GW-9 4F55Y3NQ-8	GW01 4F55Y3NQ-9	GW02 4F55Y3NQ-10
Sampling date / time				16-Jan-2025 13:30	15-Jan-2025 07:45	16-Jan-2025 07:40	14-Jan-2025 08:08	13-Jan-2025 08:45
Compound	CAS Number	LOR	Unit	EN2500866-006	EN2500866-007	EN2500866-008	EN2500866-009	EN2500866-010
				Result	Result	Result	Result	Result
EG020F: Dissolved Metals by ICP-MS - Continued								
Manganese	7439-96-5	0.001	mg/L	0.040	0.132	2.60	0.240	0.006
Molybdenum	7439-98-7	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001
Nickel	7440-02-0	0.001	mg/L	0.001	0.002	<0.001	<0.001	<0.001
Selenium	7782-49-2	0.01	mg/L	<0.01	<0.01	<0.01	<0.01	<0.01
Silver	7440-22-4	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001
Strontium	7440-24-6	0.001	mg/L	0.090	2.73	1.71	1.46	0.656
Tin	7440-31-5	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001
Zinc	7440-66-6	0.005	mg/L	<0.005	<0.005	0.008	<0.005	0.005
Boron	7440-42-8	0.05	mg/L	0.17	0.07	<0.05	0.07	0.06
Iron	7439-89-6	0.05	mg/L	<0.05	5.72	64.1	0.77	<0.05
EG035F: Dissolved Mercury by FIMS								
Mercury	7439-97-6	0.0001	mg/L	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001
EK055G: Ammonia as N by Discrete Analyser								
Ammonia as N	7664-41-7	0.01	mg/L	1.53	1.63	0.90	0.24	0.02
EK057G: Nitrite as N by Discrete Analyser								
Nitrite as N	14797-65-0	0.01	mg/L	0.15	<0.01	<0.01	0.01	<0.01
EK058G: Nitrate as N by Discrete Analyser								
Nitrate as N	14797-55-8	0.01	mg/L	<0.01	<0.01	0.01	0.19	0.74
EK059G: Nitrite plus Nitrate as N (NOx) by Discrete Analyser								
Nitrite + Nitrate as N	----	0.01	mg/L	0.01	<0.01	0.01	0.20	0.74
EK067FG: Filtered Total Phosphorus as P by Discrete Analyser								
Filtered Total Phosphorus as P	----	0.01	mg/L	0.09	0.14	0.02	0.19	0.17
EK067G: Total Phosphorus as P by Discrete Analyser								
Total Phosphorus as P	----	0.01	mg/L	0.07	0.16	0.02	0.16	0.18
EN055: Ionic Balance								
∅ Total Anions	----	0.01	meq/L	49.3	41.9	12.8	13.0	10.4
∅ Total Cations	----	0.01	meq/L	49.5	42.7	10.6	13.8	10.5



Analytical Results

Sub-Matrix: WATER
 (Matrix: WATER)

				Sample ID	GW-7 4F55Y3NQ-6	GW-8 4F55Y3NQ-7	GW-9 4F55Y3NQ-8	GW01 4F55Y3NQ-9	GW02 4F55Y3NQ-10
				Sampling date / time	16-Jan-2025 13:30	15-Jan-2025 07:45	16-Jan-2025 07:40	14-Jan-2025 08:08	13-Jan-2025 08:45
Compound	CAS Number	LOR	Unit	EN2500866-006	EN2500866-007	EN2500866-008	EN2500866-009	EN2500866-010	EN2500866-010
				Result	Result	Result	Result	Result	Result
EN055: Ionic Balance - Continued									
∅ Ionic Balance	----	0.01	%	0.15	0.95	9.26	3.03	0.39	
EP020: Oil and Grease (O&G)									
Oil & Grease	----	5	mg/L	<5	<5	<5	<5	<5	
EP025: Oxygen - Dissolved (DO)									
Dissolved Oxygen	----	0.1	mg/L	8.4	8.4	7.9	8.5	8.7	



Analytical Results

Sub-Matrix: WATER (Matrix: WATER)				Sample ID	GW03 4F55Y3NQ-11	MD01 4F55Y3NQ-12	MD02 4F55Y3NQ-13	SB01 4F55Y3NQ-14	SB02 4F55Y3NQ-15
Sampling date / time				13-Jan-2025 12:42	14-Jan-2025 10:11	14-Jan-2025 09:47	13-Jan-2025 13:12	14-Jan-2025 08:32	
Compound	CAS Number	LOR	Unit	EN2500866-011 Result	EN2500866-012 Result	EN2500866-013 Result	EN2500866-014 Result	EN2500866-015 Result	EN2500866-015 Result
EA005P: pH by PC Titrator									
pH Value	----	0.01	pH Unit	7.51	9.05	7.07	7.59	7.50	
EA010P: Conductivity by PC Titrator									
Electrical Conductivity @ 25°C	----	1	µS/cm	867	1360	1180	1640	6640	
EA015: Total Dissolved Solids dried at 180 ± 5 °C									
Total Dissolved Solids @180°C	----	10	mg/L	577	774	683	958	4570	
ED037P: Alkalinity by PC Titrator									
Hydroxide Alkalinity as CaCO3	DMO-210-001	1	mg/L	<1	<1	<1	<1	<1	
Carbonate Alkalinity as CaCO3	3812-32-6	1	mg/L	<1	93	<1	<1	<1	
Bicarbonate Alkalinity as CaCO3	71-52-3	1	mg/L	417	231	511	550	841	
Total Alkalinity as CaCO3	----	1	mg/L	417	324	511	550	841	
ED041G: Sulfate (Turbidimetric) as SO4 2- by DA									
Sulfate as SO4 - Turbidimetric	14808-79-8	1	mg/L	53	33	28	216	1280	
ED045G: Chloride by Discrete Analyser									
Chloride	16887-00-6	1	mg/L	22	258	81	175	1300	
ED093F: Dissolved Major Cations									
Calcium	7440-70-2	1	mg/L	86	9	100	102	76	
Magnesium	7439-95-4	1	mg/L	31	8	55	68	69	
Sodium	7440-23-5	1	mg/L	79	267	137	214	1550	
Potassium	7440-09-7	1	mg/L	2	22	10	2	2	
EG020F: Dissolved Metals by ICP-MS									
Aluminium	7429-90-5	0.01	mg/L	<0.01	0.04	<0.01	<0.01	<0.01	
Antimony	7440-36-0	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	
Arsenic	7440-38-2	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	
Barium	7440-39-3	0.001	mg/L	0.080	0.141	0.262	0.114	0.028	
Chromium	7440-47-3	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	
Cobalt	7440-48-4	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	0.002	
Lead	7439-92-1	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	



Analytical Results

Sub-Matrix: WATER
 (Matrix: WATER)

Sample ID

				GW03 4F55Y3NQ-11	MD01 4F55Y3NQ-12	MD02 4F55Y3NQ-13	SB01 4F55Y3NQ-14	SB02 4F55Y3NQ-15
Sampling date / time				13-Jan-2025 12:42	14-Jan-2025 10:11	14-Jan-2025 09:47	13-Jan-2025 13:12	14-Jan-2025 08:32
Compound	CAS Number	LOR	Unit	EN2500866-011	EN2500866-012	EN2500866-013	EN2500866-014	EN2500866-015
				Result	Result	Result	Result	Result
EG020F: Dissolved Metals by ICP-MS - Continued								
Manganese	7439-96-5	0.001	mg/L	0.089	0.017	0.050	0.153	0.692
Molybdenum	7439-98-7	0.001	mg/L	<0.001	0.002	0.001	<0.001	0.002
Nickel	7440-02-0	0.001	mg/L	<0.001	0.002	0.010	<0.001	0.001
Selenium	7782-49-2	0.01	mg/L	<0.01	<0.01	<0.01	<0.01	<0.01
Silver	7440-22-4	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001
Strontium	7440-24-6	0.001	mg/L	0.977	1.34	1.33	2.07	2.03
Tin	7440-31-5	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001
Zinc	7440-66-6	0.005	mg/L	<0.005	0.014	0.006	<0.005	<0.005
Boron	7440-42-8	0.05	mg/L	<0.05	<0.05	<0.05	0.08	0.14
Iron	7439-89-6	0.05	mg/L	0.42	<0.05	1.55	0.14	0.08
EG035F: Dissolved Mercury by FIMS								
Mercury	7439-97-6	0.0001	mg/L	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001
EK055G: Ammonia as N by Discrete Analyser								
Ammonia as N	7664-41-7	0.01	mg/L	0.72	16.4	0.29	0.10	0.03
EK057G: Nitrite as N by Discrete Analyser								
Nitrite as N	14797-65-0	0.01	mg/L	0.03	<0.01	0.02	<0.01	<0.01
EK058G: Nitrate as N by Discrete Analyser								
Nitrate as N	14797-55-8	0.01	mg/L	0.85	0.05	0.02	0.01	0.13
EK059G: Nitrite plus Nitrate as N (NOx) by Discrete Analyser								
Nitrite + Nitrate as N	----	0.01	mg/L	0.88	0.05	0.04	0.01	0.13
EK067FG: Filtered Total Phosphorus as P by Discrete Analyser								
Filtered Total Phosphorus as P	----	0.01	mg/L	0.10	0.27	0.06	0.21	0.64
EK067G: Total Phosphorus as P by Discrete Analyser								
Total Phosphorus as P	----	0.01	mg/L	0.84	0.33	0.11	0.34	0.65
EN055: Ionic Balance								
∅ Total Anions	----	0.01	meq/L	10.0	14.4	13.1	20.4	80.1
∅ Total Cations	----	0.01	meq/L	10.3	13.3	15.7	20.0	76.9



Analytical Results

Sub-Matrix: WATER
 (Matrix: WATER)

				Sample ID	GW03 4F55Y3NQ-11	MD01 4F55Y3NQ-12	MD02 4F55Y3NQ-13	SB01 4F55Y3NQ-14	SB02 4F55Y3NQ-15
Sampling date / time					13-Jan-2025 12:42	14-Jan-2025 10:11	14-Jan-2025 09:47	13-Jan-2025 13:12	14-Jan-2025 08:32
Compound	CAS Number	LOR	Unit	EN2500866-011	EN2500866-012	EN2500866-013	EN2500866-014	EN2500866-015	EN2500866-015
				Result	Result	Result	Result	Result	Result
EN055: Ionic Balance - Continued									
∅ Ionic Balance	----	0.01	%	1.35	4.16	9.21	0.93	2.02	
EP020: Oil and Grease (O&G)									
Oil & Grease	----	5	mg/L	<5	<5	<5	<5	<5	
EP025: Oxygen - Dissolved (DO)									
Dissolved Oxygen	----	0.1	mg/L	8.0	6.8	8.1	8.2	8.4	



Analytical Results

Sub-Matrix: WATER (Matrix: WATER)				Sample ID	SB04 4F55Y3NQ-16	SB05 4F55Y3NQ-17	SB06 4F55Y3NQ-18	SB07 4F55Y3NQ-19	SB08 4F55Y3NQ-20
Sampling date / time				13-Jan-2025 11:52	13-Jan-2025 14:30	13-Jan-2025 15:04	13-Jan-2025 09:32	13-Jan-2025 12:04	
Compound	CAS Number	LOR	Unit	EN2500866-016	EN2500866-017	EN2500866-018	EN2500866-019	EN2500866-020	
				Result	Result	Result	Result	Result	
EA005P: pH by PC Titrator									
pH Value	----	0.01	pH Unit	7.55	7.92	7.84	7.69	7.69	
EA010P: Conductivity by PC Titrator									
Electrical Conductivity @ 25°C	----	1	µS/cm	3060	3220	2860	901	1020	
EA015: Total Dissolved Solids dried at 180 ± 5 °C									
Total Dissolved Solids @180°C	----	10	mg/L	2070	2230	1800	561	582	
ED037P: Alkalinity by PC Titrator									
Hydroxide Alkalinity as CaCO3	DMO-210-001	1	mg/L	<1	<1	<1	<1	<1	
Carbonate Alkalinity as CaCO3	3812-32-6	1	mg/L	<1	<1	<1	<1	<1	
Bicarbonate Alkalinity as CaCO3	71-52-3	1	mg/L	830	725	481	374	386	
Total Alkalinity as CaCO3	----	1	mg/L	830	725	481	374	386	
ED041G: Sulfate (Turbidimetric) as SO4 2- by DA									
Sulfate as SO4 - Turbidimetric	14808-79-8	1	mg/L	413	447	366	89	97	
ED045G: Chloride by Discrete Analyser									
Chloride	16887-00-6	1	mg/L	452	462	545	40	66	
ED093F: Dissolved Major Cations									
Calcium	7440-70-2	1	mg/L	102	26	35	54	71	
Magnesium	7439-95-4	1	mg/L	88	19	30	24	38	
Sodium	7440-23-5	1	mg/L	584	777	634	134	118	
Potassium	7440-09-7	1	mg/L	1	<1	<1	<1	<1	
EG020F: Dissolved Metals by ICP-MS									
Aluminium	7429-90-5	0.01	mg/L	0.56	<0.01	<0.01	<0.01	<0.01	
Antimony	7440-36-0	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	
Arsenic	7440-38-2	0.001	mg/L	<0.001	0.004	0.002	<0.001	<0.001	
Barium	7440-39-3	0.001	mg/L	0.112	0.086	0.104	0.045	0.054	
Chromium	7440-47-3	0.001	mg/L	0.001	<0.001	<0.001	0.001	<0.001	
Cobalt	7440-48-4	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	
Lead	7439-92-1	0.001	mg/L	0.001	<0.001	<0.001	<0.001	<0.001	



Analytical Results

Sub-Matrix: WATER
 (Matrix: WATER)

Sample ID

				SB04 4F55Y3NQ-16	SB05 4F55Y3NQ-17	SB06 4F55Y3NQ-18	SB07 4F55Y3NQ-19	SB08 4F55Y3NQ-20
Sampling date / time				13-Jan-2025 11:52	13-Jan-2025 14:30	13-Jan-2025 15:04	13-Jan-2025 09:32	13-Jan-2025 12:04
Compound	CAS Number	LOR	Unit	EN2500866-016	EN2500866-017	EN2500866-018	EN2500866-019	EN2500866-020
				Result	Result	Result	Result	Result
EG020F: Dissolved Metals by ICP-MS - Continued								
Manganese	7439-96-5	0.001	mg/L	0.307	0.703	0.285	0.002	0.007
Molybdenum	7439-98-7	0.001	mg/L	<0.001	0.002	0.002	<0.001	<0.001
Nickel	7440-02-0	0.001	mg/L	0.002	<0.001	<0.001	<0.001	<0.001
Selenium	7782-49-2	0.01	mg/L	<0.01	<0.01	<0.01	<0.01	<0.01
Silver	7440-22-4	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001
Strontium	7440-24-6	0.001	mg/L	2.47	0.646	1.07	0.699	1.10
Tin	7440-31-5	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001
Zinc	7440-66-6	0.005	mg/L	0.056	<0.005	<0.005	<0.005	<0.005
Boron	7440-42-8	0.05	mg/L	0.11	0.15	0.13	0.06	0.06
Iron	7439-89-6	0.05	mg/L	1.58	0.19	0.23	<0.05	<0.05
EG035F: Dissolved Mercury by FIMS								
Mercury	7439-97-6	0.0001	mg/L	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001
EK055G: Ammonia as N by Discrete Analyser								
Ammonia as N	7664-41-7	0.01	mg/L	0.10	0.24	0.07	0.02	0.03
EK057G: Nitrite as N by Discrete Analyser								
Nitrite as N	14797-65-0	0.01	mg/L	0.02	<0.01	<0.01	<0.01	0.01
EK058G: Nitrate as N by Discrete Analyser								
Nitrate as N	14797-55-8	0.01	mg/L	0.06	0.05	<0.01	0.29	0.30
EK059G: Nitrite plus Nitrate as N (NOx) by Discrete Analyser								
Nitrite + Nitrate as N	----	0.01	mg/L	0.08	0.05	<0.01	0.29	0.31
EK067FG: Filtered Total Phosphorus as P by Discrete Analyser								
Filtered Total Phosphorus as P	----	0.01	mg/L	0.16	0.63	0.19	0.07	0.06
EK067G: Total Phosphorus as P by Discrete Analyser								
Total Phosphorus as P	----	0.01	mg/L	0.24	1.11	0.29	0.09	0.12
EN055: Ionic Balance								
∅ Total Anions	----	0.01	meq/L	37.9	36.8	32.6	10.4	11.6
∅ Total Cations	----	0.01	meq/L	37.8	36.6	31.8	10.5	11.8



Analytical Results

Sub-Matrix: WATER
 (Matrix: WATER)

				Sample ID	SB04	SB05	SB06	SB07	SB08
					4F55Y3NQ-16	4F55Y3NQ-17	4F55Y3NQ-18	4F55Y3NQ-19	4F55Y3NQ-20
Sampling date / time					13-Jan-2025 11:52	13-Jan-2025 14:30	13-Jan-2025 15:04	13-Jan-2025 09:32	13-Jan-2025 12:04
Compound	CAS Number	LOR	Unit	EN2500866-016	EN2500866-017	EN2500866-018	EN2500866-019	EN2500866-020	EN2500866-020
				Result	Result	Result	Result	Result	Result
EN055: Ionic Balance - Continued									
∅ Ionic Balance	----	0.01	%	0.23	0.23	1.26	0.21	0.90	
EP020: Oil and Grease (O&G)									
Oil & Grease	----	5	mg/L	<5	<5	<5	<5	<5	
EP025: Oxygen - Dissolved (DO)									
Dissolved Oxygen	----	0.1	mg/L	6.9	7.5	8.3	8.6	8.6	



Analytical Results

Sub-Matrix: WATER (Matrix: WATER)				Sample ID	SB09 4F55Y3NQ-21	SB10 4F55Y3NQ-22	SB15 4F55Y3NQ-23	TR18 4F55Y3NQ-24	TR26 4F55Y3NQ-25
Sampling date / time				13-Jan-2025 13:40	13-Jan-2025 14:14	14-Jan-2025 07:42	14-Jan-2025 13:10	14-Jan-2025 12:40	
Compound	CAS Number	LOR	Unit	EN2500866-021	EN2500866-022	EN2500866-023	EN2500866-024	EN2500866-025	
				Result	Result	Result	Result	Result	
EA005P: pH by PC Titrator									
pH Value	----	0.01	pH Unit	7.83	7.86	7.60	7.31	7.59	
EA010P: Conductivity by PC Titrator									
Electrical Conductivity @ 25°C	----	1	µS/cm	968	2010	1020	13200	6560	
EA015: Total Dissolved Solids dried at 180 ± 5 °C									
Total Dissolved Solids @180°C	----	10	mg/L	544	1280	642	8700	3660	
ED037P: Alkalinity by PC Titrator									
Hydroxide Alkalinity as CaCO3	DMO-210-001	1	mg/L	<1	<1	<1	<1	<1	
Carbonate Alkalinity as CaCO3	3812-32-6	1	mg/L	<1	<1	<1	<1	<1	
Bicarbonate Alkalinity as CaCO3	71-52-3	1	mg/L	437	663	439	690	1240	
Total Alkalinity as CaCO3	----	1	mg/L	437	663	439	690	1240	
ED041G: Sulfate (Turbidimetric) as SO4 2- by DA									
Sulfate as SO4 - Turbidimetric	14808-79-8	1	mg/L	78	238	119	630	229	
ED045G: Chloride by Discrete Analyser									
Chloride	16887-00-6	1	mg/L	29	202	37	4090	1580	
ED093F: Dissolved Major Cations									
Calcium	7440-70-2	1	mg/L	48	41	75	261	158	
Magnesium	7439-95-4	1	mg/L	28	31	45	328	166	
Sodium	7440-23-5	1	mg/L	164	419	117	2410	1230	
Potassium	7440-09-7	1	mg/L	1	<1	<1	11	10	
EG020F: Dissolved Metals by ICP-MS									
Aluminium	7429-90-5	0.01	mg/L	<0.01	<0.01	<0.01	0.03	<0.01	
Antimony	7440-36-0	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	
Arsenic	7440-38-2	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	
Barium	7440-39-3	0.001	mg/L	0.078	0.050	0.066	0.065	0.157	
Chromium	7440-47-3	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	
Cobalt	7440-48-4	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	
Lead	7439-92-1	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	



Analytical Results

Sub-Matrix: WATER
 (Matrix: WATER)

Sample ID

				SB09 4F55Y3NQ-21	SB10 4F55Y3NQ-22	SB15 4F55Y3NQ-23	TR18 4F55Y3NQ-24	TR26 4F55Y3NQ-25
Sampling date / time				13-Jan-2025 13:40	13-Jan-2025 14:14	14-Jan-2025 07:42	14-Jan-2025 13:10	14-Jan-2025 12:40
Compound	CAS Number	LOR	Unit	EN2500866-021	EN2500866-022	EN2500866-023	EN2500866-024	EN2500866-025
				Result	Result	Result	Result	Result
EG020F: Dissolved Metals by ICP-MS - Continued								
Manganese	7439-96-5	0.001	mg/L	0.615	0.011	0.002	0.032	0.105
Molybdenum	7439-98-7	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001
Nickel	7440-02-0	0.001	mg/L	<0.001	<0.001	<0.001	0.011	0.006
Selenium	7782-49-2	0.01	mg/L	<0.01	<0.01	<0.01	<0.01	<0.01
Silver	7440-22-4	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001
Strontium	7440-24-6	0.001	mg/L	0.934	0.987	1.41	7.29	3.82
Tin	7440-31-5	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001
Zinc	7440-66-6	0.005	mg/L	0.013	<0.005	<0.005	<0.005	<0.005
Boron	7440-42-8	0.05	mg/L	0.07	0.10	0.06	0.07	0.09
Iron	7439-89-6	0.05	mg/L	<0.05	<0.05	<0.05	0.20	0.07
EG035F: Dissolved Mercury by FIMS								
Mercury	7439-97-6	0.0001	mg/L	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001
EK055G: Ammonia as N by Discrete Analyser								
Ammonia as N	7664-41-7	0.01	mg/L	0.14	0.03	0.01	0.02	0.03
EK057G: Nitrite as N by Discrete Analyser								
Nitrite as N	14797-65-0	0.01	mg/L	<0.01	<0.01	0.02	0.01	0.07
EK058G: Nitrate as N by Discrete Analyser								
Nitrate as N	14797-55-8	0.01	mg/L	<0.01	0.10	0.17	0.09	0.14
EK059G: Nitrite plus Nitrate as N (NOx) by Discrete Analyser								
Nitrite + Nitrate as N	----	0.01	mg/L	<0.01	0.10	0.19	0.10	0.21
EK067FG: Filtered Total Phosphorus as P by Discrete Analyser								
Filtered Total Phosphorus as P	----	0.01	mg/L	0.09	0.11	0.07	0.21	0.08
EK067G: Total Phosphorus as P by Discrete Analyser								
Total Phosphorus as P	----	0.01	mg/L	0.94	0.12	0.12	0.32	0.14
EN055: Ionic Balance								
∅ Total Anions	----	0.01	meq/L	11.2	23.9	12.3	142	74.1
∅ Total Cations	----	0.01	meq/L	11.8	22.8	12.5	145	75.3



Analytical Results

Sub-Matrix: WATER
 (Matrix: WATER)

				Sample ID	SB09	SB10	SB15	TR18	TR26
					4F55Y3NQ-21	4F55Y3NQ-22	4F55Y3NQ-23	4F55Y3NQ-24	4F55Y3NQ-25
				Sampling date / time	13-Jan-2025 13:40	13-Jan-2025 14:14	14-Jan-2025 07:42	14-Jan-2025 13:10	14-Jan-2025 12:40
Compound	CAS Number	LOR	Unit	EN2500866-021	EN2500866-022	EN2500866-023	EN2500866-024	EN2500866-025	EN2500866-025
				Result	Result	Result	Result	Result	Result
EN055: Ionic Balance - Continued									
∅ Ionic Balance	----	0.01	%	2.98	2.31	0.98	0.99	0.80	0.80
EP020: Oil and Grease (O&G)									
Oil & Grease	----	5	mg/L	<5	<5	<5	<5	<5	<5
EP025: Oxygen - Dissolved (DO)									
Dissolved Oxygen	----	0.1	mg/L	8.4	8.4	8.5	7.2	6.9	6.9



Analytical Results

Sub-Matrix: WATER (Matrix: WATER)				Sample ID	TR35 4F55Y3NQ-26	TR7 4F55Y3NQ-27	VKY0035C 4F55Y3NQ-28	VKY0036C 4F55Y3NQ-29	VKY0042C 4F55Y3NQ-30
Sampling date / time				14-Jan-2025 13:40	14-Jan-2025 12:55	15-Jan-2025 10:10	15-Jan-2025 10:45	15-Jan-2025 11:15	
Compound	CAS Number	LOR	Unit	EN2500866-026	EN2500866-027	EN2500866-028	EN2500866-029	EN2500866-030	
				Result	Result	Result	Result	Result	
EA005P: pH by PC Titrator									
pH Value	----	0.01	pH Unit	7.25	7.19	7.52	7.67	7.28	
EA010P: Conductivity by PC Titrator									
Electrical Conductivity @ 25°C	----	1	µS/cm	17100	15300	3090	5620	5510	
EA015: Total Dissolved Solids dried at 180 ± 5 °C									
Total Dissolved Solids @180°C	----	10	mg/L	12000	10000	1920	3550	3570	
ED037P: Alkalinity by PC Titrator									
Hydroxide Alkalinity as CaCO3	DMO-210-001	1	mg/L	<1	<1	<1	<1	<1	
Carbonate Alkalinity as CaCO3	3812-32-6	1	mg/L	<1	<1	<1	<1	<1	
Bicarbonate Alkalinity as CaCO3	71-52-3	1	mg/L	710	726	890	1260	787	
Total Alkalinity as CaCO3	----	1	mg/L	710	726	890	1260	787	
ED041G: Sulfate (Turbidimetric) as SO4 2- by DA									
Sulfate as SO4 - Turbidimetric	14808-79-8	1	mg/L	526	458	83	190	307	
ED045G: Chloride by Discrete Analyser									
Chloride	16887-00-6	1	mg/L	5420	4810	535	1120	1320	
ED093F: Dissolved Major Cations									
Calcium	7440-70-2	1	mg/L	358	310	51	55	215	
Magnesium	7439-95-4	1	mg/L	570	368	46	43	235	
Sodium	7440-23-5	1	mg/L	3000	2780	655	1340	788	
Potassium	7440-09-7	1	mg/L	19	14	7	7	22	
EG020F: Dissolved Metals by ICP-MS									
Aluminium	7429-90-5	0.01	mg/L	<0.01	<0.01	<0.01	<0.01	<0.01	
Antimony	7440-36-0	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	
Arsenic	7440-38-2	0.001	mg/L	<0.001	<0.001	0.001	0.006	<0.001	
Barium	7440-39-3	0.001	mg/L	0.098	0.114	0.073	0.250	0.138	
Chromium	7440-47-3	0.001	mg/L	<0.001	<0.001	0.001	<0.001	<0.001	
Cobalt	7440-48-4	0.001	mg/L	0.008	0.005	<0.001	<0.001	<0.001	
Lead	7439-92-1	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	



Analytical Results

Sub-Matrix: WATER
 (Matrix: WATER)

Sample ID

				TR35 4F55Y3NQ-26	TR7 4F55Y3NQ-27	VKY0035C 4F55Y3NQ-28	VKY0036C 4F55Y3NQ-29	VKY0042C 4F55Y3NQ-30
Sampling date / time				14-Jan-2025 13:40	14-Jan-2025 12:55	15-Jan-2025 10:10	15-Jan-2025 10:45	15-Jan-2025 11:15
Compound	CAS Number	LOR	Unit	EN2500866-026	EN2500866-027	EN2500866-028	EN2500866-029	EN2500866-030
				Result	Result	Result	Result	Result
EG020F: Dissolved Metals by ICP-MS - Continued								
Manganese	7439-96-5	0.001	mg/L	0.907	0.381	0.308	0.151	0.220
Molybdenum	7439-98-7	0.001	mg/L	0.002	<0.001	0.006	0.002	<0.001
Nickel	7440-02-0	0.001	mg/L	0.111	0.024	0.006	0.004	0.003
Selenium	7782-49-2	0.01	mg/L	<0.01	<0.01	<0.01	<0.01	<0.01
Silver	7440-22-4	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001
Strontium	7440-24-6	0.001	mg/L	9.40	10.2	0.864	0.947	3.58
Tin	7440-31-5	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001
Zinc	7440-66-6	0.005	mg/L	0.009	0.006	<0.005	<0.005	0.015
Boron	7440-42-8	0.05	mg/L	0.07	0.07	<0.05	0.09	0.06
Iron	7439-89-6	0.05	mg/L	0.10	0.54	0.64	0.11	0.94
EG035F: Dissolved Mercury by FIMS								
Mercury	7439-97-6	0.0001	mg/L	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001
EK055G: Ammonia as N by Discrete Analyser								
Ammonia as N	7664-41-7	0.01	mg/L	0.05	0.11	0.90	1.06	0.54
EK057G: Nitrite as N by Discrete Analyser								
Nitrite as N	14797-65-0	0.01	mg/L	<0.01	<0.01	<0.01	0.02	0.02
EK058G: Nitrate as N by Discrete Analyser								
Nitrate as N	14797-55-8	0.01	mg/L	<0.01	<0.01	0.02	0.01	0.02
EK059G: Nitrite plus Nitrate as N (NOx) by Discrete Analyser								
Nitrite + Nitrate as N	----	0.01	mg/L	<0.01	<0.01	0.02	0.03	0.04
EK067FG: Filtered Total Phosphorus as P by Discrete Analyser								
Filtered Total Phosphorus as P	----	0.01	mg/L	0.03	0.14	0.13	0.55	0.07
EK067G: Total Phosphorus as P by Discrete Analyser								
Total Phosphorus as P	----	0.01	mg/L	0.06	0.32	0.14	0.62	0.02
EN055: Ionic Balance								
∅ Total Anions	----	0.01	meq/L	178	160	34.6	60.7	59.4
∅ Total Cations	----	0.01	meq/L	196	167	35.0	64.7	64.9



Analytical Results

Sub-Matrix: WATER
 (Matrix: WATER)

				Sample ID	TR35 4F55Y3NQ-26	TR7 4F55Y3NQ-27	VKY0035C 4F55Y3NQ-28	VKY0036C 4F55Y3NQ-29	VKY0042C 4F55Y3NQ-30
Sampling date / time					14-Jan-2025 13:40	14-Jan-2025 12:55	15-Jan-2025 10:10	15-Jan-2025 10:45	15-Jan-2025 11:15
Compound	CAS Number	LOR	Unit		EN2500866-026	EN2500866-027	EN2500866-028	EN2500866-029	EN2500866-030
					Result	Result	Result	Result	Result
EN055: Ionic Balance - Continued									
∅ Ionic Balance	----	0.01	%		4.74	2.24	0.57	3.21	4.47
EP020: Oil and Grease (O&G)									
Oil & Grease	----	5	mg/L		<5	<5	<5	<5	<5
EP025: Oxygen - Dissolved (DO)									
Dissolved Oxygen	----	0.1	mg/L		7.9	7.0	7.8	7.0	8.8



Analytical Results

Sub-Matrix: WATER (Matrix: WATER)				Sample ID	VKY0034C 4F55Y3NQ-31	VKY0043C 4F55Y3NQ-32	VNW223/P-3 4F55Y3NQ-33	VNW390 4F55Y3NQ-34	VNW391 4F55Y3NQ-35
Sampling date / time				15-Jan-2025 09:45	14-Jan-2025 13:25	15-Jan-2025 11:45	14-Jan-2025 10:15	14-Jan-2025 11:40	
Compound	CAS Number	LOR	Unit	EN2500866-031	EN2500866-032	EN2500866-033	EN2500866-034	EN2500866-035	
				Result	Result	Result	Result	Result	
EA005P: pH by PC Titrator									
pH Value	----	0.01	pH Unit	7.71	8.13	7.74	7.35	7.68	
EA010P: Conductivity by PC Titrator									
Electrical Conductivity @ 25°C	----	1	µS/cm	3830	2950	5300	2260	2320	
EA015: Total Dissolved Solids dried at 180 ± 5 °C									
Total Dissolved Solids @180°C	----	10	mg/L	2580	1460	3080	1360	1380	
ED037P: Alkalinity by PC Titrator									
Hydroxide Alkalinity as CaCO3	DMO-210-001	1	mg/L	<1	<1	<1	<1	<1	
Carbonate Alkalinity as CaCO3	3812-32-6	1	mg/L	<1	<1	<1	<1	<1	
Bicarbonate Alkalinity as CaCO3	71-52-3	1	mg/L	1350	1120	1050	597	603	
Total Alkalinity as CaCO3	----	1	mg/L	1350	1120	1050	597	603	
ED041G: Sulfate (Turbidimetric) as SO4 2- by DA									
Sulfate as SO4 - Turbidimetric	14808-79-8	1	mg/L	115	<1	91	107	101	
ED045G: Chloride by Discrete Analyser									
Chloride	16887-00-6	1	mg/L	534	377	1140	406	446	
ED093F: Dissolved Major Cations									
Calcium	7440-70-2	1	mg/L	28	11	102	195	186	
Magnesium	7439-95-4	1	mg/L	28	4	126	46	59	
Sodium	7440-23-5	1	mg/L	1000	752	982	286	277	
Potassium	7440-09-7	1	mg/L	7	5	8	11	12	
EG020F: Dissolved Metals by ICP-MS									
Aluminium	7429-90-5	0.01	mg/L	<0.01	<0.01	<0.01	<0.01	<0.01	
Antimony	7440-36-0	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	
Arsenic	7440-38-2	0.001	mg/L	0.001	<0.001	<0.001	0.001	<0.001	
Barium	7440-39-3	0.001	mg/L	0.257	0.328	0.109	0.125	0.171	
Chromium	7440-47-3	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	
Cobalt	7440-48-4	0.001	mg/L	<0.001	<0.001	<0.001	0.002	<0.001	
Lead	7439-92-1	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	



Analytical Results

Sub-Matrix: WATER
 (Matrix: WATER)

Sample ID

				VKY0034C 4F55Y3NQ-31	VKY0043C 4F55Y3NQ-32	VNW223/P-3 4F55Y3NQ-33	VNW390 4F55Y3NQ-34	VNW391 4F55Y3NQ-35
Sampling date / time				15-Jan-2025 09:45	14-Jan-2025 13:25	15-Jan-2025 11:45	14-Jan-2025 10:15	14-Jan-2025 11:40
Compound	CAS Number	LOR	Unit	EN2500866-031	EN2500866-032	EN2500866-033	EN2500866-034	EN2500866-035
				Result	Result	Result	Result	Result
EG020F: Dissolved Metals by ICP-MS - Continued								
Manganese	7439-96-5	0.001	mg/L	0.008	0.005	0.007	0.227	0.233
Molybdenum	7439-98-7	0.001	mg/L	0.003	<0.001	<0.001	0.003	<0.001
Nickel	7440-02-0	0.001	mg/L	0.003	0.001	0.002	0.024	0.004
Selenium	7782-49-2	0.01	mg/L	<0.01	<0.01	<0.01	<0.01	<0.01
Silver	7440-22-4	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001
Strontium	7440-24-6	0.001	mg/L	0.523	0.411	2.18	1.91	1.78
Tin	7440-31-5	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001
Zinc	7440-66-6	0.005	mg/L	0.014	<0.005	0.027	0.005	0.019
Boron	7440-42-8	0.05	mg/L	0.19	0.06	0.08	0.11	0.10
Iron	7439-89-6	0.05	mg/L	<0.05	0.10	<0.05	0.49	0.06
EG035F: Dissolved Mercury by FIMS								
Mercury	7439-97-6	0.0001	mg/L	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001
EK055G: Ammonia as N by Discrete Analyser								
Ammonia as N	7664-41-7	0.01	mg/L	0.72	0.40	0.66	0.41	0.23
EK057G: Nitrite as N by Discrete Analyser								
Nitrite as N	14797-65-0	0.01	mg/L	0.01	<0.01	0.22	<0.01	<0.01
EK058G: Nitrate as N by Discrete Analyser								
Nitrate as N	14797-55-8	0.01	mg/L	0.08	<0.01	1.68	<0.01	0.11
EK059G: Nitrite plus Nitrate as N (NOx) by Discrete Analyser								
Nitrite + Nitrate as N	----	0.01	mg/L	0.09	<0.01	1.90	<0.01	0.11
EK067FG: Filtered Total Phosphorus as P by Discrete Analyser								
Filtered Total Phosphorus as P	----	0.01	mg/L	0.67	0.09	0.26	0.08	0.12
EK067G: Total Phosphorus as P by Discrete Analyser								
Total Phosphorus as P	----	0.01	mg/L	0.87	0.05	0.35	0.06	0.14
EN055: Ionic Balance								
∅ Total Anions	----	0.01	meq/L	44.4	33.0	55.0	25.6	26.7
∅ Total Cations	----	0.01	meq/L	47.4	33.7	58.4	26.2	26.5



Analytical Results

Sub-Matrix: WATER
 (Matrix: WATER)

				Sample ID	VKY0034C 4F55Y3NQ-31	VKY0043C 4F55Y3NQ-32	VNW223/P-3 4F55Y3NQ-33	VNW390 4F55Y3NQ-34	VNW391 4F55Y3NQ-35
				Sampling date / time	15-Jan-2025 09:45	14-Jan-2025 13:25	15-Jan-2025 11:45	14-Jan-2025 10:15	14-Jan-2025 11:40
Compound	CAS Number	LOR	Unit	EN2500866-031	EN2500866-032	EN2500866-033	EN2500866-034	EN2500866-035	EN2500866-035
				Result	Result	Result	Result	Result	Result
EN055: Ionic Balance - Continued									
∅ Ionic Balance	----	0.01	%	3.21	1.05	2.95	1.21	0.45	
EP020: Oil and Grease (O&G)									
Oil & Grease	----	5	mg/L	<5	<5	<5	<5	<5	
EP025: Oxygen - Dissolved (DO)									
Dissolved Oxygen	----	0.1	mg/L	6.6	8.0	7.4	6.8	7.6	



Analytical Results

Sub-Matrix: WATER (Matrix: WATER)				Sample ID	VNW392 4F55Y3NQ-36	VNW393 4F55Y3NQ-37	VNW394 4F55Y3NQ-38	VNW395 4F55Y3NQ-39	WR1 4F55Y3NQ-40
Sampling date / time				14-Jan-2025 12:10	14-Jan-2025 11:30	14-Jan-2025 11:00	14-Jan-2025 11:17	14-Jan-2025 09:30	
Compound	CAS Number	LOR	Unit	EN2500866-036	EN2500866-037	EN2500866-038	EN2500866-039	EN2500866-040	
				Result	Result	Result	Result	Result	
EA005P: pH by PC Titrator									
pH Value	----	0.01	pH Unit	7.57	7.68	7.45	8.06	7.30	
EA010P: Conductivity by PC Titrator									
Electrical Conductivity @ 25°C	----	1	µS/cm	3310	2930	5300	2050	25900	
EA015: Total Dissolved Solids dried at 180 ± 5 °C									
Total Dissolved Solids @180°C	----	10	mg/L	2250	1800	3640	1250	28200	
ED037P: Alkalinity by PC Titrator									
Hydroxide Alkalinity as CaCO3	DMO-210-001	1	mg/L	<1	<1	<1	<1	<1	
Carbonate Alkalinity as CaCO3	3812-32-6	1	mg/L	<1	<1	<1	<1	<1	
Bicarbonate Alkalinity as CaCO3	71-52-3	1	mg/L	609	352	357	496	603	
Total Alkalinity as CaCO3	----	1	mg/L	609	352	357	496	603	
ED041G: Sulfate (Turbidimetric) as SO4 2- by DA									
Sulfate as SO4 - Turbidimetric	14808-79-8	1	mg/L	300	205	498	147	1490	
ED045G: Chloride by Discrete Analyser									
Chloride	16887-00-6	1	mg/L	702	710	1250	348	8460	
ED093F: Dissolved Major Cations									
Calcium	7440-70-2	1	mg/L	303	169	214	56	1450	
Magnesium	7439-95-4	1	mg/L	95	32	86	28	851	
Sodium	7440-23-5	1	mg/L	364	473	933	394	4200	
Potassium	7440-09-7	1	mg/L	18	6	7	6	11	
EG020F: Dissolved Metals by ICP-MS									
Aluminium	7429-90-5	0.01	mg/L	<0.01	0.01	<0.01	<0.01	<0.01	
Antimony	7440-36-0	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	
Arsenic	7440-38-2	0.001	mg/L	<0.001	<0.001	0.004	<0.001	<0.001	
Barium	7440-39-3	0.001	mg/L	0.118	0.058	0.061	0.050	0.130	
Chromium	7440-47-3	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	
Cobalt	7440-48-4	0.001	mg/L	0.002	<0.001	0.002	<0.001	<0.001	
Lead	7439-92-1	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	



Analytical Results

Sub-Matrix: WATER
 (Matrix: WATER)

Sample ID

				VNW392 4F55Y3NQ-36	VNW393 4F55Y3NQ-37	VNW394 4F55Y3NQ-38	VNW395 4F55Y3NQ-39	WR1 4F55Y3NQ-40
Sampling date / time				14-Jan-2025 12:10	14-Jan-2025 11:30	14-Jan-2025 11:00	14-Jan-2025 11:17	14-Jan-2025 09:30
Compound	CAS Number	LOR	Unit	EN2500866-036	EN2500866-037	EN2500866-038	EN2500866-039	EN2500866-040
				Result	Result	Result	Result	Result
EG020F: Dissolved Metals by ICP-MS - Continued								
Manganese	7439-96-5	0.001	mg/L	0.220	0.176	0.283	0.056	0.080
Molybdenum	7439-98-7	0.001	mg/L	0.004	0.005	0.001	0.001	<0.001
Nickel	7440-02-0	0.001	mg/L	0.026	0.013	0.006	0.140	0.024
Selenium	7782-49-2	0.01	mg/L	<0.01	<0.01	<0.01	<0.01	<0.01
Silver	7440-22-4	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001
Strontium	7440-24-6	0.001	mg/L	2.82	2.17	2.96	0.599	32.2
Tin	7440-31-5	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001
Zinc	7440-66-6	0.005	mg/L	0.009	<0.005	0.005	<0.005	0.007
Boron	7440-42-8	0.05	mg/L	0.09	0.08	0.06	0.05	0.17
Iron	7439-89-6	0.05	mg/L	0.93	0.40	0.69	<0.05	<0.05
EG035F: Dissolved Mercury by FIMS								
Mercury	7439-97-6	0.0001	mg/L	<0.0001	<0.0001	<0.0001	<0.0001	0.0003
EK055G: Ammonia as N by Discrete Analyser								
Ammonia as N	7664-41-7	0.01	mg/L	0.31	0.44	0.21	0.65	0.15
EK057G: Nitrite as N by Discrete Analyser								
Nitrite as N	14797-65-0	0.01	mg/L	0.02	0.06	0.01	0.01	0.01
EK058G: Nitrate as N by Discrete Analyser								
Nitrate as N	14797-55-8	0.01	mg/L	0.01	0.01	<0.01	1.18	0.12
EK059G: Nitrite plus Nitrate as N (NOx) by Discrete Analyser								
Nitrite + Nitrate as N	----	0.01	mg/L	0.03	0.07	<0.01	1.19	0.13
EK067FG: Filtered Total Phosphorus as P by Discrete Analyser								
Filtered Total Phosphorus as P	----	0.01	mg/L	0.07	0.08	0.31	0.45	0.26
EK067G: Total Phosphorus as P by Discrete Analyser								
Total Phosphorus as P	----	0.01	mg/L	0.04	0.10	0.41	0.50	0.31
EN055: Ionic Balance								
∅ Total Anions	----	0.01	meq/L	38.2	31.3	52.8	22.8	282
∅ Total Cations	----	0.01	meq/L	39.2	31.8	58.5	22.4	325



Analytical Results

Sub-Matrix: WATER
 (Matrix: WATER)

				Sample ID	VNW392 4F55Y3NQ-36	VNW393 4F55Y3NQ-37	VNW394 4F55Y3NQ-38	VNW395 4F55Y3NQ-39	WR1 4F55Y3NQ-40
Sampling date / time					14-Jan-2025 12:10	14-Jan-2025 11:30	14-Jan-2025 11:00	14-Jan-2025 11:17	14-Jan-2025 09:30
Compound	CAS Number	LOR	Unit		EN2500866-036	EN2500866-037	EN2500866-038	EN2500866-039	EN2500866-040
					Result	Result	Result	Result	Result
EN055: Ionic Balance - Continued									
∅ Ionic Balance	----	0.01	%		1.31	0.74	5.17	0.88	7.19
EP020: Oil and Grease (O&G)									
Oil & Grease	----	5	mg/L		<5	<5	<5	<5	<5
EP025: Oxygen - Dissolved (DO)									
Dissolved Oxygen	----	0.1	mg/L		9.0	8.7	8.1	8.2	8.7



Analytical Results

Sub-Matrix: WATER (Matrix: WATER)				Sample ID	WR2 4F55Y3NQ-41	GW-4 4F55Y3NQ-42	GW-10 4F55Y3NQ-43	GW-15 4F55Y3NQ-44	Landreef Tap 4F55Y3NQ-45
Sampling date / time					14-Jan-2025 07:50	16-Jan-2025 08:25	15-Jan-2025 13:00	15-Jan-2025 08:45	16-Jan-2025 08:30
Compound	CAS Number	LOR	Unit	EN2500866-041	EN2500866-042	EN2500866-043	EN2500866-044	EN2500866-045	EN2500866-045
				Result	Result	Result	Result	Result	Result
EA005P: pH by PC Titrator									
pH Value	----	0.01	pH Unit	7.16	8.36	8.08	8.89	7.56	
EA010P: Conductivity by PC Titrator									
Electrical Conductivity @ 25°C	----	1	µS/cm	25800	2650	1560	689	736	
EA015: Total Dissolved Solids dried at 180 ± 5 °C									
Total Dissolved Solids @180°C	----	10	mg/L	21800	1740	1120	424	441	
ED037P: Alkalinity by PC Titrator									
Hydroxide Alkalinity as CaCO3	DMO-210-001	1	mg/L	<1	<1	<1	<1	<1	
Carbonate Alkalinity as CaCO3	3812-32-6	1	mg/L	<1	29	<1	37	<1	
Bicarbonate Alkalinity as CaCO3	71-52-3	1	mg/L	513	1020	751	254	261	
Total Alkalinity as CaCO3	----	1	mg/L	513	1040	751	291	261	
ED041G: Sulfate (Turbidimetric) as SO4 2- by DA									
Sulfate as SO4 - Turbidimetric	14808-79-8	1	mg/L	1790	<1	21	28	54	
ED045G: Chloride by Discrete Analyser									
Chloride	16887-00-6	1	mg/L	8220	309	60	29	52	
ED093F: Dissolved Major Cations									
Calcium	7440-70-2	1	mg/L	1300	6	41	5	62	
Magnesium	7439-95-4	1	mg/L	698	4	23	2	24	
Sodium	7440-23-5	1	mg/L	4220	685	324	166	68	
Potassium	7440-09-7	1	mg/L	19	3	26	4	<1	
EG020F: Dissolved Metals by ICP-MS									
Aluminium	7429-90-5	0.01	mg/L	<0.01	<0.01	<0.01	<0.01	<0.01	
Antimony	7440-36-0	0.001	mg/L	<0.001	<0.001	0.004	<0.001	<0.001	
Arsenic	7440-38-2	0.001	mg/L	<0.001	0.002	<0.001	0.002	<0.001	
Barium	7440-39-3	0.001	mg/L	0.174	0.272	0.081	0.020	0.018	
Chromium	7440-47-3	0.001	mg/L	0.001	<0.001	<0.001	<0.001	<0.001	
Cobalt	7440-48-4	0.001	mg/L	0.014	<0.001	<0.001	<0.001	<0.001	
Lead	7439-92-1	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	



Analytical Results

Sub-Matrix: WATER
 (Matrix: WATER)

Sample ID

				WR2 4F55Y3NQ-41	GW-4 4F55Y3NQ-42	GW-10 4F55Y3NQ-43	GW-15 4F55Y3NQ-44	Landreef Tap 4F55Y3NQ-45
Sampling date / time				14-Jan-2025 07:50	16-Jan-2025 08:25	15-Jan-2025 13:00	15-Jan-2025 08:45	16-Jan-2025 08:30
Compound	CAS Number	LOR	Unit	EN2500866-041	EN2500866-042	EN2500866-043	EN2500866-044	EN2500866-045
				Result	Result	Result	Result	Result
EG020F: Dissolved Metals by ICP-MS - Continued								
Manganese	7439-96-5	0.001	mg/L	1.12	0.008	0.023	0.010	<0.001
Molybdenum	7439-98-7	0.001	mg/L	0.020	<0.001	0.001	0.003	<0.001
Nickel	7440-02-0	0.001	mg/L	0.158	<0.001	0.003	<0.001	<0.001
Selenium	7782-49-2	0.01	mg/L	<0.01	<0.01	<0.01	<0.01	<0.01
Silver	7440-22-4	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001
Strontium	7440-24-6	0.001	mg/L	30.7	0.164	1.01	0.219	0.628
Tin	7440-31-5	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001
Zinc	7440-66-6	0.005	mg/L	0.011	0.029	0.116	<0.005	<0.005
Boron	7440-42-8	0.05	mg/L	0.12	0.14	0.14	<0.05	<0.05
Iron	7439-89-6	0.05	mg/L	1.43	0.25	<0.05	<0.05	<0.05
EG035F: Dissolved Mercury by FIMS								
Mercury	7439-97-6	0.0001	mg/L	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001
EK055G: Ammonia as N by Discrete Analyser								
Ammonia as N	7664-41-7	0.01	mg/L	0.23	0.51	0.11	0.10	0.02
EK057G: Nitrite as N by Discrete Analyser								
Nitrite as N	14797-65-0	0.01	mg/L	<0.01	<0.01	<0.01	0.02	<0.01
EK058G: Nitrate as N by Discrete Analyser								
Nitrate as N	14797-55-8	0.01	mg/L	<0.01	<0.01	4.02	<0.01	0.69
EK059G: Nitrite plus Nitrate as N (NOx) by Discrete Analyser								
Nitrite + Nitrate as N	----	0.01	mg/L	<0.01	<0.01	4.02	0.02	0.69
EK067FG: Filtered Total Phosphorus as P by Discrete Analyser								
Filtered Total Phosphorus as P	----	0.01	mg/L	0.39	0.04	0.17	0.13	0.07
EK067G: Total Phosphorus as P by Discrete Analyser								
Total Phosphorus as P	----	0.01	mg/L	0.37	0.11	0.17	0.10	0.06
EN055: Ionic Balance								
∅ Total Anions	----	0.01	meq/L	279	29.5	17.1	7.22	7.80
∅ Total Cations	----	0.01	meq/L	306	30.5	18.7	7.74	8.03



Analytical Results

Sub-Matrix: WATER
 (Matrix: WATER)

Sample ID

				WR2 4F55Y3NQ-41	GW-4 4F55Y3NQ-42	GW-10 4F55Y3NQ-43	GW-15 4F55Y3NQ-44	Landreef Tap 4F55Y3NQ-45
Sampling date / time				14-Jan-2025 07:50	16-Jan-2025 08:25	15-Jan-2025 13:00	15-Jan-2025 08:45	16-Jan-2025 08:30
Compound	CAS Number	LOR	Unit	EN2500866-041	EN2500866-042	EN2500866-043	EN2500866-044	EN2500866-045
				Result	Result	Result	Result	Result
EN055: Ionic Balance - Continued								
∅ Ionic Balance	----	0.01	%	4.60	1.68	4.36	3.49	1.40
EP020: Oil and Grease (O&G)								
Oil & Grease	----	5	mg/L	<5	<5	<5	<5	<5
EP025: Oxygen - Dissolved (DO)								
Dissolved Oxygen	----	0.1	mg/L	8.7	6.7	8.5	8.4	8.7



Analytical Results

Sub-Matrix: WATER (Matrix: WATER)				Sample ID	GW97164 4F55Y3NQ-46	VKY GW Duplicate 1 4F55Y3NQ-47	VKY GW Duplicate 2 4F55Y3NQ-48	VKY-GW-Blank 4F55Y3NQ-49	VKY Lab Split Dup 1 4F55Y3NQ-50
Sampling date / time				16-Jan-2025 08:00	15-Jan-2025 08:45	15-Jan-2025 08:25	16-Jan-2025 08:40	15-Jan-2025 08:45	
Compound	CAS Number	LOR	Unit	EN2500866-046	EN2500866-047	EN2500866-048	EN2500866-049	EN2500866-050	
				Result	Result	Result	Result	Result	
EA005P: pH by PC Titrator									
pH Value	----	0.01	pH Unit	7.50	8.79	7.24	5.97	8.89	
EA010P: Conductivity by PC Titrator									
Electrical Conductivity @ 25°C	----	1	µS/cm	611	678	4660	<1	681	
EA015: Total Dissolved Solids dried at 180 ± 5 °C									
Total Dissolved Solids @180°C	----	10	mg/L	378	374	3000	<10	396	
ED037P: Alkalinity by PC Titrator									
Hydroxide Alkalinity as CaCO3	DMO-210-001	1	mg/L	<1	<1	<1	<1	<1	
Carbonate Alkalinity as CaCO3	3812-32-6	1	mg/L	<1	32	<1	<1	39	
Bicarbonate Alkalinity as CaCO3	71-52-3	1	mg/L	251	259	111	<1	251	
Total Alkalinity as CaCO3	----	1	mg/L	251	291	111	<1	290	
ED041G: Sulfate (Turbidimetric) as SO4 2- by DA									
Sulfate as SO4 - Turbidimetric	14808-79-8	1	mg/L	30	29	2	<1	28	
ED045G: Chloride by Discrete Analyser									
Chloride	16887-00-6	1	mg/L	33	29	1420	<1	28	
ED093F: Dissolved Major Cations									
Calcium	7440-70-2	1	mg/L	58	5	214	<1	5	
Magnesium	7439-95-4	1	mg/L	21	2	47	<1	2	
Sodium	7440-23-5	1	mg/L	52	164	664	<1	161	
Potassium	7440-09-7	1	mg/L	<1	4	11	<1	4	
EG020F: Dissolved Metals by ICP-MS									
Aluminium	7429-90-5	0.01	mg/L	<0.01	<0.01	<0.01	<0.01	<0.01	
Antimony	7440-36-0	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	
Arsenic	7440-38-2	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	
Barium	7440-39-3	0.001	mg/L	0.019	0.019	0.114	<0.001	0.019	
Chromium	7440-47-3	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	
Cobalt	7440-48-4	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	
Lead	7439-92-1	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	



Analytical Results

Sub-Matrix: WATER (Matrix: WATER)				Sample ID	GW97164 4F55Y3NQ-46	VKY GW Duplicate 1 4F55Y3NQ-47	VKY GW Duplicate 2 4F55Y3NQ-48	VKY-GW-Blank 4F55Y3NQ-49	VKY Lab Split Dup 1 4F55Y3NQ-50
Sampling date / time				16-Jan-2025 08:00	15-Jan-2025 08:45	15-Jan-2025 08:25	16-Jan-2025 08:40	15-Jan-2025 08:45	
Compound	CAS Number	LOR	Unit	EN2500866-046	EN2500866-047	EN2500866-048	EN2500866-049	EN2500866-050	
				Result	Result	Result	Result	Result	
EG020F: Dissolved Metals by ICP-MS - Continued									
Manganese	7439-96-5	0.001	mg/L	<0.001	0.010	1.07	<0.001	0.010	
Molybdenum	7439-98-7	0.001	mg/L	<0.001	0.002	<0.001	<0.001	0.002	
Nickel	7440-02-0	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	
Selenium	7782-49-2	0.01	mg/L	<0.01	<0.01	<0.01	<0.01	<0.01	
Silver	7440-22-4	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	
Strontium	7440-24-6	0.001	mg/L	0.586	0.215	3.20	<0.001	0.212	
Tin	7440-31-5	0.001	mg/L	<0.001	<0.001	<0.001	<0.001	<0.001	
Zinc	7440-66-6	0.005	mg/L	<0.005	<0.005	0.048	<0.005	<0.005	
Boron	7440-42-8	0.05	mg/L	<0.05	<0.05	0.14	<0.05	<0.05	
Iron	7439-89-6	0.05	mg/L	<0.05	<0.05	10.4	<0.05	<0.05	
EG035F: Dissolved Mercury by FIMS									
Mercury	7439-97-6	0.0001	mg/L	<0.0001	<0.0001	<0.0001	<0.0001	<0.0001	
EK055G: Ammonia as N by Discrete Analyser									
Ammonia as N	7664-41-7	0.01	mg/L	<0.01	0.10	1.48	0.03	0.10	
EK057G: Nitrite as N by Discrete Analyser									
Nitrite as N	14797-65-0	0.01	mg/L	0.02	<0.01	0.02	<0.01	<0.01	
EK058G: Nitrate as N by Discrete Analyser									
Nitrate as N	14797-55-8	0.01	mg/L	0.20	<0.01	0.02	<0.01	<0.01	
EK059G: Nitrite plus Nitrate as N (NOx) by Discrete Analyser									
Nitrite + Nitrate as N	----	0.01	mg/L	0.22	<0.01	0.04	<0.01	<0.01	
EK067FG: Filtered Total Phosphorus as P by Discrete Analyser									
Filtered Total Phosphorus as P	----	0.01	mg/L	0.06	0.14	0.01	<0.01	0.08	
EK067G: Total Phosphorus as P by Discrete Analyser									
Total Phosphorus as P	----	0.01	mg/L	0.04	0.23	0.02	<0.01	0.10	
EN055: Ionic Balance									
∅ Total Anions	----	0.01	meq/L	6.57	7.24	42.3	<0.01	7.17	
∅ Total Cations	----	0.01	meq/L	6.88	7.65	43.7	<0.01	7.52	



Analytical Results

Sub-Matrix: WATER
 (Matrix: WATER)

Sample ID

				GW97164 4F55Y3NQ-46	VKY GW Duplicate 1 4F55Y3NQ-47	VKY GW Duplicate 2 4F55Y3NQ-48	VKY-GW-Blank 4F55Y3NQ-49	VKY Lab Split Dup 1 4F55Y3NQ-50
Sampling date / time				16-Jan-2025 08:00	15-Jan-2025 08:45	15-Jan-2025 08:25	16-Jan-2025 08:40	15-Jan-2025 08:45
Compound	CAS Number	LOR	Unit	EN2500866-046	EN2500866-047	EN2500866-048	EN2500866-049	EN2500866-050
				Result	Result	Result	Result	Result
EN055: Ionic Balance - Continued								
∅ Ionic Balance	----	0.01	%	2.33	2.78	1.62	----	2.40
EP020: Oil and Grease (O&G)								
Oil & Grease	----	5	mg/L	<5	<5	<5	<5	<5
EP025: Oxygen - Dissolved (DO)								
Dissolved Oxygen	----	0.1	mg/L	8.8	9.0	8.1	9.0	8.5



Analytical Results

Sub-Matrix: WATER (Matrix: WATER)		Sample ID		VKY Lab Split Dup 2 4F55Y3NQ-51	SB11	----	----	----
		Sampling date / time		15-Jan-2025 08:45	13-Jan-2025 15:19	----	----	----
Compound	CAS Number	LOR	Unit	EN2500866-051	EN2500866-052	-----	-----	-----
				Result	Result	----	----	----
EA005P: pH by PC Titrator								
pH Value	----	0.01	pH Unit	6.99	7.70	----	----	----
EA010P: Conductivity by PC Titrator								
Electrical Conductivity @ 25°C	----	1	µS/cm	4650	1020	----	----	----
EA015: Total Dissolved Solids dried at 180 ± 5 °C								
Total Dissolved Solids @180°C	----	10	mg/L	3290	688	----	----	----
ED037P: Alkalinity by PC Titrator								
Hydroxide Alkalinity as CaCO3	DMO-210-001	1	mg/L	<1	<1	----	----	----
Carbonate Alkalinity as CaCO3	3812-32-6	1	mg/L	<1	<1	----	----	----
Bicarbonate Alkalinity as CaCO3	71-52-3	1	mg/L	75	454	----	----	----
Total Alkalinity as CaCO3	----	1	mg/L	75	454	----	----	----
ED041G: Sulfate (Turbidimetric) as SO4 2- by DA								
Sulfate as SO4 - Turbidimetric	14808-79-8	1	mg/L	<1	106	----	----	----
ED045G: Chloride by Discrete Analyser								
Chloride	16887-00-6	1	mg/L	1370	35	----	----	----
ED093F: Dissolved Major Cations								
Calcium	7440-70-2	1	mg/L	217	35	----	----	----
Magnesium	7439-95-4	1	mg/L	48	22	----	----	----
Sodium	7440-23-5	1	mg/L	672	205	----	----	----
Potassium	7440-09-7	1	mg/L	11	1	----	----	----
EG020F: Dissolved Metals by ICP-MS								
Aluminium	7429-90-5	0.01	mg/L	<0.01	<0.01	----	----	----
Antimony	7440-36-0	0.001	mg/L	<0.001	<0.001	----	----	----
Arsenic	7440-38-2	0.001	mg/L	<0.001	<0.001	----	----	----
Barium	7440-39-3	0.001	mg/L	0.115	0.062	----	----	----
Chromium	7440-47-3	0.001	mg/L	<0.001	<0.001	----	----	----
Cobalt	7440-48-4	0.001	mg/L	<0.001	<0.001	----	----	----
Lead	7439-92-1	0.001	mg/L	<0.001	<0.001	----	----	----



Analytical Results

Sub-Matrix: WATER (Matrix: WATER)				Sample ID	VKY Lab Split Dup 2 4F55Y3NQ-51	SB11	----	----	----
Sampling date / time				15-Jan-2025 08:45	13-Jan-2025 15:19	----	----	----	
Compound	CAS Number	LOR	Unit	EN2500866-051	EN2500866-052	-----	-----	-----	
				Result	Result	----	----	----	
EG020F: Dissolved Metals by ICP-MS - Continued									
Manganese	7439-96-5	0.001	mg/L	1.09	0.142	----	----	----	
Molybdenum	7439-98-7	0.001	mg/L	<0.001	<0.001	----	----	----	
Nickel	7440-02-0	0.001	mg/L	<0.001	<0.001	----	----	----	
Selenium	7782-49-2	0.01	mg/L	<0.01	<0.01	----	----	----	
Silver	7440-22-4	0.001	mg/L	<0.001	<0.001	----	----	----	
Strontium	7440-24-6	0.001	mg/L	3.22	0.844	----	----	----	
Tin	7440-31-5	0.001	mg/L	<0.001	<0.001	----	----	----	
Zinc	7440-66-6	0.005	mg/L	0.040	<0.005	----	----	----	
Boron	7440-42-8	0.05	mg/L	0.13	0.08	----	----	----	
Iron	7439-89-6	0.05	mg/L	9.92	<0.05	----	----	----	
EG035F: Dissolved Mercury by FIMS									
Mercury	7439-97-6	0.0001	mg/L	<0.0001	<0.0001	----	----	----	
EK055G: Ammonia as N by Discrete Analyser									
Ammonia as N	7664-41-7	0.01	mg/L	1.53	0.16	----	----	----	
EK057G: Nitrite as N by Discrete Analyser									
Nitrite as N	14797-65-0	0.01	mg/L	0.01	<0.01	----	----	----	
EK058G: Nitrate as N by Discrete Analyser									
Nitrate as N	14797-55-8	0.01	mg/L	0.04	0.43	----	----	----	
EK059G: Nitrite plus Nitrate as N (NOx) by Discrete Analyser									
Nitrite + Nitrate as N	----	0.01	mg/L	0.05	0.43	----	----	----	
EK067FG: Filtered Total Phosphorus as P by Discrete Analyser									
Filtered Total Phosphorus as P	----	0.01	mg/L	0.01	0.07	----	----	----	
EK067G: Total Phosphorus as P by Discrete Analyser									
Total Phosphorus as P	----	0.01	mg/L	0.04	0.12	----	----	----	
EN055: Ionic Balance									
∅ Total Anions	----	0.01	meq/L	40.1	12.3	----	----	----	
∅ Total Cations	----	0.01	meq/L	44.3	12.5	----	----	----	



Analytical Results

Sub-Matrix: WATER (Matrix: WATER)			Sample ID	VKY Lab Split Dup 2 4F55Y3NQ-51	SB11	----	----	----
Sampling date / time			15-Jan-2025 08:45	13-Jan-2025 15:19	----	----	----	
Compound	CAS Number	LOR	Unit	EN2500866-051	EN2500866-052	-----	-----	-----
				Result	Result	----	----	----
EN055: Ionic Balance - Continued								
∅ Ionic Balance	----	0.01	%	4.91	0.95	----	----	----
EP020: Oil and Grease (O&G)								
Oil & Grease	----	5	mg/L	<5	<5	----	----	----
EP025: Oxygen - Dissolved (DO)								
Dissolved Oxygen	----	0.1	mg/L	8.2	8.7	----	----	----

Inter-Laboratory Testing

Analysis conducted by ALS Sydney, NATA accreditation no. 825, site no. 10911 (Chemistry / Biology).

(WATER) EG020F: Dissolved Metals by ICP-MS

(WATER) EP025: Oxygen - Dissolved (DO)

(WATER) EG035F: Dissolved Mercury by FIMS

(WATER) EK067FG: Filtered Total Phosphorus as P by Discrete Analyser

(WATER) EA005P: pH by PC Titrator

(WATER) ED093F: Dissolved Major Cations

(WATER) EN055: Ionic Balance

(WATER) ED045G: Chloride by Discrete Analyser

(WATER) ED041G: Sulfate (Turbidimetric) as SO₄²⁻ by DA

(WATER) ED037P: Alkalinity by PC Titrator

(WATER) EK055G: Ammonia as N by Discrete Analyser

(WATER) EA010P: Conductivity by PC Titrator

(WATER) EA015: Total Dissolved Solids dried at 180 ± 5 °C

(WATER) EP020: Oil and Grease (O&G)

(WATER) EK057G: Nitrite as N by Discrete Analyser

(WATER) EK058G: Nitrate as N by Discrete Analyser

(WATER) EK059G: Nitrite plus Nitrate as N (NO_x) by Discrete Analyser

(WATER) EK067G: Total Phosphorus as P by Discrete Analyser

Client: Whitehaven Coal - Vickery Project

Sampled By: *GA*

Project: Quarterly Groundwater Sampling (Jan, Apr, Jul, Oct)

Signed: *GA*

Site	Date	Time	Logger Downloaded	Logger Batteries Replaced	Bore Total Depth (m)	Standpipe TOC to Ground (m) height	Depth to Water (m)	Typical Depth (m)	Sampling Method	Field pH	Field EC	Temp. (°C)	Redox (mV)	Odour	Water Turbidity	Water Colour	Monitoring bore in good condition (note any damage under comments)	Photo taken	Bottles				Comments	
																			500ml GP	PP (filt.)	PP	PG		
GW-4									GS LF HF HS						C ST	C O Bk Bn Gn Gy	Y / N	Y / N	1	1	1	1		
GW-10									GS LF HF HS						C ST	C O Bk Bn Gn Gy	Y / N	Y / N	1	1	1	1		
GW-15									GS LF HF HS						C ST	C O Bk Bn Gn Gy	Y / N	Y / N	1	1	1	1		
GW971614									GS LF HF HS						C ST	C O Bk Bn Gn Gy	Y / N	Y / N	1	1	1	1		
<i>GW971400</i>	<i>24-1-25</i>	<i>0759</i>	<i>N/A</i>	<i>N/A</i>	<i>N/A</i>	<i>0.85</i>	<i>10.64</i>	<i>-</i>	<i>PUMP</i>	<i>6.97</i>	<i>2.79ms</i>	<i>20.9</i>	<i>-77</i>	<i>NEL</i>	<i>(C)</i>	<i>(C)</i>	<i>(Y/N)</i>	<i>(Y/N)</i>	<i>(1)</i>	<i>(1)</i>	<i>(1)</i>	<i>(1)</i>		
QA Samples																								
VKY GW Duplicate 1			Duplicate 1 Taken From:.....						GS LF HF HS						C ST	C O Bk Bn Gn Gy				1	1	1	1	
VKY GW Duplicate 2			Duplicate 2 Taken From:.....						GS LF HF HS						C ST	C O Bk Bn Gn Gy				1	1	1	1	
VKY GW Blank															C ST	C O Bk Bn Gn Gy				1	1	1	1	
Split Duplicate samples to be split into two bottle sets. Please label one set as 'Split Dup (1/2) ALS' and one as 'Split Dup (1/2) Eurofins'																								
VKY GW Lab Split Dup 1			Site Split Duplicate 1 Taken From:.....						GS LF HF HS						C ST	C O Bk Bn Gn Gy				2	2	2	2	
VKY GW Lab Split Dup 2			Site Split Duplicate 2 Taken From:.....						GS LF HF HS						C ST	C O Bk Bn Gn Gy				2	2	2	2	
																		Total Bottles:	56	56	56	56		

ML = Mini Logger
 QL = Quattro Logger
 VL = V-Logger
 WS = Win-Situ (Rugged Troll)
 RST = RST Logger

GS = Grab Sample with Baller,
 LF = Low Flow Sampling,
 HF = High Volume Pumping,
 HS = Hydrasilieve (CIRCLE)

Total Bottles: 56 56 56 56

4

CBased Sampling Method: M105 - Groundwater Sampling
 Turbidity: C=Clear, S= Slight, T=Turbid (CIRCLE)
 Colour: C=Colourless, O=Orange, Bk = Black, Bn=Brown, Gn=Green, Gy= Grey (CIRCLE)
 Flow Rate: Still -> Trickle -> Steady -> Fast
 Bottles: GP = Green Plastic, RP = Red Plastic, (filt. = filtered), PP = Purple Plastic, BP = Blue Plastic, YP = Yellow Plastic,
 OG = Orange Glass, PG = Purple Glass, BG = Brown Glass, MP = Maroon Plastic, PV = Purple Vial, ST = Sterile

pH 7 buffer check required every 10 samples - If the Difference is over 0.2, recalibrate using Form F305 (2 point calibration)

Date	Time	pH reading	Recalibration required? (Yes/No)	Date	Time	pH reading	Recalibration required? (Yes/No)
			Yes/No				Yes/No
			Yes/No				Yes/No

Transport conditions

Esky with ice
 Other (Provide details)

LAB USE ONLY RECEIVED (DATE/TIME): 28-01-25 APPROPRIATELY SEALED?: YES NO TEMPERATURE: 2.0 JOB #: SIGNED: IR

LABORATORY	ALS Newcastle 5/585 Maitland Road Mayfield West 2304 NSW
SAMPLERS	CBased Environmental
QUOTE #	SYBQ-403-21 v4
PO #	

SITE	Vickery
PROJECT	Vickery Quarterly Groundwaters
PROJECT MANAGER	
COMPANY	CBased Environmental Pty Ltd PO Box 245 Cessnock NSW 2325
CONTACT PERSON	Marnie Blake
CONTACT NUMBER	
CONTACT FAX	
CONTACT EMAILS	monitoringresults@cbased.com.au
INVOICING EMAILS	accounts@cbased.com.au
RESULT EMAILS	monitoringresults@cbased.com.au, inxpreservemail@whitehavencoal.com.au, vickeryenvironment@whitehavencoal.com.au

ANALYSIS REQUIRED	GENERAL INSTRUCTIONS
A. Ammonia as N B. Bicarbonate Alkalinity as CaCO3 C. Calcium (dissolved) D. Carbonate Alkalinity as CaCO3 E. DO F. EC G. Hydroxide Alkalinity as CaCO3 H. Ionic balance I. Nitrate as N J. Nitrite + Nitrate as N K. Nitrite as N L. Oil and Grease M. pH N. Sodium (Dissolved) O. TDS	

#	SAMPLE NAME	DATE/TIME	SAMPLE ID	CONTAINERS	MATRIX	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	SAMPLE INSTRUCTIONS
1	GW971400	2025-01-24 07:59	U4UYK3VY-1	4	Water	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	

ALS PLU

Environmental Division
 Newcastle
 Work Order Reference
EN2501508





CERTIFICATE OF ANALYSIS

Work Order : EN2501508
Client : CBASED ENVIRONMENTAL PTY LTD
Contact : All Deliverables
Address : Unit 3 2 Enterprise Cres
Singleton NSW 2330
Telephone : +61 02 6571 3334
Project : Vickery Quarterly Groundwaters
Order number : ----
C-O-C number : ----
Sampler : CBased Environmental
Site : Vickery
Quote number : SYBQ/403/21v4 and PLANNED EVENTS
No. of samples received : 1
No. of samples analysed : 1

Page : 1 of 5
Laboratory : Environmental Division Newcastle
Contact :
Address : 5/585 Maitland Road Mayfield West NSW Australia 2304
Telephone : +61 2 4014 2500
Date Samples Received : 28-Jan-2025 15:55
Date Analysis Commenced : 28-Jan-2025
Issue Date : 03-Feb-2025 09:10



This report supersedes any previous report(s) with this reference. Results apply to the sample(s) as submitted, unless the sampling was conducted by ALS. This document shall not be reproduced, except in full.

This Certificate of Analysis contains the following information:

- General Comments
- Analytical Results

Additional information pertinent to this report will be found in the following separate attachments: Quality Control Report, QA/QC Compliance Assessment to assist with Quality Review and Sample Receipt Notification.

Signatories

This document has been electronically signed by the authorized signatories below. Electronic signing is carried out in compliance with procedures specified in 21 CFR Part 11.

<i>Signatories</i>	<i>Position</i>	<i>Accreditation Category</i>
Allan Brown	Laboratory Technician	Newcastle - Inorganics, Mayfield West, NSW
Ankit Joshi	Senior Chemist - Inorganics	Sydney Inorganics, Smithfield, NSW



General Comments

The analytical procedures used by ALS have been developed from established internationally recognised procedures such as those published by the USEPA, APHA, AS and NEPM. In house developed procedures are fully validated and are often at the client request.

Where moisture determination has been performed, results are reported on a dry weight basis.

Where a reported less than (<) result is higher than the LOR, this may be due to primary sample extract/digestate dilution and/or insufficient sample for analysis.

Where the LOR of a reported result differs from standard LOR, this may be due to high moisture content, insufficient sample (reduced weight employed) or matrix interference.

When sampling time information is not provided by the client, sampling dates are shown without a time component. In these instances, the time component has been assumed by the laboratory for processing purposes.

Where a result is required to meet compliance limits the associated uncertainty must be considered. Refer to the ALS Contract for details.

Key : CAS Number = CAS registry number from database maintained by Chemical Abstracts Services. The Chemical Abstracts Service is a division of the American Chemical Society.
LOR = Limit of reporting
^ = This result is computed from individual analyte detections at or above the level of reporting
ø = ALS is not NATA accredited for these tests.
~ = Indicates an estimated value.

- As per QWI – EN55-3 Data Interpreting Procedures, Ionic balances are typically calculated using Major Anions - Chloride, Alkalinity and Sulfate; and Major Cations - Calcium, Magnesium, Potassium and Sodium. Where applicable and dependent upon sample matrix, the Ionic Balance may also include the additional contribution of Ammonia, Dissolved Metals by ICPMS and H+ to the Cations and Nitrate, SiO₂ and Fluoride to the Anions.
- ED093: It is recognised that total concentration is less than dissolved for some metal analytes. However, the difference is within experimental variation of the methods.
- TDS by method EA-015 may bias high due to the presence of fine particulate matter, which may pass through the prescribed GF/C paper.
- Sodium Adsorption Ratio (where reported): Where results for Na, Ca or Mg are <LOR, a concentration at half the reported LOR is incorporated into the SAR calculation. This represents a conservative approach for Na relative to the assumption that <LOR = zero concentration and a conservative approach for Ca & Mg relative to the assumption that <LOR is equivalent to the LOR concentration.
- ED045G: The presence of Thiocyanate, Thiosulfate and Sulfite can positively contribute to the chloride result, thereby may bias results higher than expected. Results should be scrutinised accordingly.



Analytical Results

Sub-Matrix: WATER (Matrix: WATER)		Sample ID		GW971400 U4UYK3VY-1	----	----	----	----
Sampling date / time		24-Jan-2025 07:59		----	----	----	----	----
Compound	CAS Number	LOR	Unit	EN2501508-001	-----	-----	-----	-----
				Result	----	----	----	----
EA005P: pH by PC Titrator								
pH Value	----	0.01	pH Unit	7.08	----	----	----	----
EA010P: Conductivity by PC Titrator								
Electrical Conductivity @ 25°C	----	1	µS/cm	2810	----	----	----	----
EA015: Total Dissolved Solids dried at 180 ± 5 °C								
Total Dissolved Solids @180°C	----	10	mg/L	2100	----	----	----	----
ED037P: Alkalinity by PC Titrator								
Hydroxide Alkalinity as CaCO3	DMO-210-001	1	mg/L	<1	----	----	----	----
Carbonate Alkalinity as CaCO3	3812-32-6	1	mg/L	<1	----	----	----	----
Bicarbonate Alkalinity as CaCO3	71-52-3	1	mg/L	470	----	----	----	----
Total Alkalinity as CaCO3	----	1	mg/L	470	----	----	----	----
ED041G: Sulfate (Turbidimetric) as SO4 2- by DA								
Sulfate as SO4 - Turbidimetric	14808-79-8	1	mg/L	477	----	----	----	----
ED045G: Chloride by Discrete Analyser								
Chloride	16887-00-6	1	mg/L	379	----	----	----	----
ED093F: Dissolved Major Cations								
Calcium	7440-70-2	1	mg/L	229	----	----	----	----
Magnesium	7439-95-4	1	mg/L	76	----	----	----	----
Sodium	7440-23-5	1	mg/L	283	----	----	----	----
Potassium	7440-09-7	1	mg/L	2	----	----	----	----
ED093T: Total Major Cations								
Calcium	7440-70-2	1	mg/L	208	----	----	----	----
Magnesium	7439-95-4	1	mg/L	84	----	----	----	----
Sodium	7440-23-5	1	mg/L	314	----	----	----	----
Potassium	7440-09-7	1	mg/L	2	----	----	----	----
EG020F: Dissolved Metals by ICP-MS								
Aluminium	7429-90-5	0.01	mg/L	<0.01	----	----	----	----
Antimony	7440-36-0	0.001	mg/L	<0.001	----	----	----	----



Analytical Results

Sub-Matrix: WATER (Matrix: WATER)				Sample ID	GW971400 U4UYK3VY-1	----	----	----	----
Sampling date / time				24-Jan-2025 07:59	----	----	----	----	----
Compound	CAS Number	LOR	Unit	EN2501508-001	-----	-----	-----	-----	-----
				Result	----	----	----	----	----
EG020F: Dissolved Metals by ICP-MS - Continued									
Arsenic	7440-38-2	0.001	mg/L	<0.001	----	----	----	----	----
Barium	7440-39-3	0.001	mg/L	0.055	----	----	----	----	----
Chromium	7440-47-3	0.001	mg/L	<0.001	----	----	----	----	----
Cobalt	7440-48-4	0.001	mg/L	<0.001	----	----	----	----	----
Lead	7439-92-1	0.001	mg/L	<0.001	----	----	----	----	----
Manganese	7439-96-5	0.001	mg/L	0.024	----	----	----	----	----
Molybdenum	7439-98-7	0.001	mg/L	<0.001	----	----	----	----	----
Nickel	7440-02-0	0.001	mg/L	0.018	----	----	----	----	----
Selenium	7782-49-2	0.01	mg/L	<0.01	----	----	----	----	----
Silver	7440-22-4	0.001	mg/L	<0.001	----	----	----	----	----
Strontium	7440-24-6	0.001	mg/L	1.86	----	----	----	----	----
Tin	7440-31-5	0.001	mg/L	<0.001	----	----	----	----	----
Zinc	7440-66-6	0.005	mg/L	<0.005	----	----	----	----	----
Boron	7440-42-8	0.05	mg/L	0.05	----	----	----	----	----
Iron	7439-89-6	0.05	mg/L	0.15	----	----	----	----	----
EG035F: Dissolved Mercury by FIMS									
Mercury	7439-97-6	0.0001	mg/L	<0.0001	----	----	----	----	----
EK055G: Ammonia as N by Discrete Analyser									
Ammonia as N	7664-41-7	0.01	mg/L	0.01	----	----	----	----	----
EK057G: Nitrite as N by Discrete Analyser									
Nitrite as N	14797-65-0	0.01	mg/L	<0.01	----	----	----	----	----
EK058G: Nitrate as N by Discrete Analyser									
Nitrate as N	14797-55-8	0.01	mg/L	3.58	----	----	----	----	----
EK059G: Nitrite plus Nitrate as N (NOx) by Discrete Analyser									
Nitrite + Nitrate as N	----	0.01	mg/L	3.58	----	----	----	----	----
EK067G: Total Phosphorus as P by Discrete Analyser									
Total Phosphorus as P	----	0.01	mg/L	0.18	----	----	----	----	----



Analytical Results

Sub-Matrix: WATER (Matrix: WATER)				Sample ID	GW971400 U4UYK3VY-1	----	----	----	----
Sampling date / time				24-Jan-2025 07:59	----	----	----	----	----
Compound	CAS Number	LOR	Unit	EN2501508-001	-----	-----	-----	-----	-----
				Result	----	----	----	----	----
EK071FG: Dissolved Reactive Phosphorus as P by DA									
Dissolved Reactive Phosphorus as P	----	0.01	mg/L	<0.01	----	----	----	----	----
EN055: Ionic Balance									
∅ Total Anions	----	0.01	meq/L	30.0	----	----	----	----	----
∅ Total Cations	----	0.01	meq/L	30.0	----	----	----	----	----
∅ Ionic Balance	----	0.01	%	0.05	----	----	----	----	----
EP020: Oil and Grease (O&G)									
Oil & Grease	----	5	mg/L	<5	----	----	----	----	----
EP025: Oxygen - Dissolved (DO)									
Dissolved Oxygen	----	0.1	mg/L	9.2	----	----	----	----	----

Inter-Laboratory Testing

Analysis conducted by ALS Sydney, NATA accreditation no. 825, site no. 10911 (Chemistry / Biology).

- (WATER) ED037P: Alkalinity by PC Titrator
- (WATER) ED093F: Dissolved Major Cations
- (WATER) EN055: Ionic Balance
- (WATER) ED045G: Chloride by Discrete Analyser
- (WATER) ED041G: Sulfate (Turbidimetric) as SO4 2- by DA
- (WATER) ED093T: Total Major Cations
- (WATER) EK067G: Total Phosphorus as P by Discrete Analyser
- (WATER) EG020F: Dissolved Metals by ICP-MS
- (WATER) EG035F: Dissolved Mercury by FIMS
- (WATER) EK057G: Nitrite as N by Discrete Analyser
- (WATER) EK058G: Nitrate as N by Discrete Analyser
- (WATER) EK059G: Nitrite plus Nitrate as N (NOx) by Discrete Analyser
- (WATER) EP020: Oil and Grease (O&G)
- (WATER) EA015: Total Dissolved Solids dried at 180 ± 5 °C
- (WATER) EK071FG: Dissolved Reactive Phosphorus as P by DA
- (WATER) EK055G: Ammonia as N by Discrete Analyser
- (WATER) EP025: Oxygen - Dissolved (DO)
- (WATER) EA010P: Conductivity by PC Titrator

Cbased Environmental Pty Ltd
Unit 3, 2 Enterprise Crescent
Singleton
NSW 2330



NATA Accredited
Accreditation Number 1261
Site Number 18217

Accredited for compliance with ISO/IEC 17025 – Testing
 NATA is a signatory to the ILAC Mutual Recognition
 Arrangement for the mutual recognition of the
 equivalence of testing, medical testing, calibration,
 inspection, proficiency testing scheme providers and
 reference materials producers reports and certificates.

Attention: **Marni Blake**

Report **1178740-W**
Project name **VICKERY QTRLY GW**
Received Date **Jan 17, 2025**

Client Sample ID			VKY Lab Split Dup 1 Eurofins	VKY Lab Split Dup 2 Eurofins
Sample Matrix			Water	Water
Eurofins Sample No.			N25-Ja0025645	N25-Ja0025646
Date Sampled			Jan 15, 2025	Jan 15, 2025
Test/Reference	LOR	Unit		
Ammonia (as N)	0.01	mg/L	0.09	5.8
Chloride	1	mg/L	1600	24
Conductivity (at 25 °C)	10	uS/cm	690	5000
Oil & Grease (HEM)	10	mg/L	< 10	< 10
pH (at 25 °C)	0.1	pH Units	9.2	7.2
Phosphate total (as P)	0.01	mg/L	0.10	0.03
Sulphate (as SO4)	2	mg/L	< 2	28
Total Dissolved Solids Dried at 180 °C ± 2 °C	10	mg/L	410	^{Q19} 3500
Alkalinity (speciated)				
Bicarbonate Alkalinity (as CaCO3)	20	mg/L	250	190
Carbonate Alkalinity (as CaCO3)	20	mg/L	71	< 20
Hydroxide Alkalinity (as CaCO3)	20	mg/L	< 20	< 20
Total Alkalinity (as CaCO3)	20	mg/L	320	190
Eurofins Suite B19B: NO3/NO2/NOx				
Nitrate & Nitrite (as N)	0.05	mg/L	0.06	< 0.05
Nitrate (as N)	0.02	mg/L	0.04	0.04
Nitrite (as N)	0.02	mg/L	0.02	< 0.02
Heavy Metals				
Aluminium (filtered)	0.05	mg/L	< 0.05	< 0.05
Antimony (filtered)	0.005	mg/L	< 0.005	< 0.005
Arsenic (filtered)	0.001	mg/L	< 0.001	< 0.001
Barium (filtered)	0.02	mg/L	0.02	0.11
Boron (filtered)	0.05	mg/L	< 0.05	0.13
Cadmium (filtered)	0.0002	mg/L	< 0.0002	< 0.0002
Chromium (filtered)	0.001	mg/L	< 0.001	< 0.001
Cobalt (filtered)	0.001	mg/L	< 0.001	< 0.001
Copper (filtered)	0.001	mg/L	0.003	0.004
Iron (filtered)	0.05	mg/L	< 0.05	10
Lead (filtered)	0.001	mg/L	< 0.001	< 0.001
Manganese (filtered)	0.005	mg/L	0.011	1.0
Mercury (filtered)	0.0001	mg/L	< 0.0001	< 0.0001
Molybdenum (filtered)	0.005	mg/L	< 0.005	< 0.005
Nickel (filtered)	0.001	mg/L	< 0.001	< 0.001
Selenium (filtered)	0.001	mg/L	< 0.001	< 0.001
Silver (filtered)	0.005	mg/L	< 0.005	< 0.005
Strontium (filtered)	0.001	mg/L	0.22	3.2

Client Sample ID			VKY Lab Split Dup 1 Eurofins	VKY Lab Split Dup 2 Eurofins
Sample Matrix			Water	Water
Eurofins Sample No.			N25-Ja0025645	N25-Ja0025646
Date Sampled			Jan 15, 2025	Jan 15, 2025
Test/Reference	LOR	Unit		
Heavy Metals				
Tin (filtered)	0.005	mg/L	< 0.005	< 0.005
Zinc (filtered)	0.005	mg/L	< 0.005	0.058
Eurofins Suite B11C: Na/K/Ca/Mg				
Calcium	0.5	mg/L	4.5	190
Magnesium	0.5	mg/L	2.0	49
Potassium	0.5	mg/L	4.2	12
Sodium	0.5	mg/L	160	720

Sample History

Where samples are submitted/analysed over several days, the last date of extraction is reported.

If the date and time of sampling are not provided, the Laboratory will not be responsible for compromised results should testing be performed outside the recommended holding time.

Description	Testing Site	Extracted	Holding Time
Ammonia (as N) - Method: APHA 4500-NH3 Ammonia Nitrogen by FIA	Melbourne	Jan 21, 2025	28 Days
Conductivity (at 25 °C) - Method: LTM-INO-4030 Conductivity	Newcastle	Jan 20, 2025	28 Days
Oil & Grease (HEM) - Method: LTM-INO-4180 Oil and Grease	Melbourne	Jan 24, 2025	28 Days
pH (at 25 °C) - Method: LTM-GEN-7090 pH by ISE	Newcastle	Jan 20, 2025	6 Hours
Phosphate total (as P) - Method: E052 Total Phosphate (as P)	Sydney	Jan 21, 2025	28 Days
Eurofins Suite B19B: NO3/NO2/NOx - Method: LTM-INO-4120 Analysis of NOx NO2 NH3 by FIA	Melbourne	Jan 21, 2025	14 Days
Heavy Metals (filtered) - Method: LTM-MET-3040 Metals in Waters, Soils & Sediments by ICP-MS	Sydney	Jan 21, 2025	180 Days
Metals IWRG 621 : Metals M12 filtered - Method: LTM-MET-3040 Metals in Waters, Soils & Sediments by ICP-MS	Sydney	Jan 21, 2025	28 Days
Eurofins Suite B11C: Na/K/Ca/Mg - Method: LTM-MET-3040 Metals in Waters, Soils & Sediments by ICP-MS	Sydney	Jan 21, 2025	180 Days
Eurofins Suite B11E: Cl/SO4/Alkalinity			
Chloride - Method: LTM-INO-4270 Anions by Ion Chromatography	Sydney	Jan 21, 2025	28 Days
Sulphate (as SO4) - Method: In-house method LTM-INO-4270 Sulphate by Ion Chromatograph	Sydney	Jan 21, 2025	28 Days
Alkalinity (speciated) - Method: LTM-INO-4250 Alkalinity by Electrometric Titration	Sydney	Jan 21, 2025	14 Days
Total Dissolved Solids Dried at 180 °C ± 2 °C - Method: LTM-INO-4170 Total Dissolved Solids in Water	Newcastle	Jan 20, 2025	28 Days

Melbourne 6 Monterey Road Dandenong South VIC 3175 +61 3 8564 5000 NATA# 1261 Site# 1254	Geelong 19/8 Lewalan Street Grovedale VIC 3216 +61 3 8564 5000 NATA# 1261 Site# 25403	Sydney 179 Magowar Road Girraween NSW 2145 +61 2 9900 8400 NATA# 1261 Site# 18217	Canberra Unit 1,2 Dacre Street Mitchell ACT 2911 +61 2 6113 8091 NATA# 1261 Site# 25466	Brisbane 1/21 Smallwood Place Murarrie QLD 4172 T: +61 7 3902 4600 NATA# 1261 Site# 20794 & 2780	Newcastle 1/2 Frost Drive Mayfield West NSW 2304 +61 2 4968 8448 NATA# 1261 Site# 25079	Perth 46-48 Banksia Road Welshpool WA 6106 +61 8 6253 4444 NATA# 2377 Site# 2370 & 2554	Auckland 35 O'Rorke Road Penrose, Auckland 1061 +64 9 526 4551 IANZ# 1327	Auckland (Focus) Unit C1/4 Pacific Rise, Mount Wellington, Auckland 1061 +64 9 525 0568 IANZ# 1308	Christchurch 43 Detroit Drive Rolleston, Christchurch 7675 +64 3 343 5201 IANZ# 1290	Tauranga 1277 Cameron Road, Gate Pa, Tauranga 3112 +64 9 525 0568 IANZ# 1402
---	--	--	--	---	--	--	---	--	--	--

Company Name: Cbased Environmental Pty Ltd	Order No.:	Received: Jan 17, 2025 5:00 PM
Address: Unit 3, 2 Enterprise Crescent Singleton NSW 2330	Report #: 1178740	Due: Jan 24, 2025
	Phone: 02 6571 3334	Priority: 5 Day
	Fax:	Contact Name: Marni Blake
Project Name: VICKERY QTRLY GW	Eurofins Analytical Services Manager : Irem Haskara	

Sample Detail						Aluminium (filtered)	Ammonia (as N)	Antimony (filtered)	Barium (filtered)	Boron (filtered)	Cobalt (filtered)	Conductivity (at 25 °C)	Iron (filtered)	Manganese (filtered)	Oil & Grease (HEM)	pH (at 25 °C)	Phosphate total (as P)	Strontium (filtered)	Metals IWRG 621 : Metals M12 filtered	Eurofins Suite B19B: NO3/NO2/NOx	Eurofins Suite B11E: Cl/SO4/Alkalinity	Eurofins Suite B11C: Na/K/Ca/Mg	Total Dissolved Solids Dried at 180 °C ± 2 °C
Melbourne Laboratory - NATA # 1261 Site # 1254							X								X				X				
Sydney Laboratory - NATA # 1261 Site # 18217						X		X	X	X	X		X	X			X	X			X	X	
Mayfield West Laboratory - NATA # 1261 Site # 25079												X				X							X
External Laboratory																							
No	Sample ID	Sample Date	Sampling Time	Matrix	LAB ID																		
1	VKY Lab Split Dup 1 Eurofins	Jan 15, 2025	8:45AM	Water	N25-Ja0025645	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
2	VKY Lab Split Dup 2 Eurofins	Jan 15, 2025	12:25PM	Water	N25-Ja0025646	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X
Test Counts						2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2	2

Internal Quality Control Review and Glossary

General

- Laboratory QC results for Method Blanks, Duplicates, Matrix Spikes, and Laboratory Control Samples follow guidelines delineated in the National Environment Protection (Assessment of Site Contamination) Measure 1999, as amended May 2013. They are included in this QC report where applicable. Additional QC data may be available on request.
- Unless otherwise stated, all soil/sediment/solid results are reported on a dry weight basis.
- Unless otherwise stated, all biota/food results are reported on a wet weight basis on the edible portion.
- For CEC results where the sample's origin is unknown or environmentally contaminated, the results should be used advisedly.
- Actual LORs are matrix dependent. Quoted LORs may be raised where sample extracts are diluted due to interferences.
- Results are uncorrected for matrix spikes or surrogate recoveries except for PFAS compounds where annotated.
- SVOC analysis on waters is performed on homogenised, unfiltered samples unless noted otherwise.
- Samples were analysed on an 'as received' basis.
- Information identified in this report with **blue** colour indicates data provided by customers that may have an impact on the results.
- This report replaces any interim results previously issued.

Holding Times

Please refer to the 'Sample Preservation and Container Guide' for holding times (QS3001).

For samples received on the last day of holding time, notification of testing requirements should have been received at least 6 hours before sample receipt deadlines as stated on the SRA.

If the Laboratory did not receive the information in the required timeframe, and despite any other integrity issues, suitably qualified results may still be reported.

Holding times apply from the sampling date; therefore, compliance with these may be outside the laboratory's control.

For VOCs containing vinyl chloride, styrene and 2-chloroethyl vinyl ether, the holding time is seven days; however, for all other VOCs, such as BTEX or C6-10 TRH, the holding time is 14 days.

Units

mg/kg: milligrams per kilogram	mg/L: milligrams per litre	ppm: parts per million
µg/L: micrograms per litre	ppb: parts per billion	%: Percentage
org/100 mL: Organisms per 100 millilitres	NTU: Nephelometric Turbidity Units	MPN/100 mL: Most Probable Number of organisms per 100 millilitres
CFU: Colony Forming Unit	Colour: Pt-Co Units (CU)	

Terms

APHA	American Public Health Association
CEC	Cation Exchange Capacity
COC	Chain of Custody
CP	Client Parent - QC was performed on samples pertaining to this report
CRM	Certified Reference Material (ISO17034) - reported as percent recovery.
Dry	Where moisture has been determined on a solid sample, the result is expressed on a dry weight basis.
Duplicate	A second piece of analysis from the same sample and reported in the same units as the result to show comparison.
LOR	Limit of Reporting.
LCS	Laboratory Control Sample - reported as percent recovery.
Method Blank	In the case of solid samples, these are performed on laboratory-certified clean sands and in the case of water samples, these are performed on de-ionised water.
NCP	Non-Client Parent - QC performed on samples not pertaining to this report, QC represents the sequence or batch that client samples were analysed within.
RPD	Relative Percent Difference between two Duplicate pieces of analysis.
SPIKE	Addition of the analyte to the sample and reported as percentage recovery.
SRA	Sample Receipt Advice
Surr - Surrogate	The addition of a similar compound to the analyte target is reported as percentage recovery. See below for acceptance criteria.
TBTO	Tributyltin oxide (<i>bis</i> -tributyltin oxide) - individual tributyltin compounds cannot be identified separately in the environment; however, free tributyltin was measured, and its values were converted stoichiometrically into tributyltin oxide for comparison with regulatory limits.
TCLP	Toxicity Characteristic Leaching Procedure
TEQ	Toxic Equivalency Quotient or Total Equivalence
QSM	US Department of Defense Quality Systems Manual Version 6.0
US EPA	United States Environmental Protection Agency
WA DWER	Sum of PFBA, PFPeA, PFHxA, PFHpA, PFOA, PFBS, PFHxS, PFOS, 6:2 FTSA, 8:2 FTSA

QC - Acceptance Criteria

The acceptance criteria should only be used as a guide and may be different when site-specific Sampling Analysis and Quality Plan (SAQP) have been implemented.

RPD Duplicates: Global RPD Duplicates Acceptance Criteria is ≤30%; however, the following acceptance guidelines are equally applicable:

Results <10 times the LOR:	No Limit
Results between 10-20 times the LOR:	RPD must lie between 0-50%
Results >20 times the LOR:	RPD must lie between 0-30%

NOTE: pH duplicates are reported as a range, not as RPD

Surrogate Recoveries: Recoveries must lie between 20-130% for Speciated Phenols & 50-150% for PFAS. SVOCs recoveries 20 – 150%, VOC recoveries 50 – 150%

PFAS field samples containing surrogate recoveries above the QC limit designated in QSM 6.0, where no positive PFAS results have been reported or reviewed, and no data was affected.

QC Data General Comments

- Where a result is reported as less than (<), higher than the nominated LOR, this is due to either matrix interference, extract dilution required due to interferences or contaminant levels within the sample, high moisture content or insufficient sample provided.
- Duplicate data shown within this report that states the word "BATCH" is a Batch Duplicate from outside of your sample batch but within the laboratory sample batch at a 1:10 ratio. The Parent and Duplicate data shown are not data from your samples.
- pH and Free Chlorine analysed in the laboratory - Analysis on this test must begin within 30 minutes of sampling. Therefore, laboratory analysis is unlikely to be completed within holding time. Analysis will begin as soon as possible after sample receipt.
- Recovery Data (Spikes & Surrogates) - where chromatographic interference does not allow the determination of recovery, the term "INT" appears against that analyte.
- For Matrix Spikes and LCS results, a dash "-" in the report means that the specific analyte was not added to the QC sample.
- Duplicate RPDs are calculated from raw analytical data; thus, it is possible to have two sets of data.

Quality Control Results

Test	Units	Result 1			Acceptance Limits	Pass Limits	Qualifying Code
Method Blank							
Ammonia (as N)	mg/L	< 0.01			0.01	Pass	
Chloride	mg/L	< 1			1	Pass	
Oil & Grease (HEM)	mg/L	< 10			10	Pass	
Phosphate total (as P)	mg/L	< 0.01			0.01	Pass	
Sulphate (as SO4)	mg/L	< 2			2	Pass	
Method Blank							
Eurofins Suite B19B: NO3/NO2/NOx							
Nitrate & Nitrite (as N)	mg/L	< 0.05			0.05	Pass	
Nitrate (as N)	mg/L	< 0.02			0.02	Pass	
Nitrite (as N)	mg/L	< 0.02			0.02	Pass	
Method Blank							
Heavy Metals							
Aluminium (filtered)	mg/L	< 0.05			0.05	Pass	
Antimony (filtered)	mg/L	< 0.005			0.005	Pass	
Arsenic (filtered)	mg/L	< 0.001			0.001	Pass	
Barium (filtered)	mg/L	< 0.02			0.02	Pass	
Boron (filtered)	mg/L	< 0.05			0.05	Pass	
Cadmium (filtered)	mg/L	< 0.0002			0.0002	Pass	
Chromium (filtered)	mg/L	< 0.001			0.001	Pass	
Cobalt (filtered)	mg/L	< 0.001			0.001	Pass	
Copper (filtered)	mg/L	< 0.001			0.001	Pass	
Iron (filtered)	mg/L	< 0.05			0.05	Pass	
Lead (filtered)	mg/L	< 0.001			0.001	Pass	
Manganese (filtered)	mg/L	< 0.005			0.005	Pass	
Mercury (filtered)	mg/L	< 0.0001			0.0001	Pass	
Molybdenum (filtered)	mg/L	< 0.005			0.005	Pass	
Nickel (filtered)	mg/L	< 0.001			0.001	Pass	
Selenium (filtered)	mg/L	< 0.001			0.001	Pass	
Silver (filtered)	mg/L	< 0.005			0.005	Pass	
Strontium (filtered)	mg/L	< 0.001			0.001	Pass	
Tin (filtered)	mg/L	< 0.005			0.005	Pass	
Zinc (filtered)	mg/L	< 0.005			0.005	Pass	
Method Blank							
Eurofins Suite B11C: Na/K/Ca/Mg							
Calcium	mg/L	< 0.5			0.5	Pass	
Magnesium	mg/L	< 0.5			0.5	Pass	
Potassium	mg/L	< 0.5			0.5	Pass	
Sodium	mg/L	< 0.5			0.5	Pass	
Method Blank							
Alkalinity (speciated)							
Bicarbonate Alkalinity (as CaCO3)	mg/L	< 20			20	Pass	
Carbonate Alkalinity (as CaCO3)	mg/L	< 20			20	Pass	
Hydroxide Alkalinity (as CaCO3)	mg/L	< 20			20	Pass	
Total Alkalinity (as CaCO3)	mg/L	< 20			20	Pass	
LCS - % Recovery							
Ammonia (as N)	%	92			70-130	Pass	
Chloride	%	105			70-130	Pass	
Oil & Grease (HEM)	%	92			70-130	Pass	
Sulphate (as SO4)	%	105			70-130	Pass	
LCS - % Recovery							
Eurofins Suite B19B: NO3/NO2/NOx							

Test		Units	Result 1			Acceptance Limits	Pass Limits	Qualifying Code
Nitrate & Nitrite (as N)		%	80			70-130	Pass	
Nitrite (as N)		%	77			70-130	Pass	
LCS - % Recovery								
Heavy Metals								
Aluminium (filtered)		%	96			80-120	Pass	
Antimony (filtered)		%	90			80-120	Pass	
Arsenic (filtered)		%	99			80-120	Pass	
Barium (filtered)		%	97			80-120	Pass	
Boron (filtered)		%	97			80-120	Pass	
Cadmium (filtered)		%	100			80-120	Pass	
Chromium (filtered)		%	97			80-120	Pass	
Cobalt (filtered)		%	96			80-120	Pass	
Copper (filtered)		%	95			80-120	Pass	
Iron (filtered)		%	90			80-120	Pass	
Lead (filtered)		%	93			80-120	Pass	
Manganese (filtered)		%	96			80-120	Pass	
Mercury (filtered)		%	90			80-120	Pass	
Molybdenum (filtered)		%	91			80-120	Pass	
Nickel (filtered)		%	96			80-120	Pass	
Selenium (filtered)		%	95			80-120	Pass	
Silver (filtered)		%	98			80-120	Pass	
Strontium (filtered)		%	98			80-120	Pass	
Tin (filtered)		%	98			80-120	Pass	
Zinc (filtered)		%	96			80-120	Pass	
LCS - % Recovery								
Eurofins Suite B11C: Na/K/Ca/Mg								
Calcium		%	101			80-120	Pass	
Magnesium		%	113			80-120	Pass	
Potassium		%	105			80-120	Pass	
Sodium		%	110			80-120	Pass	
LCS - % Recovery								
Alkalinity (speciated)								
Bicarbonate Alkalinity (as CaCO3)		%	108			70-130	Pass	
Hydroxide Alkalinity (as CaCO3)		%	108			70-130	Pass	
Total Alkalinity (as CaCO3)		%	108			70-130	Pass	
Test	Lab Sample ID	QA Source	Units	Result 1		Acceptance Limits	Pass Limits	Qualifying Code
Spike - % Recovery								
				Result 1				
Ammonia (as N)	M25-Ja0022871	NCP	%	95		70-130	Pass	
Chloride	N25-Ja0025645	CP	%	96		70-130	Pass	
Sulphate (as SO4)	N25-Ja0025645	CP	%	106		70-130	Pass	
Spike - % Recovery								
Eurofins Suite B19B: NO3/NO2/NOx								
				Result 1				
Nitrate & Nitrite (as N)	M25-Ja0022871	NCP	%	88		70-130	Pass	
Nitrite (as N)	M25-Ja0022871	NCP	%	100		70-130	Pass	
Spike - % Recovery								
Heavy Metals								
				Result 1				
Aluminium (filtered)	S25-Ja0039056	NCP	%	105		75-125	Pass	
Antimony (filtered)	S25-Ja0039056	NCP	%	106		75-125	Pass	
Arsenic (filtered)	S25-Ja0039056	NCP	%	116		75-125	Pass	
Boron (filtered)	S25-Ja0039056	NCP	%	92		75-125	Pass	
Cadmium (filtered)	S25-Ja0039056	NCP	%	113		75-125	Pass	
Chromium (filtered)	S25-Ja0039056	NCP	%	101		75-125	Pass	
Cobalt (filtered)	S25-Ja0039056	NCP	%	99		75-125	Pass	

Test	Lab Sample ID	QA Source	Units	Result 1			Acceptance Limits	Pass Limits	Qualifying Code
Copper (filtered)	S25-Ja0039056	NCP	%	96			75-125	Pass	
Iron (filtered)	S25-Ja0039056	NCP	%	89			75-125	Pass	
Lead (filtered)	S25-Ja0039056	NCP	%	99			75-125	Pass	
Mercury (filtered)	S25-Ja0039056	NCP	%	94			75-125	Pass	
Molybdenum (filtered)	S25-Ja0039056	NCP	%	112			75-125	Pass	
Nickel (filtered)	S25-Ja0039056	NCP	%	97			75-125	Pass	
Selenium (filtered)	S25-Ja0039056	NCP	%	106			75-125	Pass	
Silver (filtered)	S25-Ja0039056	NCP	%	113			75-125	Pass	
Tin (filtered)	S25-Ja0039056	NCP	%	114			75-125	Pass	
Zinc (filtered)	S25-Ja0039056	NCP	%	102			75-125	Pass	
Spike - % Recovery									
Eurofins Suite B11C: Na/K/Ca/Mg				Result 1					
Magnesium	S25-Ja0026920	NCP	%	92			75-125	Pass	
Potassium	S25-Ja0026920	NCP	%	88			75-125	Pass	
Test	Lab Sample ID	QA Source	Units	Result 1			Acceptance Limits	Pass Limits	Qualifying Code
Duplicate									
				Result 1	Result 2	RPD			
Ammonia (as N)	B25-Ja0025120	NCP	mg/L	8.1	7.9	2.0	30%	Pass	
Chloride	L25-Ja0027235	NCP	mg/L	470	470	1.0	30%	Pass	
Sulphate (as SO4)	S25-Ja0020781	NCP	mg/L	< 2	< 2	<1	30%	Pass	
Duplicate									
Eurofins Suite B19B: NO3/NO2/NOx				Result 1	Result 2	RPD			
Nitrate & Nitrite (as N)	B25-Ja0025120	NCP	mg/L	< 0.05	< 0.05	<1	30%	Pass	
Nitrite (as N)	B25-Ja0025120	NCP	mg/L	0.03	0.03	20	30%	Pass	
Duplicate									
Heavy Metals				Result 1	Result 2	RPD			
Aluminium (filtered)	N25-Ja0029526	NCP	mg/L	< 0.05	< 0.05	<1	30%	Pass	
Antimony (filtered)	N25-Ja0029526	NCP	mg/L	< 0.005	< 0.005	<1	30%	Pass	
Arsenic (filtered)	N25-Ja0029526	NCP	mg/L	< 0.001	< 0.001	<1	30%	Pass	
Barium (filtered)	N25-Ja0029526	NCP	mg/L	< 0.02	< 0.02	<1	30%	Pass	
Boron (filtered)	N25-Ja0029526	NCP	mg/L	< 0.05	< 0.05	<1	30%	Pass	
Cadmium (filtered)	N25-Ja0029526	NCP	mg/L	< 0.0002	< 0.0002	<1	30%	Pass	
Chromium (filtered)	N25-Ja0029526	NCP	mg/L	< 0.001	< 0.001	<1	30%	Pass	
Cobalt (filtered)	N25-Ja0029526	NCP	mg/L	< 0.001	< 0.001	<1	30%	Pass	
Copper (filtered)	N25-Ja0029526	NCP	mg/L	< 0.001	< 0.001	<1	30%	Pass	
Iron (filtered)	N25-Ja0029526	NCP	mg/L	< 0.05	< 0.05	<1	30%	Pass	
Lead (filtered)	N25-Ja0029526	NCP	mg/L	< 0.001	< 0.001	<1	30%	Pass	
Manganese (filtered)	N25-Ja0029526	NCP	mg/L	< 0.005	< 0.005	<1	30%	Pass	
Mercury (filtered)	N25-Ja0029526	NCP	mg/L	< 0.0001	< 0.0001	<1	30%	Pass	
Molybdenum (filtered)	N25-Ja0029526	NCP	mg/L	< 0.005	< 0.005	<1	30%	Pass	
Nickel (filtered)	N25-Ja0029526	NCP	mg/L	< 0.001	< 0.001	<1	30%	Pass	
Selenium (filtered)	N25-Ja0029526	NCP	mg/L	< 0.001	< 0.001	<1	30%	Pass	
Silver (filtered)	N25-Ja0029526	NCP	mg/L	< 0.005	< 0.005	<1	30%	Pass	
Strontium (filtered)	N25-Ja0029526	NCP	mg/L	< 0.001	< 0.001	<1	30%	Pass	
Tin (filtered)	N25-Ja0029526	NCP	mg/L	< 0.005	< 0.005	<1	30%	Pass	
Zinc (filtered)	N25-Ja0029526	NCP	mg/L	< 0.005	< 0.005	<1	30%	Pass	
Duplicate									
Eurofins Suite B11C: Na/K/Ca/Mg				Result 1	Result 2	RPD			
Calcium	S24-De0023514	NCP	mg/L	1.3	1.3	<1	30%	Pass	
Magnesium	S24-De0023514	NCP	mg/L	1.3	1.3	2.0	30%	Pass	
Potassium	S24-De0023514	NCP	mg/L	< 0.5	< 0.5	<1	30%	Pass	
Sodium	S24-De0023514	NCP	mg/L	1.3	1.3	2.0	30%	Pass	

Duplicate								
Alkalinity (speciated)				Result 1	Result 2	RPD		
Bicarbonate Alkalinity (as CaCO ₃)	N25-Ja0025646	CP	mg/L	190	190	3.0	30%	Pass
Carbonate Alkalinity (as CaCO ₃)	N25-Ja0025646	CP	mg/L	< 20	< 20	<1	30%	Pass
Hydroxide Alkalinity (as CaCO ₃)	N25-Ja0025646	CP	mg/L	< 20	< 20	<1	30%	Pass
Total Alkalinity (as CaCO ₃)	N25-Ja0025646	CP	mg/L	190	190	3.0	30%	Pass

Comments
Sample Integrity

Custody Seals Intact (if used)	N/A
Attempt to Chill was evident	Yes
Sample correctly preserved	Yes
Appropriate sample containers have been used	Yes
Sample containers for volatile analysis received with minimal headspace	Yes
Samples received within HoldingTime	Yes
Some samples have been subcontracted	No

Qualifier Codes/Comments

Code	Description
Q19	TDS may bias high due to the presence of fine particulate or colloidal matter that may pass through the filter paper.

Authorised by:

Andrew Black	Analytical Services Manager
Kirra Bailey	Senior Analyst-Inorganic
Mary Makarios	Senior Analyst-Inorganic
Mickael Ros	Senior Analyst-Metal
Ryan Phillips	Senior Analyst-Inorganic



Glenn Jackson
Managing Director


Final Report – this report replaces any previously issued Report

- Indicates Not Requested

* Indicates NATA accreditation does not cover the performance of this service

Measurement uncertainty of test data is available on request or please [click here](#).

Eurofins shall not be liable for loss, cost, damages or expenses incurred by the client, or any other person or company, resulting from the use of any information or interpretation given in this report. In no case shall Eurofins be liable for consequential damages including, but not limited to, lost profits, damages for failure to meet deadlines and lost production arising from this report. This document shall not be reproduced except in full and relates only to the items tested. Unless indicated otherwise, the tests were performed on the samples as received.



Appendix D Quality Trigger Level Anlaysia

Vickery Extension Project Groundwater Monitoring Report

Quarterly Review November 2024 – January 2025

Whitehaven Coal Ltd

SLR Project No.: 640.031099.00001

26 March 2025

Table D-1: pH (Field) Trigger Level Review

Bore	Trigger Level		Oct/Nov-23	Jan-24	Apr-24	Jul-24	Oct-24	Jan-24
GW01	6.90	8.30	7.33	7.20	7.14	7.2	7.16	7.10
GW02	7.20	8.60	7.59	7.79	7.14	7.23	7.42	6.63
GW03	6.10	8.10	7.19	7.16	7.05	7.36	7.22	7.08
GW-10	6.70	8.40	no data	no data	no data	no data	7.57	7.36
GW-11	7.00	9.30	7.36	6.93	6.55	6.09	7.17	7.03
GW-13	6.70	8.40	no data	no data	no data	no data	7.35	7.30
GW-14	6.90	8.30	no data	no data	no data	no data	6.95	6.53
GW-15	6.90	8.30	no data	no data	no data	no data	8.97	8.85
GW-2	6.90	8.30	no data	no data	6.85	no data	6.84	6.45
GW-4	6.70	8.40	no data	no data	no data	no data	7.92	7.84
GW-6	6.70	8.40	no data	no data	no data	no data	7.73	7.52
GW-7	7.70	8.50	8.89	8.82	8.79	8.67	8.3	7.76
GW-8	6.70	8.40	7.11	7.03	6.95	6.49	7.0	6.62
GW-9	6.60	8.20	7.94	6.68	6.81	6.76	6.68	5.40
GW971400	6.90	8.30	no data	no data	no data	no data	6.8	7.08*
GW971614	6.90	8.30	no data	no data	no data	no data	6.65	7.08
MD01	6.70	8.40	11.58	11.69	10.73	9.59	8.33	8.84
MD02	6.70	8.40	6.84	6.78	6.59	6.57	6.72	6.81
SB01	6.90	8.30	7.44	7.31	7.20	7.21	7.23	7.12
SB02	6.90	8.30	7.28	7.28	7.14	7.2	7.23	7.22
SB04	6.90	8.30	7.29	7.43	7.27	7.12	7.21	7.04
SB05	6.90	8.30	2.09	7.73	7.63	7.58	7.71	7.52
SB06	6.90	8.30	7.35	7.61	7.42	7.56	7.7	7.42
SB07	6.90	8.30	7.35	7.47	7.28	7.22	7.58	7.29
SB08	6.90	8.30	7.24	7.39	7.17	7.29	7.27	7.27
SB09	6.90	8.30	3.32	7.56	7.27	7.52	7.44	7.40
SB10	6.90	8.30	7.43	7.47	7.28	7.5	7.38	7.25
SB11	6.90	8.30	7.26	7.70	7.45	7.77	7.51	7.39
SB15	6.90	8.30	7.29	7.23	7.17	7.3	7.24	7.41
TR18	6.70	8.40	6.58	6.85	6.69	6.64	6.79	6.68
TR26	6.70	8.40	7.06	7.16	7.11	6.69	6.93	6.85
TR35	6.70	8.40	6.66	6.75	6.72	6.75	6.73	6.54
TR7	7.40	7.80	6.53	7.05	6.71	6.82	6.63	6.51



Bore	Trigger Level		Oct/Nov-23	Jan-24	Apr-24	Jul-24	Oct-24	Jan-24
VKY034C	6.70	8.40	7.30	6.94	7.05	7.25	7.25	7.16
VKY035C	6.70	8.40	7.10	7.01	6.88	6.9	7.09	6.93
VKY036C	6.70	8.40	7.08	6.79	6.80	7.19	7.21	7.06
VKY042C	6.70	8.40	6.75	6.72	6.61	6.65	6.72	6.64
VKY043C	6.70	8.40	7.72	7.80	7.65	7.85	7.7	7.50
VNW223	6.90	7.40	7.25	no data	no data	no data	7.17	7.07
VNW390	6.70	8.40	6.92	7.13	6.59	6.84	6.81	6.96
VNW391	6.70	8.40	7.04	7.31	7.06	6.81	7.1	7.02
VNW392	6.70	8.40	6.74	6.74	6.66	6.51	6.74	6.47
VNW393	6.70	8.40	7.36	7.56	7.20	7.13	7.16	6.94
VNW394	6.90	8.30	7.13	6.92	6.94	6.62	7.07	6.87
VNW395	6.90	8.30	7.47	7.77	7.77	7.61	7.56	7.58
WR1	6.90	8.30	no data	no data	6.70	6.47	6.5	6.95
WR2	6.90	8.30	no data	no data	6.57	6.52	6.36	6.41

Note: Reported as field pH value. Values marked with an asterisk (*) are reported as Laboratory pH value. Red text shows exceedance of trigger level. Highlighted cell shows trigger level 1 as defined by TARP in the GWMP (Appendix A).



Table D-2: EC Trigger Level Review

Bore	Trigger Level	Oct/Nov-23	Jan-24	Apr-24	Jul-24	Oct-24	Jan-25
GW01	10,083	1,042	1,265	1,384	1,052	738	1,244
GW02	969	731	971	926	1,065	1,016	992
GW03	811	862	888	862	947	1,004	983
GW-10	12,315	no data	no data	no data	no data	1,438	1,423
GW-11	4,912	4,360	4,340	4,520	4,760	4,760	4,310
GW-13	12,315	no data	no data	no data	no data	1,647	1,570
GW-14	10,083	no data	no data	no data	no data	3,840	4,260
GW-15	10,083	no data	no data	no data	no data	638	644
GW-2	10,083	no data	no data	1,218	no data	1,226	1,339
GW-4	12,315	no data	no data	no data	no data	2,980	2,970
GW-6	12,315	no data	no data	no data	no data	1,459	1,256
GW-7	5,378	4,300	4,490	4,560	4,710	4,470	4,690
GW-8	12,315	4,290	3,950	4,000	4,100	3,930	4,350
GW-9	12,740	6,110	3,320	5,630	1,591	1,099	1,544
GW971400	10,083	no data	no data	no data	no data	2,458	2,810*
GW971614	10,083	no data	no data	no data	no data	651	608
MD01	12,315	1,799	1,786	1,283	1,505	1,787	1,519
MD02	12,315	1,195	1,306	1,210	1,224	1,279	1,381
SB01	10,083	1,541	1,716	1,698	1,756	1,869	1,851
SB02	10,083	7,330	7,330	7,210	6,860	7,250	6,990
SB04	10,083	2,680	3,360	1,868	2,390	2,289	3,420
SB05	10,083	3,740	3,690	3,680	3,490	3,790	3,660
SB06	10,083	3,280	3,460	3,410	3,440	2,790	3,160
SB07	10,083	770	919	934	978	1,042	1,009
SB08	10,083	983	1,115	1,039	1,088	388	1,154
SB09	10,083	949	1,014	973	1,013	1,130	1,045
SB10	10,083	1,880	1,972	1,859	1,928	2,200	2,086
SB11	10,083	1,080	1,021	1,048	461	1,266	1,209
SB15	10,083	1,019	1,070	972	1,049	1,143	1,163
TR18	12,315	13,400	13,640	12,730	15,350	13,820	13,810
TR26	12,315	6,290	8,380	5,180	7,330	6,090	6,170
TR35	12,315	15,300	17,330	16,740	17,260	16,690	18,320
TR7	12,970	14,800	15,390	14,410	15,380	14,840^	15,520



Bore	Trigger Level	Oct/Nov-23	Jan-24	Apr-24	Jul-24	Oct-24	Jan-25
VKY034C	12,315	3,590	3,850	4,030	4,170	3,970	3,910
VKY035C	12,315	3,110	3,340	3,230	3,290	3,330	3,220
VKY036C	12,315	5,600	5,810	5,780	5,830	6,020	2,980
VKY042C	12,315	5,420	5,430	5,480	5,990	5,850	5,590
VKY043C	12,315	2,990	3,410	3,410	3,290	3,050	3,240
VNW223	10,120	5,940	no data	no data	no data	5,360	4,390
VNW390	12,315	2,300	2,376	2,291	2,473	2,431	2,629
VNW391	12,315	2,530	2,471	2,352	2,458	2,424	2,550
VNW392	12,315	3,690	3,310	3,480	3,510	3,410	3,480
VNW393	12,315	2,740	2,830	2,840	3,090	3,140	3,210
VNW394	10,083	5,520	5,410	5,400	5,620	5,420	5,480
VNW395	10,083	463	1,395	1,681	1,832	1,834	2,153
WR1	10,083	no data	no data	26,500	26,800	26,800	25,400
WR2	10,083	no data	no data	25,340	26,600	26,600	27,900

Note: Reported as field EC value in $\mu\text{S}/\text{cm}$. Values marked with an asterisk (*) are reported as Laboratory EC value. Red text shows exceedance of trigger level. Highlighted cell shows trigger level 1 as defined by TARP in the GWMP (Appendix A).

^Compared to the lab result, the field EC result at TR7 in the October 2024 monitoring round was updated from 1,484 $\mu\text{S}/\text{cm}$ to 14,840 $\mu\text{S}/\text{cm}$ due to a typo in the October 2024 field note. The EC values at TR7 have been a level 1 trigger since October 2024, as defined by the TARP.



Table D-3: Sulfate trigger level review

Bore	Trigger Level	Oct/Nov-23	Jan-24	Apr-24	Jul-24	Oct-24	Jan-25
GW01	365	96	171	132	54	111	132
GW02	365	77	74	81	102	79	91
GW03	365	52	56	58	46	54	53
GW-10	86	no data	no data	no data	no data	7	21
GW-11	365	<1	1	<1	1	<1	3
GW-13	86	no data	no data	no data	no data	24	26
GW-14	365	no data	no data	no data	no data	435	462
GW-15	365	no data	no data	no data	no data	28	28
GW-2	365	no data	no data	23	no data	26	23
GW-4	86	no data	no data	no data	no data	15	<1
GW-6	86	no data	no data	no data	no data	<1	<1
GW-7	86	364	385	399	380	396	414
GW-8	86	no data	100	109	72	82	109
GW-9	86	102	128	51	25	28	<1
GW971400	365	no data	no data	no data	no data	425	477
GW971614	365	no data	no data	no data	no data	32	30
MD01	86	22	23	26	36	14	33
MD02	86	28	29	28	29	29	28
SB01	365	182	183	190	148	193	216
SB02	365	1,120	no data	1,160	741	1,110	1,280
SB04	365	284	394	220	195	208	413
SB05	365	735	551	520	595	496	447
SB06	365	372	362	362	324	307	366
SB07	365	74	74	78	66	71	89
SB08	365	86	87	88	79	74	97
SB09	365	71	63	70	62	67	78
SB10	365	190	188	196	168	198	238
SB11	365	85	72	93	80	85	106
SB15	365	90	79	95	53	98	119
TR18	86	702	620	592	622	626	630
TR26	86	194	230	180	198	195	229
TR35	86	660	651	622	624	624	526
TR7	365	508	714	501	518	563	458



Bore	Trigger Level	Oct/Nov-23	Jan-24	Apr-24	Jul-24	Oct-24	Jan-25
VKY034C	86	123	185	116	98	90	115
VKY035C	86	87	77	88	73	68	83
VKY036C	86	244	294	281	100	174	190
VKY042C	86	302	309	312	283	326	307
VKY043C	86	<1	<1	<1	<1	<1	<1
VNW223	365	97	no data	no data	no data	164	91
VNW390	86	95	95	106	55	104	107
VNW391	86	88	88	96	52	86	101
VNW392	86	no data	284	296	263	314	300
VNW393	86	179	185	200	165	202	205
VNW394	365	no data	551	560	574	591	498
VNW395	365	14	61	143	91	131	147
WR1	365	no data	no data	1,320	901	1,280	1,490
WR2	365	no data	no data	1,540	1,120	1,670	1,790

Note: Sulfate as SO₄ in mg/L. Red text shows exceedance of trigger level. Highlight cell shows trigger level 1 as defined by TARP in the GWMP (Appendix A).



Table D-4: Metal trigger against ANZECC default guideline values

Bore ID	Date	Aluminium	Antimony	Arsenic	Boron	Cadmium	Chromium	Cobalt	Copper	Lead	Manganese	Mercury	Molybdenum	Nickel	Selenium	Silver	Zinc
Unit		mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L
DGV		0.055	0.009	0.013	0.94	0.0002	0.001	0.0014	0.0014	0.0034	1.9	0.0006	0.034	0.011	0.011	0.00005	0.008
GW01	Jan-24	<0.01	<0.001	<0.001	0.14	<0.0001	<0.001	<0.001	<0.001	<0.001	0.967	<0.0001	<0.001	0.013	<0.01	<0.001*	<0.005
GW01	Apr-24	<0.01	<0.001	<0.001	0.06	<0.0001	<0.001	<0.001	<0.001	<0.001	0.063	<0.0001	<0.001	<0.001	<0.01	<0.001*	<0.005
GW01	Jul-24	<0.01	<0.001	<0.001	0.07	<0.0001	<0.001	<0.001	<0.001	<0.001	0.126	<0.0001	<0.001	<0.001	<0.01	<0.001*	<0.005
GW01	Oct-24	<0.01	<0.001	<0.001	0.07	<0.0001	<0.001	<0.001	<0.001	<0.001	0.155	<0.0001	<0.001	<0.001	<0.01	<0.001*	<0.005
GW01	Jan-25	<0.01	<0.001	<0.001	0.07	No data	<0.001	<0.001	No data	<0.001	0.24	<0.0001	<0.001	<0.001	<0.01	<0.001*	<0.005
GW02	Jan-24	<0.01	<0.001	<0.001	0.1	<0.0001	<0.001	<0.001	0.002	<0.001	0.021	<0.0001	<0.001	0.375	<0.01	<0.001*	0.013
GW02	Apr-24	<0.01	<0.001	<0.001	<0.05	<0.0001	<0.001	<0.001	0.007	<0.001	0.026	<0.0001	<0.001	<0.001	<0.01	<0.001*	<0.005
GW02	Jul-24	<0.01	0.001	<0.001	0.08	<0.0001	<0.001	<0.001	0.003	<0.001	0.018	<0.0001	<0.001	<0.001	<0.01	<0.001*	0.006
GW02	Oct-24	<0.01	<0.001	<0.001	0.06	<0.0001	<0.001	<0.001	0.014	<0.001	0.005	<0.0001	<0.001	<0.001	<0.01	<0.001*	<0.005
GW02	Jan-25	<0.01	<0.001	<0.001	0.06	No data	<0.001	<0.001	No data	<0.001	0.006	<0.0001	<0.001	<0.001	<0.01	<0.001*	0.005
GW03	Jan-24	<0.01	<0.001	<0.001	0.09	<0.0001	<0.001	<0.001	<0.001	<0.001	0.014	<0.0001	<0.001	0.971	<0.01	<0.001*	<0.005
GW03	Apr-24	<0.01	<0.001	<0.001	<0.05	<0.0001	<0.001	<0.001	<0.001	<0.001	0.01	<0.0001	<0.001	<0.001	<0.01	<0.001*	<0.005
GW03	Jul-24	<0.01	<0.001	<0.001	0.06	<0.0001	<0.001	<0.001	<0.001	<0.001	0.012	<0.0001	<0.001	0.002	<0.01	<0.001*	0.006
GW03	Oct-24	<0.01	<0.001	<0.001	<0.05	<0.0001	<0.001	<0.001	<0.001	<0.001	0.043	<0.0001	<0.001	0.001	<0.01	<0.001*	<0.005
GW03	Jan-25	<0.01	<0.001	<0.001	<0.05	No data	<0.001	<0.001	No data	<0.001	0.089	<0.0001	<0.001	<0.001	<0.01	<0.001*	<0.005
GW-10	Oct-24	0.02	0.004	0.002	0.11	<0.0001	<0.001	<0.001	0.114	<0.001	0.033	<0.0001	0.002	0.005	<0.01	<0.001*	0.072
GW-10	Jan-25	<0.01	0.004	<0.001	0.14	No data	<0.001	<0.001	No data	<0.001	0.023	<0.0001	0.001	0.003	<0.01	<0.001*	0.116
GW-11	Jan-24	<0.01	<0.001	<0.001	0.13	<0.0001	<0.001	<0.001	<0.001	0.001	2.2	<0.0001	no data	0.00075	<0.01	<0.001*	0.0075
GW-11	Apr-24	<0.01	<0.001	<0.001	0.08	<0.0001	<0.001	<0.001	0.001	<0.001	0.224	<0.0001	no data	0.004	<0.01	<0.001*	0.012
GW-11	Jul-24	<0.01	<0.001	<0.001	0.13	0.0003	<0.001	<0.001	0.002	<0.001	1.06	<0.0001	<0.001	0.002	<0.01	<0.001*	0.043
GW-11	Oct-24	<0.01	<0.001	<0.001	0.14	<0.0001	<0.001	<0.001	0.019	<0.001	0.98	<0.0001	<0.001	<0.001	<0.01	<0.001*	0.043



Bore ID	Date	Aluminium	Antimony	Arsenic	Boron	Cadmium	Chromium	Cobalt	Copper	Lead	Manganese	Mercury	Molybdenum	Nickel	Selenium	Silver	Zinc
GW-11	Jan-25	<0.01	<0.001	<0.001	0.13	No data	<0.001	<0.001	No data	<0.001	1.04	<0.0001	<0.001	<0.001	<0.01	<0.001*	0.034
GW-13	Oct-24	<0.01	0.001	0.001	0.08	<0.0001	<0.001	0.001	0.006	<0.001	0.161	<0.0001	<0.001	0.006	<0.01	<0.001*	0.019
GW-13	Jan-25	<0.01	<0.001	<0.001	0.08	No data	<0.001	<0.001	No data	<0.001	0.136	<0.0001	<0.001	0.005	<0.01	<0.001*	0.02
GW-14	Oct-24	<0.01	<0.001	<0.001	<0.05	<0.0001	<0.001	<0.001	<0.001	<0.001	0.026	<0.0001	<0.001	0.004	<0.01	<0.001*	0.095
GW-14	Jan-25	<0.01	<0.001	<0.001	<0.05	No data	<0.001	<0.001	No data	<0.001	0.008	<0.0001	<0.001	0.001	<0.01	<0.001*	0.031
GW-15	Oct-24	<0.01	<0.001	<0.001	<0.05	<0.0001	<0.001	<0.001	0.002	<0.001	0.011	<0.0001	0.004	<0.001	<0.01	<0.001*	0.011
GW-15	Jan-25	<0.01	<0.001	0.002	<0.05	No data	<0.001	<0.001	No data	<0.001	0.01	<0.0001	0.003	<0.001	<0.01	<0.001*	<0.005
GW-2	Apr-24	<0.01	<0.001	<0.001	0.08	<0.0001	<0.001	<0.001	0.001	<0.001	0.224	<0.0001	<0.001	0.004	<0.01	<0.001*	0.012
GW-2	Oct-24	<0.01	<0.001	0.002	<0.05	<0.0001	0.003	<0.001	0.003	<0.001	0.005	<0.0001	<0.001	<0.001	<0.01	<0.001*	0.006
GW-2	Jan-25	<0.01	<0.001	0.001	<0.05	No data	0.002	<0.001	No data	<0.001	0.009	<0.0001	<0.001	<0.001	<0.01	<0.001*	0.016
GW-4	Oct-24	<0.01	<0.001	0.002	0.12		<0.001	<0.001		<0.001	0.009	<0.0001	<0.001	<0.001	<0.01	<0.001*	0.052
GW-4	Jan-25	<0.01	<0.001	0.002	0.14	No data	<0.001	<0.001	No data	<0.001	0.008	<0.0001	<0.001	<0.001	<0.01	<0.001*	0.029
GW-6	Oct-24	<0.01	<0.001	<0.001	0.07		<0.001	<0.001		<0.001	0.017	<0.0001	<0.001	<0.001	<0.01	<0.001*	0.01
GW-6	Jan-25	<0.01	<0.001	<0.001	0.08	No data	<0.001	<0.001	No data	<0.001	0.029	<0.0001	<0.001	<0.001	<0.01	<0.001*	<0.005
GW-7	Jan-24	<0.01	<0.001	<0.001	0.18	<0.0001	<0.001	<0.001	0.003	<0.001	0.011	<0.0001	0.002	0.002	<0.01	<0.001*	<0.005
GW-7	Apr-24	<0.01	<0.001	<0.001	0.08	<0.0001	<0.001	<0.001	0.001	<0.001	0.224	<0.0001	<0.001	0.004	<0.01	<0.001*	0.012
GW-7	Jul-24	<0.01	<0.001	<0.001	0.17	0.0002	<0.001	<0.001	0.016	0.002	0.024	<0.0001	0.001	0.005	<0.01	<0.001*	0.018
GW-7	Oct-24	<0.01	<0.001	<0.001	0.18	<0.0001	<0.001	<0.001	0.001	<0.001	0.03	<0.0001	<0.001	0.001	<0.01	<0.001*	<0.005
GW-7	Jan-25	<0.01	<0.001	<0.001	0.17	No data	<0.001	<0.001	No data	<0.001	0.04	<0.0001	<0.001	0.001	<0.01	<0.001*	<0.005
GW-8	Jan-24	<0.01	<0.001	<0.001	0.09	<0.0001	<0.001	<0.001	<0.001	<0.001	0.092	<0.0001	<0.001	0.001	<0.01	<0.001*	0.012
GW-8	Apr-24	<0.01	<0.001	<0.001	0.08	<0.0001	<0.001	<0.001	0.001	<0.001	0.224	<0.0001	<0.001	0.004	<0.01	<0.001*	0.012
GW-8	Jul-24	<0.01	<0.001	0.002	0.07	0.0001	<0.001	<0.001	<0.001	<0.001	0.089	<0.0001	<0.001	0.003	<0.01	<0.001*	0.01
GW-8	Oct-24	<0.01	<0.001	<0.001	0.07	<0.0001	<0.001	<0.001	<0.001	<0.001	0.176	<0.0001	<0.001	0.002	<0.01	<0.001*	<0.005
GW-8	Jan-25	<0.01	<0.001	<0.001	0.07	No data	<0.001	<0.001	No data	<0.001	0.132	<0.0001	<0.001	0.002	<0.01	<0.001*	<0.005



Bore ID	Date	Aluminium	Antimony	Arsenic	Boron	Cadmium	Chromium	Cobalt	Copper	Lead	Manganese	Mercury	Molybdenum	Nickel	Selenium	Silver	Zinc
GW-9	Jan-24	<0.01	<0.001	<0.001	0.05	0.0001	<0.001	0.00075	<0.001	<0.001	3.8	<0.0001	<0.001	<0.001	<0.01	<0.001*	0.00825
GW-9	Apr-24	<0.01	<0.001	<0.001	0.08	<0.0001	<0.001	<0.001	0.001	<0.001	0.224	<0.0001	<0.001	0.004	<0.01	<0.001*	0.012
GW-9	Jul-24	<0.01	<0.001	<0.001	0.07	0.0001	<0.001	<0.001	<0.001	<0.001	1.71	<0.0001	<0.001	0.003	<0.01	<0.001*	0.008
GW-9	Oct-24	<0.01	<0.001	<0.001	0.05	<0.0001	<0.001	<0.001	0.002	<0.001	2.12	<0.0001	<0.001	0.001	<0.01	<0.001*	<0.005
GW-9	Jan-25	<0.01	<0.001	<0.001	<0.05	No data	<0.001	<0.001	No data	<0.001	2.6	<0.0001	<0.001	<0.001	<0.01	<0.001*	0.008
GW971400	Oct-24	<0.01	<0.001	<0.001	0.06	<0.0001	<0.001	0.001	0.006	<0.001	0.024	<0.0001	<0.001	0.039	<0.01	<0.001*	<0.005
GW971400	Jan-25	<0.01	<0.001	<0.001	0.05	No data	<0.001	<0.001	No data	<0.001	0.024	<0.0001	<0.001	0.018	<0.01	<0.001*	<0.005
GW971614	Oct-24	<0.01	<0.001	<0.001	<0.05	<0.0001	<0.001	<0.001	0.001	<0.001	0.002	<0.0001	<0.001	<0.001	<0.01	<0.001*	<0.005
GW971614	Jan-25	<0.01	<0.001	<0.001	<0.05	No data	<0.001	<0.001	No data	<0.001	<0.001	<0.0001	<0.001	<0.001	<0.01	<0.001*	<0.005
Landreef Tap	Jan-25	<0.01	<0.001	<0.001	<0.05	No data	<0.001	<0.001	No data	<0.001	<0.001	<0.0001	<0.001	<0.001	<0.01	<0.001*	<0.005
MD01	Jan-24	0.58	0.001	<0.001	0.04	<0.0001	<0.001	<0.001	0.020	0.001	0.004	<0.0001	0.018	0.005	<0.01	<0.001*	0.31
MD01	Apr-24	0.28	<0.001	0.002	<0.05	<0.0001	<0.001	<0.001	0.006	0.001	<0.001	<0.0001	0.019	0.006	<0.01	<0.001*	0.213
MD01	Jul-24	0.04	0.002	0.001	<0.05	<0.0001	<0.001	<0.001	0.002	0.003	0.013	<0.0001	0.007	0.006	<0.01	<0.001*	0.106
MD01	Oct-24	0.02	<0.001	<0.001	<0.05	<0.0001	<0.001	<0.001	<0.001	<0.001	0.022	<0.0001	0.008	0.004	0.01	<0.001*	0.049
MD01	Jan-25	0.04	<0.001	<0.001	<0.05	No data	<0.001	<0.001	No data	<0.001	0.017	<0.0001	0.002	0.002	<0.01	<0.001*	0.014
MD02	Jan-24	<0.01	<0.001	0.001	0.08	<0.0001	<0.001	<0.001	<0.001	<0.001	0.039	<0.0001	0.001	0.036	<0.01	<0.001*	<0.005
MD02	Apr-24	<0.01	<0.001	0.003	<0.05	<0.0001	<0.001	<0.001	<0.001	<0.001	0.051	<0.0001	0.003	0.019	<0.01	<0.001*	<0.005
MD02	Jul-24	<0.01	<0.001	0.002	0.05	<0.0001	<0.001	<0.001	<0.001	0.002	0.044	<0.0001	0.002	0.012	<0.01	<0.001*	0.009
MD02	Oct-24	<0.01	<0.001	<0.001	<0.05	<0.0001	<0.001	<0.001	<0.001	<0.001	0.044	<0.0001	0.001	0.011	<0.01	<0.001*	<0.005
MD02	Jan-25	<0.01	<0.001	<0.001	<0.05	No data	<0.001	<0.001	No data	<0.001	0.05	<0.0001	0.001	0.01	<0.01	<0.001*	0.006
SB01	Jan-24	<0.01	<0.001	<0.001	0.11	<0.0001	<0.001	0.003	<0.001	<0.001	0.39	<0.0001	<0.001	0.032	<0.01	<0.001*	<0.005
SB01	Apr-24	<0.01	<0.001	<0.001	0.05	<0.0001	<0.001	0.005	<0.001	<0.001	0.73	<0.0001	0.005	0.027	<0.01	<0.001*	<0.005
SB01	Jul-24	0.11	<0.001	0.004	0.08	<0.0001	0.004	0.024	<0.001	<0.001	1.65	<0.0001	<0.001	0.011	<0.01	<0.001*	0.01
SB01	Oct-24	<0.01	<0.001	<0.001	0.08	<0.0001	<0.001	<0.001	<0.001	<0.001	0.211	<0.0001	<0.001	0.002	<0.01	<0.001*	0.011



Bore ID	Date	Aluminium	Antimony	Arsenic	Boron	Cadmium	Chromium	Cobalt	Copper	Lead	Manganese	Mercury	Molybdenum	Nickel	Selenium	Silver	Zinc
SB01	Jan-25	<0.01	<0.001	<0.001	0.08	No data	<0.001	<0.001	No data	<0.001	0.153	<0.0001	<0.001	<0.001	<0.01	<0.001*	<0.005
SB02	Jan-24	<0.01	<0.001	0.003	0.21	<0.0001	0.003	0.002	<0.001	<0.001	0.735	<0.0001	0.003	0.012	<0.01	<0.001*	0.007
SB02	Apr-24	<0.01	<0.001	0.001	0.07	<0.0001	<0.001	0.003	<0.001	<0.001	0.315	<0.0001	0.002	0.014	<0.01	<0.001*	<0.005
SB02	Jul-24	<0.01	<0.001	0.004	0.14	<0.0001	<0.001	0.002	<0.001	<0.001	0.68	<0.0001	0.003	<0.001	<0.01	<0.001*	<0.005
SB02	Oct-24	<0.01	<0.001	0.004	0.14	<0.0001	<0.001	0.001	<0.001	<0.001	0.696	<0.0001	0.002	0.001	<0.01	<0.001*	<0.005
SB02	Jan-25	<0.01	<0.001	<0.001	0.14	No data	<0.001	0.002	No data	<0.001	0.692	<0.0001	0.002	0.001	<0.01	<0.001*	<0.005
SB04	Jan-24	<0.01	<0.001	<0.001	0.16	<0.0001	<0.001	<0.001	<0.001	<0.001	0.38	<0.0001	0.001	<0.001	<0.01	<0.001*	<0.005
SB04	Apr-24	<0.01	<0.001	<0.001	0.08	<0.0001	<0.001	<0.001	<0.001	<0.001	0.094	<0.0001	<0.001	<0.001	<0.01	<0.001*	<0.005
SB04	Jul-24	<0.01	<0.001	<0.001	0.09	<0.0001	<0.001	<0.001	<0.001	<0.001	0.076	<0.0001	<0.001	<0.001	<0.01	<0.001*	<0.005
SB04	Oct-24	<0.01	<0.001	<0.001	0.08	<0.0001	<0.001	<0.001	<0.001	<0.001	0.061	<0.0001	<0.001	<0.001	<0.01	<0.001*	<0.005
SB04	Jan-25	0.56	<0.001	<0.001	0.11	No data	0.001	<0.001	No data	0.001	0.307	<0.0001	<0.001	0.002	<0.01	<0.001*	0.056
SB05	Jan-24	<0.01	<0.001	0.004	0.21	<0.0001	<0.001	<0.001	<0.001	<0.001	0.233	<0.0001	0.004	0.002	<0.01	<0.001*	<0.005
SB05	Apr-24	<0.01	<0.001	0.004	0.13	<0.0001	<0.001	<0.001	<0.001	<0.001	0.405	<0.0001	0.005	0.002	<0.01	<0.001*	<0.005
SB05	Jul-24	<0.01	<0.001	0.008	0.15	<0.0001	<0.001	<0.001	<0.001	<0.001	0.516	<0.0001	0.003	<0.001	<0.01	<0.001*	<0.005
SB05	Oct-24	<0.01	<0.001	0.004	0.16	<0.0001	<0.001	<0.001	<0.001	<0.001	0.273	<0.0001	0.003	0.001	<0.01	<0.001*	<0.005
SB05	Jan-25	<0.01	<0.001	0.004	0.15	No data	<0.001	<0.001	No data	<0.001	0.703	<0.0001	0.002	<0.001	<0.01	<0.001*	<0.005
SB06	Jan-24	0.02	<0.001	0.003	0.19	<0.0001	<0.001	0.002	0.003	<0.001	1.18	<0.0001	0.002	0.002	<0.01	<0.001*	<0.005
SB06	Apr-24	<0.01	<0.001	0.003	0.12	<0.0001	<0.001	0.002	<0.001	<0.001	1.19	<0.0001	0.003	0.002	<0.01	<0.001*	<0.005
SB06	Jul-24	<0.01	<0.001	0.003	0.13	<0.0001	<0.001	0.001	<0.001	<0.001	0.771	<0.0001	0.002	<0.001	<0.01	<0.001*	0.006
SB06	Oct-24	0.01	<0.001	0.003	0.12	<0.0001	<0.001	0.002	<0.001	<0.001	0.493	<0.0001	0.003	0.003	<0.01	<0.001*	<0.005
SB06	Jan-25	<0.01	<0.001	0.002	0.13	No data	<0.001	<0.001	No data	<0.001	0.285	<0.0001	0.002	<0.001	<0.01	<0.001*	<0.005
SB07	Jan-24	<0.01	<0.001	<0.001	0.05	<0.0001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.0001	<0.001	0.07	<0.01	<0.001*	<0.005
SB07	Apr-24	<0.01	<0.001	<0.001	<0.05	<0.0001	<0.001	<0.001	0.001	<0.001	<0.001	<0.0001	<0.001	<0.001	<0.01	<0.001*	<0.005
SB07	Jul-24	<0.01	<0.001	0.001	0.08	0.0001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.0001	<0.001	0.001	<0.01	<0.001*	0.009



Bore ID	Date	Aluminium	Antimony	Arsenic	Boron	Cadmium	Chromium	Cobalt	Copper	Lead	Manganese	Mercury	Molybdenum	Nickel	Selenium	Silver	Zinc
SB07	Oct-24	<0.01	<0.001	<0.001	0.06	<0.0001	<0.001	<0.001	0.004	<0.001	<0.001	<0.0001	<0.001	<0.001	<0.01	<0.001*	<0.005
SB07	Jan-25	<0.01	<0.001	<0.001	0.06	No data	0.001	<0.001	No data	<0.001	0.002	<0.0001	<0.001	<0.001	<0.01	<0.001*	<0.005
SB08	Jan-24	<0.01	<0.001	<0.001	0.1	<0.0001	<0.001	<0.001	0.004	<0.001	0.002	<0.0001	<0.001	0.063	<0.01	<0.001*	<0.005
SB08	Apr-24	<0.01	<0.001	<0.001	0.05	<0.0001	<0.001	<0.001	0.011	<0.001	0.001	<0.0001	<0.001	<0.001	<0.01	<0.001*	<0.005
SB08	Jul-24	<0.01	<0.001	0.001	0.09	<0.0001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.0001	<0.001	<0.001	<0.01	<0.001*	<0.005
SB08	Oct-24	<0.01	<0.001	<0.001	0.06	<0.0001	<0.001	<0.001	<0.001	<0.001	0.002	<0.0001	<0.001	<0.001	<0.01	<0.001*	<0.005
SB08	Jan-25	<0.01	<0.001	<0.001	0.06	No data	<0.001	<0.001	No data	<0.001	0.007	<0.0001	<0.001	<0.001	<0.01	<0.001*	<0.005
SB09	Jan-24	<0.01	<0.001	<0.001	0.11	<0.0001	<0.001	<0.001	<0.001	<0.001	0.335	<0.0001	0.001	0.015	<0.01	<0.001*	<0.005
SB09	Apr-24	<0.01	<0.001	<0.001	<0.05	<0.0001	<0.001	<0.001	<0.001	<0.001	0.306	<0.0001	<0.001	<0.001	<0.01	<0.001*	0.013
SB09	Jul-24	<0.01	<0.001	<0.001	0.08	<0.0001	<0.001	<0.001	<0.001	<0.001	0.466	<0.0001	0.001	<0.001	<0.01	<0.001*	<0.005
SB09	Oct-24	<0.01	<0.001	<0.001	0.07	<0.0001	<0.001	<0.001	<0.001	<0.001	0.443	<0.0001	<0.001	0.001	<0.01	<0.001*	<0.005
SB09	Jan-25	<0.01	<0.001	<0.001	0.07	No data	<0.001	<0.001	No data	<0.001	0.615	<0.0001	<0.001	<0.001	<0.01	<0.001*	0.013
SB10	Jan-24	<0.01	<0.001	0.001	0.16	<0.0001	<0.001	<0.001	<0.001	<0.001	0.074	<0.0001	0.002	<0.001	<0.01	<0.001*	<0.005
SB10	Apr-24	<0.01	<0.001	0.001	0.08	<0.0001	<0.001	<0.001	<0.001	<0.001	0.146	<0.0001	0.002	<0.001	<0.01	<0.001*	<0.005
SB10	Jul-24	<0.01	<0.001	0.001	0.1	<0.0001	<0.001	<0.001	<0.001	<0.001	0.024	<0.0001	0.001	<0.001	<0.01	<0.001*	<0.005
SB10	Oct-24	<0.01	<0.001	0.001	0.11	<0.0001	<0.001	<0.001	<0.001	<0.001	0.104	<0.0001	<0.001	<0.001	<0.01	<0.001*	<0.005
SB10	Jan-25	<0.01	<0.001	<0.001	0.1	No data	<0.001	<0.001	No data	<0.001	0.011	<0.0001	<0.001	<0.001	<0.01	<0.001*	<0.005
SB11	Jan-24	<0.01	<0.001	<0.001	0.13	<0.0001	<0.001	<0.001	0.01	<0.001	0.023	<0.0001	<0.001	0.057	<0.01	<0.001*	<0.005
SB11	Apr-24	<0.01	<0.001	<0.001	0.05	<0.0001	<0.001	<0.001	0.021	<0.001	0.006	<0.0001	<0.001	0.002	<0.01	<0.001*	<0.005
SB11	Jul-24	<0.01	<0.001	<0.001	0.08	<0.0001	<0.001	<0.001	0.003	<0.001	0.01	<0.0001	<0.001	<0.001	<0.01	<0.001*	<0.005
SB11	Oct-24	<0.01	<0.001	<0.001	0.08	<0.0001	<0.001	<0.001	0.001	<0.001	0.004	<0.0001	<0.001	<0.001	<0.01	<0.001*	<0.005
SB11	Jan-25	<0.01	<0.001	<0.001	0.08	No data	<0.001	<0.001	No data	<0.001	0.142	<0.0001	<0.001	<0.001	<0.01	<0.001*	<0.005
SB15	Jan-24	<0.01	<0.001	<0.001	0.12	<0.0001	<0.001	<0.001	0.001	<0.001	0.008	<0.0001	<0.001	0.032	<0.01	<0.001*	<0.005
SB15	Apr-24	<0.01	<0.001	<0.001	0.05	<0.0001	<0.001	<0.001	<0.001	<0.001	0.004	<0.0001	<0.001	<0.001	<0.01	<0.001*	0.018



Bore ID	Date	Aluminium	Antimony	Arsenic	Boron	Cadmium	Chromium	Cobalt	Copper	Lead	Manganese	Mercury	Molybdenum	Nickel	Selenium	Silver	Zinc
SB15	Jul-24	<0.01	<0.001	<0.001	0.07	<0.0001	<0.001	<0.001	<0.001	<0.001	0.02	<0.0001	<0.001	<0.001	<0.01	<0.001*	<0.005
SB15	Oct-24	<0.01	<0.001	<0.001	0.06	<0.0001	<0.001	<0.001	0.008	<0.001	0.001	<0.0001	<0.001	<0.001	<0.01	<0.001*	<0.005
SB15	Jan-25	<0.01	<0.001	<0.001	0.06	No data	<0.001	<0.001	No data	<0.001	0.002	<0.0001	<0.001	<0.001	<0.01	<0.001*	<0.005
TR18	Jan-24	<0.01	<0.001	<0.001	0.11	<0.0001	<0.001	<0.001	0.07	<0.001	0.042	<0.0001	0.001	0.021	<0.01	<0.001*	<0.005
TR18	Apr-24	<0.01	<0.001	<0.001	0.05	<0.0001	<0.001	<0.001	0.032	<0.001	0.023	<0.0001	0.002	0.020	<0.01	<0.001*	0.009
TR18	Jul-24	<0.01	<0.001	<0.001	0.08	0.0001	<0.001	<0.001	0.033	<0.001	0.094	<0.0001	0.002	0.019	<0.01	<0.001*	0.008
TR18	Oct-24	<0.01	<0.001	<0.001	0.07	<0.0001	<0.001	<0.001	0.101	<0.001	0.043	<0.0001	0.001	0.013	<0.01	<0.001*	<0.005
TR18	Jan-25	0.03	<0.001	<0.001	0.07	No data	<0.001	<0.001	No data	<0.001	0.032	<0.0001	<0.001	0.011	<0.01	<0.001*	<0.005
TR26	Jan-24	<0.01	<0.001	<0.001	0.14	<0.0001	<0.001	<0.001	0.01	<0.001	0.07	<0.0001	0.002	0.014	<0.01	<0.001*	<0.005
TR26	Apr-24	<0.01	<0.001	<0.001	0.07	<0.0001	0.002	<0.001	<0.001	<0.001	0.033	<0.0001	0.005	0.017	<0.01	<0.001*	0.012
TR26	Jul-24	<0.01	<0.001	<0.001	0.11	0.0001	<0.001	<0.001	<0.001	<0.001	0.053	<0.0001	0.002	0.004	<0.01	<0.001*	0.007
TR26	Oct-24	<0.01	<0.001	<0.001	0.1	<0.0001	<0.001	<0.001	<0.001	<0.001	0.106	<0.0001	0.001	0.004	<0.01	<0.001*	<0.005
TR26	Jan-25	<0.01	<0.001	<0.001	0.09	No data	<0.001	<0.001	No data	<0.001	0.105	<0.0001	<0.001	0.006	<0.01	<0.001*	<0.005
TR35	Jan-24	<0.01	<0.001	<0.001	0.12	0.0002	0.002	0.007	1.24	<0.001	1.72	<0.0001	0.011	0.713	<0.01	<0.001*	0.015
TR35	Apr-24	<0.01	<0.001	<0.001	0.06	0.0004	0.002	0.010	1.730	<0.001	1.76	<0.0001	0.017	0.558	<0.01	<0.001*	0.030
TR35	Jul-24	<0.01	<0.001	0.001	0.08	0.0003	<0.001	0.011	7.09	<0.001	1.51	<0.0001	0.009	0.435	<0.01	<0.001*	0.02
TR35	Oct-24	<0.01	<0.001	<0.001	0.09	0.0004	<0.001	0.01	8.23	<0.001	1.44	<0.0001	0.01	0.308	<0.01	<0.001*	0.017
TR35	Jan-25	<0.01	<0.001	<0.001	0.07	No data	<0.001	0.008	No data	<0.001	0.907	<0.0001	0.002	0.111	<0.01	<0.001*	0.009
TR7	Jan-24	<0.01	<0.001	<0.001	0.1	<0.0001	<0.001	0.008	0.863	<0.001	0.637	<0.0001	0.002	0.39	<0.01	<0.001*	0.006
TR7	Apr-24	<0.01	<0.001	<0.001	<0.05	<0.0001	<0.001	0.004	0.346	<0.001	0.262	<0.0001	0.002	0.118	<0.01	<0.001*	0.006
TR7	Jul-24	<0.01	<0.001	<0.001	0.07	0.0001	<0.001	0.008	0.471	<0.001	0.526	<0.0001	0.003	0.272	<0.01	<0.001*	0.01
TR7	Oct-24	<0.01	<0.001	<0.001	0.07	0.0001	<0.001	0.004	1.59	<0.001	0.278	<0.0001	0.002	0.045	<0.01	<0.001*	<0.005
TR7	Jan-25	<0.01	<0.001	<0.001	0.07	No data	<0.001	0.005	No data	<0.001	0.381	<0.0001	<0.001	0.024	<0.01	<0.001*	0.006
VKY0034 C	Jan-25	<0.01	<0.001	0.001	0.19	No data	<0.001	<0.001	No data	<0.001	0.008	<0.0001	0.003	0.003	<0.01	<0.001*	0.014



Bore ID	Date	Aluminium	Antimony	Arsenic	Boron	Cadmium	Chromium	Cobalt	Copper	Lead	Manganese	Mercury	Molybdenum	Nickel	Selenium	Silver	Zinc
VKY0035C	Jan-25	<0.01	<0.001	0.001	<0.05	No data	0.001	<0.001	No data	<0.001	0.308	<0.0001	0.006	0.006	<0.01	<0.001*	<0.005
VKY0036C	Jan-25	<0.01	<0.001	0.006	0.09	No data	<0.001	<0.001	No data	<0.001	0.151	<0.0001	0.002	0.004	<0.01	<0.001*	<0.005
VKY0042C	Jan-25	<0.01	<0.001	<0.001	0.06	No data	<0.001	<0.001	No data	<0.001	0.22	<0.0001	<0.001	0.003	<0.01	<0.001*	0.015
VKY0043C	Jan-25	<0.01	<0.001	<0.001	0.06	No data	<0.001	<0.001	No data	<0.001	0.005	<0.0001	<0.001	0.001	<0.01	<0.001*	<0.005
VKY034C	Jan-24	<0.01	<0.001	0.002	0.09	<0.0001	<0.001	<0.001	<0.001	<0.001	0.102	<0.0001	0.007	0.008	<0.01	<0.001*	<0.005
VKY034C	Apr-24	<0.01	<0.001	<0.001	0.08	<0.0001	<0.001	<0.001	0.001	<0.001	0.224	<0.0001	<0.001	0.004	<0.01	<0.001*	0.012
VKY034C	Jul-24	<0.01	<0.001	0.001	0.08	<0.0001	<0.001	<0.001	0.001	<0.001	0.003	<0.0001	<0.001	0.001	<0.01	<0.001*	0.005
VKY034C	Oct-24	<0.01	0.002	0.001	0.06	<0.0001	<0.001	<0.001	<0.001	<0.001	<0.001	<0.0001	0.005	0.006	<0.01	<0.001*	0.023
VKY035C	Jan-24	<0.01	<0.001	0.001	0.07	<0.0001	0.002	<0.001	<0.001	<0.001	0.329	<0.0001	0.007	0.006	<0.01	<0.001*	0.006
VKY035C	Apr-24	<0.01	<0.001	<0.001	0.08	<0.0001	<0.001	<0.001	0.001	<0.001	0.224	<0.0001	<0.001	0.004	<0.01	<0.001*	0.012
VKY035C	Jul-24	<0.01	<0.001	0.002	<0.05	<0.0001	0.002	<0.001	<0.001	0.001	0.32	<0.0001	0.008	0.005	<0.01	<0.001*	0.008
VKY035C	Oct-24	<0.01	<0.001	<0.001	<0.05	<0.0001	0.002	<0.001	<0.001	<0.001	0.32	<0.0001	0.007	0.003	<0.01	<0.001*	<0.005
VKY036C	Jan-24	<0.01	<0.001	<0.001	0.09	<0.0001	<0.001	<0.001	<0.001	<0.001	0.013	<0.0001	0.001	0.013	<0.01	<0.001*	<0.005
VKY036C	Apr-24	<0.01	<0.001	<0.001	0.08	<0.0001	<0.001	<0.001	0.001	<0.001	0.224	<0.0001	<0.001	0.004	<0.01	<0.001*	0.012
VKY036C	Jul-24	<0.01	<0.001	0.008	0.1	<0.0001	<0.001	<0.001	<0.001	<0.001	0.153	<0.0001	0.004	0.005	<0.01	<0.001*	<0.005
VKY036C	Oct-24	<0.01	<0.001	0.007	0.09	<0.0001	<0.001	<0.001	<0.001	<0.001	0.157	<0.0001	0.003	0.004	<0.01	<0.001*	<0.005
VKY042C	Jan-24	<0.01	<0.001	<0.001	0.1	0.0001	<0.001	<0.001	0.006	<0.001	0.223	<0.0001	0.002	0.015	<0.01	<0.001*	0.014
VKY042C	Apr-24	<0.01	<0.001	<0.001	0.08	<0.0001	<0.001	<0.001	0.001	<0.001	0.224	<0.0001	<0.001	0.004	<0.01	<0.001*	0.012
VKY042C	Jul-24	<0.01	0.002	<0.001	0.07	0.001	<0.001	0.004	0.008	<0.001	0.217	<0.0001	0.001	0.038	<0.01	<0.001*	0.033
VKY042C	Oct-24	<0.01	<0.001	<0.001	0.06	<0.0001	<0.001	<0.001	0.001	<0.001	0.213	<0.0001	<0.001	0.003	<0.01	<0.001*	<0.005
VKY043C	Jan-24	<0.01	<0.001	<0.001	0.11	<0.0001	<0.001	<0.001	<0.001	<0.001	0.005	<0.0001	<0.001	<0.001	<0.01	<0.001*	<0.005
VKY043C	Apr-24	<0.01	<0.001	<0.001	0.06	<0.0001	<0.001	<0.001	<0.001	<0.001	0.004	<0.0001	<0.001	0.002	<0.01	<0.001*	0.006
VKY043C	Jul-24	<0.01	<0.001	<0.001	0.1	<0.0001	<0.001	<0.001	0.002	<0.001	<0.001	<0.0001	<0.001	<0.001	<0.01	<0.001*	<0.005
VKY043C	Oct-24	<0.01	<0.001	<0.001	0.07	<0.0001	<0.001	<0.001	0.002	<0.001	0.004	<0.0001	<0.001	<0.001	<0.01	<0.001*	0.006



Bore ID	Date	Aluminium	Antimony	Arsenic	Boron	Cadmium	Chromium	Cobalt	Copper	Lead	Manganese	Mercury	Molybdenum	Nickel	Selenium	Silver	Zinc
VNW223	Oct-24	<0.01	0.001	<0.001	0.07	<0.0001	<0.001	<0.001	0.011	<0.001	0.013	<0.0001	<0.001	0.003	<0.01	<0.001*	0.023
VNW223	Jan-25	<0.01	<0.001	<0.001	0.08	No data	<0.001	<0.001	No data	<0.001	0.007	<0.0001	<0.001	0.002	<0.01	<0.001*	0.027
VNW390	Jan-24	<0.01	<0.001	<0.001	0.14	<0.0001	<0.001	<0.001	0.005	<0.001	0.003	<0.0001	<0.001	0.002	<0.01	<0.001*	0.026
VNW390	Apr-24	<0.01	<0.001	0.002	0.09	<0.0001	<0.001	0.002	<0.001	<0.001	0.239	<0.0001	<0.001	0.002	<0.01	<0.001*	0.007
VNW390	Jul-24	<0.01	<0.001	0.002	0.12	0.0001	<0.001	0.003	<0.001	<0.001	0.298	<0.0001	0.005	0.036	<0.01	<0.001*	<0.005
VNW390	Oct-24	<0.01	<0.001	0.003	0.12	<0.0001	<0.001	0.002	<0.001	<0.001	0.321	<0.0001	0.002	0.016	<0.01	<0.001*	0.008
VNW390	Jan-25	<0.01	<0.001	0.001	0.11	No data	<0.001	0.002	No data	<0.001	0.227	<0.0001	0.003	0.024	<0.01	<0.001*	0.005
VNW391	Jan-24	<0.01	<0.001	<0.001	0.13	<0.0001	<0.001	<0.001	0.001	<0.001	0.006	<0.0001	<0.001	<0.001	<0.01	<0.001*	0.006
VNW391	Apr-24	<0.01	<0.001	<0.001	0.08	<0.0001	<0.001	<0.001	0.001	<0.001	0.225	<0.0001	0.001	0.007	<0.01	<0.001*	0.013
VNW391	Jul-24	<0.01	0.002	<0.001	0.11	0.0003	<0.001	<0.001	<0.001	0.002	0.246	<0.0001	<0.001	0.006	<0.01	<0.001*	0.018
VNW391	Oct-24	<0.01	<0.001	<0.001	0.1	<0.0001	<0.001	<0.001	<0.001	<0.001	0.266	<0.0001	<0.001	0.004	<0.01	<0.001*	<0.005
VNW391	Jan-25	<0.01	<0.001	<0.001	0.1	No data	<0.001	<0.001	No data	<0.001	0.233	<0.0001	<0.001	0.004	<0.01	<0.001*	0.019
VNW392	Jan-24	<0.01	<0.001	0.001	0.12	<0.0001	<0.001	0.003	<0.001	<0.001	0.333	<0.0001	0.002	0.02	<0.01	<0.001*	0.008
VNW392	Apr-24	<0.01	<0.001	0.001	0.07	<0.0001	<0.001	0.003	<0.001	<0.001	0.315	<0.0001	0.002	0.014	<0.01	<0.001*	<0.005
VNW392	Jul-24	<0.01	<0.001	0.002	0.1	<0.0001	<0.001	0.003	<0.001	<0.001	0.286	<0.0001	0.002	0.01	<0.01	<0.001*	0.007
VNW392	Oct-24	<0.01	<0.001	<0.001	0.09	<0.0001	<0.001	0.003	<0.001	<0.001	0.275	<0.0001	0.002	0.008	<0.01	<0.001*	<0.005
VNW392	Jan-25	<0.01	<0.001	<0.001	0.09	No data	<0.001	0.002	No data	<0.001	0.22	<0.0001	0.004	0.026	<0.01	<0.001*	0.009
VNW393	Jan-24	<0.01	<0.001	<0.001	0.1	<0.0001	<0.001	<0.001	<0.001	<0.001	0.092	<0.0001	0.003	<0.001	<0.01	<0.001*	<0.005
VNW393	Apr-24	<0.01	<0.001	<0.001	0.05	<0.0001	<0.001	<0.001	<0.001	<0.001	0.15	<0.0001	0.005	0.005	<0.01	<0.001*	<0.005
VNW393	Jul-24	<0.01	<0.001	0.001	0.09	0.0001	<0.001	<0.001	<0.001	<0.001	0.181	<0.0001	0.004	0.006	<0.01	<0.001*	0.005
VNW393	Oct-24	<0.01	<0.001	<0.001	0.08	<0.0001	<0.001	<0.001	<0.001	<0.001	0.193	<0.0001	0.005	0.01	<0.01	<0.001*	<0.005
VNW393	Jan-25	0.01	<0.001	<0.001	0.08	No data	<0.001	<0.001	No data	<0.001	0.176	<0.0001	0.005	0.013	<0.01	<0.001*	<0.005
VNW394	Jan-24	<0.01	<0.001	0.007	0.1	<0.0001	<0.001	0.011	<0.001	<0.001	2.12	<0.0001	0.003	0.035	<0.01	<0.001*	0.007
VNW394	Apr-24	<0.01	<0.001	0.006	<0.05	<0.0001	<0.001	0.002	<0.001	<0.001	1.27	<0.0001	0.003	0.006	<0.01	<0.001*	<0.005




Bore ID	Date	Aluminium	Antimony	Arsenic	Boron	Cadmium	Chromium	Cobalt	Copper	Lead	Manganese	Mercury	Molybdenum	Nickel	Selenium	Silver	Zinc
VNW394	Jul-24	<0.01	<0.001	0.005	0.07	<0.0001	<0.001	0.002	<0.001	<0.001	0.982	<0.0001	0.002	0.007	<0.01	<0.001*	0.013
VNW394	Oct-24	0.02	<0.001	0.005	0.07	<0.0001	<0.001	0.002	0.001	<0.001	0.332	<0.0001	0.002	0.014	<0.01	<0.001*	0.007
VNW394	Jan-25	<0.01	<0.001	0.004	0.06	No data	<0.001	0.002	No data	<0.001	0.283	<0.0001	0.001	0.006	<0.01	<0.001*	0.005
VNW395	Jan-24	<0.01	<0.001	0.001	0.08	<0.0001	<0.001	<0.001	0.002	<0.001	0.032	<0.0001	<0.001	0.001	<0.01	<0.001*	<0.005
VNW395	Apr-24	<0.01	<0.001	0.001	0.0575	<0.0001	<0.001	0.00125	0.00625	<0.001	0.125	<0.0001	0.00575	0.2285	<0.01	<0.001*	0.007
VNW395	Jul-24	<0.01	<0.001	0.001	0.06	<0.0001	<0.001	0.001	0.007	0.002	0.071	<0.0001	0.008	0.371	<0.01	<0.001*	0.016
VNW395	Oct-24	<0.01	0.001	<0.001	0.06	<0.0001	<0.001	<0.001	0.009	<0.001	0.006	<0.0001	0.004	0.347	<0.01	<0.001*	0.012
VNW395	Jan-25	<0.01	<0.001	<0.001	0.05	No data	<0.001	<0.001	No data	<0.001	0.056	<0.0001	0.001	0.14	<0.01	<0.001*	<0.005
WR1	Apr-24	<0.01	<0.001	<0.001	0.08	<0.0001	<0.001	<0.001	0.001	<0.001	0.224	<0.0001	<0.001	0.004	<0.01	<0.001*	0.012
WR1	Jul-24	<0.01	<0.001	0.001	0.15	0.0003	<0.001	<0.001	0.001	0.002	0.122	0.0017	0.002	0.037	<0.01	<0.001*	0.014
WR1	Oct-24	<0.01	<0.001	0.002	0.16	0.0002	<0.001	<0.001	0.005	<0.001	0.065	0.0046	0.002	0.024	<0.01	0.001	0.007
WR1	Jan-25	<0.01	<0.001	<0.001	0.17	No data	<0.001	<0.001	No data	<0.001	0.08	0.0003	<0.001	0.024	<0.01	<0.001*	0.007
WR2	Apr-24	<0.01	<0.001	<0.001	0.08	<0.0001	<0.001	<0.001	0.001	<0.001	0.224	<0.0001	<0.001	0.004	<0.01	<0.001*	0.012
WR2	Jul-24	<0.01	<0.001	<0.001	0.09	0.0001	<0.001	0.008	<0.001	<0.001	0.724	<0.0001	0.022	0.118	<0.01	<0.001*	<0.005
WR2	Oct-24	<0.01	<0.001	0.001	0.11	<0.0001	0.001	0.018	<0.001	<0.001	1.73	<0.0001	0.008	0.087	<0.01	<0.001*	0.009
WR2	Jan-25	<0.01	<0.001	<0.001	0.12	No data	0.001	0.014	No data	<0.001	1.12	<0.0001	0.02	0.158	<0.01	<0.001*	0.011

*Limit of reporting value is higher than DGV value. Red text shows exceedance of ANZECC Default Guideline Values. Highlighted cell shows trigger level 1 as defined by TARP in the GWMP (Appendix A).

In the January 2025 monitoring round, the bore (or location) Landreef Tap was reported and included in this table. However, this bore is not listed in Table 4-1 and Table 4-2 of the management plan (Whitehaven, 2023).

In the January 2025 monitoring round, bore GW97164 was reported but is considered to be a typo in the Chain of Custody (Appendix C). Therefore, it has been reported as GW971614.





Making Sustainability Happen